
WILLOW RIDGE COMMUNITY ASSOCIATION

5 DP2026-01145

2026.08.12 DTR 2 RESPONSE



DRAWING INDEX

Sheet Number	Sheet Name
L0.00	COVER SHEET + DRAWING INDEX
L0.01	LANDSCAPE NOTES AND SCHEDULES
L0.02	TREE PROTECTION PLAN
L1.00	REMOVAL PLAN
L2.00	LANDSCAPE PLAN
L2.01	PARKING PLAN - PART 1
L2.02	PARKING PLAN - PART 2
L2.03	PARKING PLAN-PART 3
L2.04	PARKING PLAN-PART 4
L5.00	SITE SECTIONS & ELEVATIONS
L6.00	SITE DETAILS -HARDSCAPE
L6.01	SITE DETAILS - SOFTSCAPE
A1	GRADING PLAN 5
FIG.1	FINAL PARKING LAYOUT

DIALOG

ISSUED FOR

2	2026.03.30	ISSUED FOR TENDER
4	2026.06.25	DTR 1 RESPONSE
5	2026.08.12	DTR 2 RESPONSE

AMENDED DRAWINGS
DP No Date Received
DP2026-01145 AUG 12 2026
THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

METRIC

THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

DIALOG
300 - 134 11th AVENUE SE
CALGARY, AB, CANADA T2G 0X5
Tel: 403.245.5501

Tel: Fax:

Tel: Fax:

Tel: Fax:

Tel: Fax:

Tel: Fax:

KEYPLAN

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED TO DALOG BY THE CONSTRUCTOR AND OTHERS SHOWING SIGNIFICANT CHANGES IN THE WORK MADE DURING CONSTRUCTION. BECAUSE RECORD DOCUMENTS ARE PREPARED USING UNVERIFIED INFORMATION PROVIDED BY OTHERS, DALOG MAKES NO WARRANTY OF THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED, IS UNDER NO OBLIGATION OR DUTY TO VERIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND HAS NOT DONE SO. DIALOG IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY THE CONSTRUCTOR.

WILLOW RIDGE COMMUNITY ASSOCIATION

680 Acadia Drive S.E.
Calgary, AB, T2J 0C1

COVER SHEET + DRAWING INDEX

DRAWN: SJ CHECKED: FS/BM
PLOT DATE: 8/12/2026 11:49:21 AM

L0.00

AB100604 - 2007874

BYLAW REQUIREMENTS

City of Calgary - Zone S-SPR	Total Area Within Property Line = 33,500 s.m. Total Construction Area = 5,400 s.m.
Setback Requirement	1.2 Trees for every 70.0 square meters for the use of School Authority - School 1.2 Trees for every 70.0 square meters for any use contained within building previously used for School Authority - School 1.0 Trees and 2.0 Shrubs for every 45.0 square metres for all other uses

Total Trees and Shrubs Required / Proposed

	Required	Proposed
Total Trees	15	21
Total Shrubs	30	43

GENERAL NOTES

- THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.
- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED. VERIFY DIMENSIONS. DO NOT SCALE DRAWINGS.
- REVIEW SITE CONDITIONS, VERIFY THE LOCATIONS AND DEPTHS OF ALL UTILITIES, AND CONFIRM UTILITY SETBACK REQUIREMENTS. REPORT INCONSISTENCIES, OMISSIONS, AND CONFLICTS TO THE LANDSCAPE ARCHITECT FOR CLARIFICATION PRIOR TO COMMENCEMENT OF WORK.
- IF EXCAVATIONS ARE REQUIRED CLOSER THAN 1.0M TO UNDERGROUND UTILITIES, HAND DIGGING UNDER THE SUPERVISION OF AFFECTED UTILITIES IS REQUIRED. NOTIFY THE APPROPRIATE UTILITY TO APPROVE, REVIEW, AND/OR DEFINE SAFE PROCEDURES FOR THESE EXCAVATIONS.
- WORK SHALL BE MAINTAINED WITHIN THE PROPERTY LINE AND/OR CONSTRUCTION LIMITS. THE CONTRACTOR IS RESPONSIBLE TO CORRECT ANY INTRUSION OR DAMAGE TO ADJACENT PROPERTY – INCLUDING BUILDINGS, PAVEMENTS, BENCHMARKS, AND ALL OTHER SITE APPURTENANCES; CORRECTION SHALL BE AT THE CONTRACTOR'S EXPENSE.
- DEVIATIONS FROM THE CONSTRUCTION DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE LANDSCAPE ARCHITECT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.
- AS THIS PROJECT IS CITY OF CALGARY CONSTRUCTION MANAGEMENT CONTRACT, THE ONLY TERMS TO BE USED ARE 'CONSTRUCTION MANAGER' OR 'TRADE CONTRACTOR'.
- CONSTRUCTION ACCESS AND LAYDOWN AREAS SHALL NOT INTRUDE ON ADJACENT SCHOOL SITE OR PUBLIC BOULEVARD.

TREE PROTECTION AND EXCAVATION NOTES

- EXTREME CAUTION IS REQUIRED WHEN EXCAVATING NEAR EXISTING TREES.
- TREE PROTECTION MEASURES: PROTECTIVE FENCING MUST BE INSTALLED AT THE DRIPLINE OF ALL EXISTING TREES PRIOR TO CONSTRUCTION AND MUST REMAIN IN PLACE FOR THE DURATION OF THE WORK. NO GRADING, TRENCHING, OR COMPACTION WITHIN THE FENCE AREA.

DEMOLITION NOTES

OVERALL REQUIREMENTS

- REVIEW SITE CONDITIONS AND NOTIFY THE OWNER OF ANY DISCREPANCIES WITH DEMOLITION PLAN AND QUESTIONS PRIOR TO COMMENCEMENT OF WORK.
- COORDINATE WITH OWNER TO PROVIDE PEDESTRIAN DETOUR ACCESS THROUGHOUT DEMOLITION.
- THE CONSTRUCTION MANAGER SHALL SECURE ALL PERMITS THAT MAY BE REQUIRED FROM ALL JURISDICTIONS AFFECTED BY THIS WORK.

EXISTING CONDITIONS

- FOR EXISTING UTILITIES AND GRADES, REFER TO CIVIL

PROTECTION

- REFER TO CIVIL FOR FIRE HYDRANTS TO REMAIN AND FIRE HYDRANTS TO BE RELOCATED. REMAINING FIRE HYDRANTS MUST BE ACCESSIBLE FOR USE THROUGHOUT ENTIRE DURATION OF CONSTRUCTION PROJECT, INCLUDING FIRE ACCESS.
- ALL EXISTING SITE ELEMENTS - INCLUDING BUT NOT LIMITED TO UTILITIES, STRUCTURES, FOUNDATION, SURFACES, FEATURES + FURNISHINGS, AND PLANT MATERIALS (ABOVE AND BELOW GROUND) - TO REMAIN ARE TO BE PROTECTED IN PLACE. DAMAGE TO EXISTING SITE ELEMENTS AND BUILDINGS TO BE CORRECTED TO THE SATISFACTION OF THE OWNER AT THE SOLE EXPENSE OF THE CONTRACTOR.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL DESIGNATED EXISTING TREES AND SHRUBS TO MEET THE CITY OF CALGARY BYLAW 23M2002 AND 'TREE PROTECTION PLAN' GUIDE FOR DURATION OF CONSTRUCTION. ALL TREE PROTECTION MEASURED TO BE REVIEWED AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO COMMENCEMENT OF WORK.
- EXISTING PLANTS TO REMAIN SHALL NOT BE USED FOR CRANE STAYS, GUYS OR OTHER FASTENINGS. VEHICLES SHALL NOT BE PARKED OR PARKED TEMPORARILY STANDING IDLE WITHIN THE DRIP LINE OR WHERE DAMAGE MAY RESULT TO TREES TO BE SAVED. CONSTRUCTION MATERIALS SHALL NOT BE STORED BENEATH TREES TO BE SAVED.

SALVAGE

- ALL ELEMENTS MARKED FOR SALVAGE TO BE COORDINATED WITH OWNER.

DEMOLITION + DISPOSAL

- ALL REFUSE, DEBRIS AND MISCELLANEOUS ITEMS TO BE REMOVED, THAT ARE NOT TO BE STOCKPILED FOR LATER USE ON THE PROJECT OR DELIVERED TO THE OWNER SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR FOLLOWING CITY OF CALGARY WASTE DIVERSION REQUIREMENTS REFERENCED IN THE CITY'S STANDARD GENERAL CONDITIONS.
- ALL ITEMS REQUIRING REMOVAL SHALL BE REMOVED TO THE FULL DEPTH TO INCLUDE BASE MATERIAL AND FOOTINGS OR FOUNDATIONS AS APPLICABLE, AND REUSED AS DIRECTED BY THE OWNER OR DISPOSED OF OFF-SITE BY CONTRACTOR FOLLOWING CITY OF CALGARY WASTE DIVERSION REQUIREMENTS REFERENCED IN THE CITY'S STANDARD GENERAL CONDITIONS.
- AT ALL LOCATIONS WHERE CONCRETE PAVEMENT OR BITUMINOUS CONCRETE ROADWAY ABUT NEW CONSTRUCTION, THE EDGE OF THE EXISTING CURB OR PAVEMENT SHALL BE SAWCUT TO A CLEAN, SMOOTH EDGE.
- BACKFILL AS NECESSARY, IN COORDINATION WITH DESIGN GRADES. BACKFILL MATERIAL TO BE 80mm GRANULAR SUB-BASE AS PER STANDARD SPECIFICATIONS: ROAD CONSTRUCTION 203.02.02 COMPACTED TO 98%. SEPARATE BACKFILL FROM EXISTING MATERIAL USING GEOTEXTILE BARRIER.
- COORDINATE BACKFILL WITH PROPOSED SITE DEVELOPMENT REQUIREMENTS AND TESTING REQUIREMENTS.

LAYOUT NOTES

- IF DISCREPANCIES EXIST BETWEEN DRAWINGS, THE LARGEST SCALE SHALL BE TAKEN AS CORRECT; REPORT DISCREPANCIES TO LANDSCAPE ARCHITECT FOR CLARIFICATION PRIOR TO COMMENCEMENT OF WORK.
- LAYOUT SHALL BE APPROVED ON SITE BY THE LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION | INSTALLATION. CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT A MINIMUM OF TWO (2) WORKING DAYS PRIOR TO COMMENCEMENT OF WORK.
- LAYOUT APPROVAL INCLUDES, BUT IS NOT LIMITED TO, THE FOLLOWING CRITICAL SITE ELEMENTS: FEATURE ELEMENT LOCATION AND ALIGNMENT, ALL FORMWORK, UNIT PAVING POINTS-OF-BEGINNING AND ADJUSTMENT ZONES, FLATWORK JOINTS, WALLS, WATER FEATURES.
- CONTRACTOR TO COORDINATE AND ATTEND ALL INSPECTIONS.

PLANTING NOTES

- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALBERTA ONE CALL (1-800-242-3447) PRIOR TO CONSTRUCTION TO LOCATE AND STAKE ALL UNDERGROUND UTILITIES
- THE CONTRACTOR SHALL STAKE TREE AND SHRUB BED LOCATIONS AND PROPOSE MODIFICATIONS TO MAINTAIN SETBACKS FROM UNDERGROUND UTILITIES. SETBACKS ARE AS FOLLOWS, UNLESS MORE SIGNIFICANT SETBACKS ARE REQUIRED BY AFFECTED UTILITIES:

STORM + SANITARY LINES	1.5 m
FIRE HYDRANTS	3.0 m
WATER MAINS	1.5 m
STREET LIGHTS / POWER HARDWARE	3.5 m
POWER, TELEPHONE, CABLE	1.0 m
TELEPHONE PEDESTALS	1.5 m
GAS LINES	1.2 m

- PRIOR TO CONSTRUCTION, THE CONSULTANT WILL INSPECT TREE AND SHRUB LOCATIONS AS STAKED BY THE CONTRACTOR.
- TREE AND SHRUB LOCATIONS CLOSER THAN THE MINIMUM UTILITY SETBACKS MAY BE EXCAVATED BY HAND OR HYDROVAC WITH THE APPROVAL OF THE AFFECTED UTILITY. THE AFFECTED UTILITY MUST BE PRESENT DURING THE EXCAVATION.
- METAL TREE STAKES SHALL NOT BE PLACED WITHIN ONE (1) METER OF AN UNDERGROUND POWERLINE.
- THE CONTRACTOR IS RESPONSIBLE TO MAKE GOOD ANY DAMAGES TO BUILDINGS, SIDEWALKS, PAVEMENTS, BENCHMARKS AND ALL OTHER SITE APPURTENANCES AT HIS OWN COST.
- RESTORE ALL DISTURBED AREAS WITH SOD ON 150 mm TOPSOIL.
- ALL LANDSCAPE CONSTRUCTION SHALL BE IN ACCORDANCE WITH CITY OF CALGARY PARKS AND OPEN SPACES DEVELOPMENT GUIDELINES AND STANDARD SPECIFICATIONS: LANDSCAPE CONSTRUCTION, CURRENT EDITION AND CANADIAN LANDSCAPE STANDARD.
- ALL TREES WILL BE BALL AND BURLAP
- IF EXCAVATIONS ARE REQUIRED CLOSER THAN 1.0m TO UNDERGROUND POWER, TELEPHONE AND GAS ALIGNMENTS; HAND DIGGING UNDER THE SUPERVISION OF THE AFFECTED UTILITY IS REQUIRED. THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT AND THE APPROPRIATE UTILITY TO APPROVE, REVIEW AND/OR DEFINE SAFE PROCEDURES FOR THESE EXCAVATIONS.
- CONTRACTOR RESPONSIBLE FOR ENSURING TREES ARE PLANTED AT REQUIRED SETBACK FROM UNDERGROUND UTILITIES.
- PRIOR TO INSTALLATION, ALL LOCAL NURSERY STOCK MAY BE INSPECTED TO ENSURE STOCK ACCEPTABILITY. CONTRACTOR TO COORDINATE THIS INSPECTION WITH THE LANDSCAPE ARCHITECT.
- ALL PLANT MATERIAL TO BE DISEASE FREE AND TRUE TO FORM. LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REJECT ANY PLANT MATERIAL THAT DOES NOT MEET THESE STANDARDS.
- PRIOR TO INSTALLATION OF PLANT MATERIALS, THE LANDSCAPE ARCHITECT WILL INSPECT THE STAKING OF ALL TREE AND SHRUB LOCATIONS HAVING REGARD FOR THE UTILITIES STAKED BY ALBERTA FIRST CALL.
- TOP SOIL TO BE ROCK PICKED AND CLEANED.
- LANDSCAPE SHALL BE COMPLETED BY THE END OF THE FIRST GROWING SEASON FOLLOWING THE DATE OF APPROVAL.
- CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF SITE UNTIL SUCH TIME AS FINAL ACCEPTANCE IS GRANTED BY THE CITY OF CALGARY (MIN. 2 YEAR PERIOD).
- CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING LANDSCAPING TO THE APPROVAL OF THE LANDSCAPE ARCHITECT. ALL EXISTING PLANT MATERIAL TO BE PROTECTED PER THE CITY OF CALGARY STANDARDS.
- ALL TREE STAKES TO BE METAL "T" BAR TYPE STAKES, PAINTED BLACK.
- TOP 300 mm OF ALL TREE STAKES TO BE PAINTED IN ACCORDANCE WITH THE CITY OF CALGARY ANNUAL COLOUR CODES.
- ALL TREE PITS TO BE 1200mm SOIL DEPTH.
- ALL SHRUB BEDS TO BE 600mm SOIL DEPTH.
- ALL NATURE'S TURF, FESCUE SOD, OR PERENNIAL BEDS TO BE 150mm SOIL DEPTH.
-
- ALL SOFT LANDSCAPE AREAS TO BE PROVIDED WITH AN AUTOMATIC IRRIGATION SYSTEM UTILIZING 'LOW-WATER' TECHNOLOGIES..



VIEW FROM WRCA BUILDING FACING EAST OVER THE AREA FOR PROPOSED UPGRADES



VIEW FACING SOUTH OVER THE AREA FOR PROPOSED UPGRADES



VIEW FACING SOUTH AT SOUTH PARKING LOT - NEW PARKING LINES PROPOSED



VIEW FACING NORTH OVER THE AREA FOR PROPOSED UPGRADES



VIEW FACING WEST OVER THE AREA FOR PROPOSED UPGRADES - NEW PARKING AND INTENSIVE PLANTING



VIEW FACING NORTH AT NORTH PARKING LOT - PROPOSED PARKING AREA AND INTENSIVE SCREEN PLANTING WITH STORMWATER CAPACITY

MATERIALS SCHEDULE

AREA	TYPE	DESCRIPTION
792 m²	ASPHALT PARKING LOT	125mm DEPTH ASPHALT PARKING LOT
541 m²	ASPHALT PATHWAY	75mm DEPTH PATHWAY PER CITY OF CALGARY DGSS
10 m²	CONCRETE PAVER HEADER	300 x 150 x 65mm BROADWAY PAVERS, SOLDIER COURSE PATTERN, IN COLOUR: NATURAL, AVAILABLE THROUGH BARKMAN CONCRETE
123 m²	CONCRETE PAVERS	300 x 150 x 65mm BROADWAY PAVERS, RUNNING BOND PATTERN, IN COLOUR: NATURAL, AVAILABLE THROUGH BARKMAN CONCRETE
14 m²	FLAGSTONE PATHWAY	RUNDLE FLAGSTONE PAVERS, (51mm) THICK IN COLOUR BLACK. AVAILABLE THROUGH THUNDERSTONE QUARRIES.
417 m²	NATIVE PLANTING	NATURESTURF MIXED GRASSLAND PLANTING AT 150mm DEPTH TOPSOIL
135 m²	POUR IN PLACE CONCRETE	125mm DEPTH POUR IN PLACE CONCRETE PER CITY OF CALGARY SPECIFICATIONS
66 m²	RUNDLE STONE	75mm DEPTH RUNDLE STONE AND SALVAGED GRAVEL SHALE FROM BASEBALL FIELD, W/ GEOTEXTILE AND TACKIFIER
94 m²	SHRUB PLANTING BED	600mm DEPTH SHRUB PLANTING BED
1753 m²	SOD PLANTING	SOD PLANTING, 300mm DEPTH TOPSOIL
73 m²	TREE PLANTING BED	1200mm DEPTH TREE PLANTING BED
44 m²	WASHED RIVER ROCK	50mm DEPTH 20mm WASHED RIVER ROCK

FENCING SCHEDULE

Length	Type	Description
25828	POST AND CABLE FENCE	800mm HEIGHT POST & CABLE FENCE PER CITY OF CALGARY SPECIFICATIONS
149582	TREE PROTECTION FENCING	TEMPORARY TREE PROTECTION FENCE PER CITY OF CALGARY STANDARDS

PLANTING SCHEDULE

ABBREVIATION	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	QTY	SPREAD
DECIDUOUS TREE						
AN	Acer negundo	Manitoba Maple	75mm CAL.	B&B	6	4.0 m
BP	Betula papyrifera	Paper Birch	50mm CAL.	B&B	6	4.0 m
PP	Prunus padus var commutata	Mayday	75mm CAL.	B&B	8	4.0 m
SHRUB						
Aa	Amelanchier alnifolia	Saskatoon Berry	5 gal.	CT	18	1.2 m
Cs	Cornus sericea subsp. sericea	Red-Osier dogwood	5 gal.	CT	9	1.5 m
Sr	Sambucus racemosa	Red elderberry	5 gal.	CT	10	1.5 m
Vo	Viburnum opulus var. americanum	American cranberrybush	5 gal.	CT	3	2.4 m

DIALOG

ISSUED FOR

2	2026.03.30	ISSUED FOR TENDER
4	2026.06.25	DTR 1 RESPONSE
5	2026.08.12	DTR 2 RESPONSE

AMENDED DRAWINGS
DP No: DP2026-01145
Date Received: AUG 12 2026
THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

METRIC
THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

DIALOG
300 - 134 11th AVENUE SE
CALGARY, AB, CANADA T2G 0X5
Tel: 403.245.5501

Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:

KEYPLAN

The Alberta Association of Landscape Architects
Bryce Miranda #406

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED TO DIALOG BY THE CONSTRUCTION AND OTHERS SHOWING SIGNIFICANT CHANGES IN THE WORK MADE DURING CONSTRUCTION. BECAUSE RECORD DOCUMENTS ARE PREPARED USING UNVERIFIED INFORMATION PROVIDED BY OTHERS, DIALOG MAKES NO WARRANTY OF THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED. IS UNDER NO OBLIGATION OR DUTY TO VERIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND HAS NOT DONE SO. DIALOG IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY THE CONSTRUCTOR.

WILLOW RIDGE COMMUNITY ASSOCIATION
680 Acadia Drive S.E.
Calgary, AB, T2J 0C1

LANDSCAPE NOTES AND SCHEDULES

DRAWN: SJ
CHECKED: FS/BM
PLOT DATE: 8/12/2026 11:49:22 AM

L0.01

AB100604 - 2007874



TRUE NORTH

1 / L0.02 TREE PROTECTION PLAN

SCALE: 1 : 300

LEGEND

- LEASE BOUNDARY / PROPERTY LINE
- SETBACK LINE
- 5 SCOPE OF WORK
- BUILDING FOOTPRINT
- EXISTING SOLID FENCE
- EXISTING WOODEN POST FENCE
- EXISTING CHAINLINK FENCE

EXISTING UTILITIES (REFER TO CIVIL)

- LIGHT POLE
- FIRE HYDRANT
- CATCH BASIN
- MANHOLE
- GAS — GAS LINE
- STM — STORM LINE
- SAN — SANITARY LINE
- SS — COMBINED STORM / SANITARY LINE
- WAT — WATER LINE
- O/H POW — O/H POWER LINE
- U/G POW — U/G POWER LINE
- CBL — BURRIED CABLE
- EXISTING ELECTRICAL JUNCTION BOX

TREE PROTECTION LEGEND

- EXISTING CONIFEROUS TREE TO BE PROTECTED
- EXISTING DECIDUOUS TREE TO BE PROTECTED
- EXISTING DECIDUOUS TREE OUTSIDE OF CONSTRUCTION LIMIT
- PROPOSED TREE PROTECTION FENCE

DIALOG

ISSUED FOR

2	2026.03.30	ISSUED FOR TENDER
4	2026.06.25	DTR 1 RESPONSE
5	2026.08.12	DTR 2 RESPONSE

AMENDED DRAWINGS
DP No: DP2026-01145
Date Received: AUG 12 2026
THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

METRIC

THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

DIALOG
300 - 134 11th AVENUE SE
CALGARY, AB, CANADA T2G 0X5
Tel: 403.245.5501

Tel: Fax:

Tel: Fax:

Tel: Fax:

Tel: Fax:

Tel: Fax:

KEYPLAN

The Alberta Association of Landscape Architects
Bryce Miranda #406

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED TO DIALOG BY THE CONSTRUCTOR AND OTHERS SHOWING SIGNIFICANT CHANGES IN THE WORK MADE DURING CONSTRUCTION. BECAUSE RECORD DOCUMENTS ARE PREPARED USING UNVERIFIED INFORMATION PROVIDED BY OTHERS, DIALOG MAKES NO WARRANTY OF THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED, IS UNDER NO OBLIGATION OR DUTY TO VERIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND HAS NOT DONE SO. DIALOG IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY THE CONSTRUCTOR.

WILLOW RIDGE COMMUNITY ASSOCIATION


680 Acadia Drive S.E.
Calgary, AB, T2J 0C1

TREE PROTECTION PLAN

DRAWN: SJ CHECKED: FS/BM
PLOT DATE: 8/12/2026 11:49:23 AM

L0.02

AB100604 - 2007874



1 L1.00 REMOVAL/DEMOLITION PLAN

SCALE: 1 : 300

REMOVAL/DEMOLITION SYMBOL LEGEND

- LEASE BOUNDARY / PROPERTY LINE
- SETBACK LINE
- SCOPE OF WORK
- BUILDING FOOTPRINT
- EXISTING SOLID FENCE
- EXISTING WOODEN POST FENCE
- EXISTING CHAINLINK FENCE
- SITE ELEMENTS MARKED FOR REMOVAL/DEMOLITION/EARTHWORK

EXISTING UTILITIES (REFER TO CIVIL)

- LIGHT POLE
- FIRE HYDRANT
- CATCH BASIN
- MANHOLE
- GAS — GAS LINE
- STM — STORM LINE
- SAN — SANITARY LINE
- SS — COMBINED STORM / SANITARY LINE
- WAT — WATER LINE
- O/H POW — O/H POWER LINE
- U/G POW — U/G POWER LINE
- CBL — BURRIED CABLE
- EXISTING ELECTRICAL JUNCTION BOX
- EXISTING ASPHALT SURFACE - ROAD AND PARKING

EXISTING PLANTING LEGEND

- EXISTING CONIFEROUS TREE TO BE RETAINED
- EXISTING DECIDUOUS TREES TO BE RETAINED

DIALOG

ISSUED FOR

2	2026.03.30	ISSUED FOR TENDER
4	2026.06.25	DTR 1 RESPONSE
5	2026.08.12	DTR 2 RESPONSE

AMENDED DRAWINGS
DP No: DP2026-01145
Date Received: AUG 12 2026
THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

METRIC

THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

DIALOG
300 - 134 11th AVENUE SE
CALGARY, AB, CANADA T2G 0X5
Tel: 403.245.5501

Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:

KEYPLAN

The Alberta Association of Landscape Architects
Bryce Miranda #406

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED TO DIALOG BY THE CONSTRUCTOR AND OTHERS SHOWING SIGNIFICANT CHANGES IN THE WORK MADE DURING CONSTRUCTION. BECAUSE RECORD DOCUMENTS ARE PREPARED USING UNVERIFIED INFORMATION PROVIDED BY OTHERS, DIALOG MAKES NO WARRANTY OF THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED, IS UNDER NO OBLIGATION OR DUTY TO VERIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND HAS NOT DONE SO. DIALOG IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY THE CONSTRUCTOR.

WILLOW RIDGE COMMUNITY ASSOCIATION


680 Acadia Drive S.E.
Calgary, AB, T2J 0C1

REMOVAL PLAN

DRAWN: SJ CHECKED: FS/BM
PLOT DATE: 8/12/2026 11:49:25 AM

L1.00

AB100604 - 2007874



TRUE NORTH

1 / L2.00 LANDSCAPE PLAN

SCALE: 1 : 300

SITE SYMBOL LEGEND

- LEASE BOUNDARY / PROPERTY LINE
- SETBACK LINE
- SCOPE OF WORK
- BUILDING FOOTPRINT
- EXISTING SOLID FENCE
- EXISTING WOODEN POST FENCE
- EXISTING CHAINLINK FENCE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- SETBACK AREA FOR BYLAW REQUIREMENT

EXISTING UTILITIES (REFER TO CIVIL)

- LIGHT POLE
- FIRE HYDRANT
- CATCH BASIN
- MANHOLE
- GAS — GAS LINE
- STM — STORM LINE
- SAN — SANITARY LINE
- WAT — WATER LINE
- O/H POW — O/H POWER LINE
- U/G POW — U/G POWER LINE
- CBL — BURRIED CABLE
- EXISTING ELECTRICAL JUNCTION BOX

LEGEND

- ASPHALT PARKING LOT
- ASPHALT PATHWAY
- CONCRETE PAVER HEADER
- CONCRETE PAVERS
- FLAGSTONE PATHWAY
- NATIVE PLANTING
- POUR IN PLACE CONCRETE
- RUNDLE STONE
- SHRUB PLANTING BED
- SOD PLANTING
- TREE PLANTING BED
- WASHED RIVER ROCK
- PROPOSED SOD
- PROPOSED TREE PROTECTION FENCE
- PROPOSED POST & CABLE FENCE
- EXISTING DOWNSPOUT
- PROPOSED FIXED BOLLARD
- EXISTING CROSS DRAINS IN SIDEWALK
- EXISTING SOD
- EXISTING SOD AREA TO BE PROTECTED
- EXISTING BIKE RACKS

EXISTING PLANTING LEGEND

- EXISTING CONIFEROUS TREE TO BE RETAINED
- EXISTING DECIDUOUS TREES TO BE RETAINED

DIALOG

ISSUED FOR

1	2026.03.20	ISSUED FOR DEVELOPMENT PERMIT
2	2026.03.30	ISSUED FOR TENDER
4	2026.06.25	DTR 1 RESPONSE
5	2026.08.12	DTR 2 RESPONSE

AMENDED DRAWINGS
DP No: DP2026-01145
Date Received: SEP 01 2026
THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

METRIC

THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

DIALOG
300 - 134 11th AVENUE SE
CALGARY, AB, CANADA T2G 0X5
Tel: 403.245.5501

Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:
Tel: Fax:

KEYPLAN

THESE RECORD DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED TO DIALOG BY THE CONSTRUCTOR AND OTHERS SHOWING SIGNIFICANT CHANGES IN THE WORK MADE DURING CONSTRUCTION. BECAUSE RECORD DOCUMENTS ARE PREPARED USING UNVERIFIED INFORMATION PROVIDED BY OTHERS, DIALOG MAKES NO WARRANTY OF THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED, IS UNDER NO OBLIGATION OR DUTY TO VERIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND HAS NOT DONE SO. DIALOG IS NOT RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY THE CONSTRUCTOR.

WILLOW RIDGE COMMUNITY ASSOCIATION


680 Acadia Drive S.E.
Calgary, AB, T2J 0C1


LANDSCAPE PLAN

DRAWN: SJ CHECKED: FS/BM
PLOT DATE: 9/1/2026 4:17:32 PM

L2.00

AB100604 - 2007874





TURNING TEMPLATE
SU9 - WASTE COLLECTION VEHICLE
(FRONT END LOADER)

AMENDED DRAWINGS

DP No	Date Received
DP2026-01145	AUG 26 2026

THESE DRAWINGS REFER TO THE ABOVE DEVELOPMENT PERMIT NO.

DEVELOPMENT PERMIT DECISION RENDERED ON THIS PLAN

LEGEND

- PROPOSED ASPHALT
- EXISTING ASPHALT
- NO PARKING ZONE
- EXISTING CONTOURS

SUMMARY

NORTH PARKING LOT:
REGULAR STALLS = 32
BARRIER-FREE STALLS = 2

SOUTH PARKING LOT:
REGULAR STALLS = 30
BARRIER-FREE STALLS = 2

TOTAL PROPOSED STALLS = 66

TOTAL APPROXIMATE
EXISTING STALLS = 44

1:750 0 15 30 m

ISL

PROJECT
WILLOW RIDGE COMMUNITY ASSOCIATION

FIGURE TITLE
NORTH AND SOUTH PARKING LOT PARKING LAYOUT DESIGN

FILE No.	SCALE	FIGURE No.
28901_Final Parking Layout.dwg	1:750	1

ISC: SHEET SIZE ANSI B 20 mm 0

FILE: C:\ADSKACCDOCS\ISL\28901_WRCA_CIVIL_SUPPORTPROJECT FILES\23_SHEETS\28901_FINAL PARKING LAYOUT.DWG | DATE: Wednesday, August 26, 2026 11:06:55 AM