



KEY NOTES

1. HANDICAP STALL (SEE GENERAL NOTE 7)
2. PARKING STALLS. GC TO ENSURE PARKING STALL SIZES MEET THE MUNICIPAL REQUIREMENTS AFTER THE INSTALLATION OF PARKING POSTS. ADJUST PARKING STALL LINE PAINTING AS REQUIRED TO SUIT
3. MAIN ENTRY / EXIT / BACK DOOR.
4. EXISTING BOLLARD TO BE REMOVED BY GC.
5. EXISTING LANDSCAPE AREA, NOT PART OF SCOPE
6. NEW DEEP MOUNT BOLLARD (TYPICAL). TO BE SUPPLIED & INSTALLED BY GC REFER TO DRAWING SP2 FOR DETAILS
7. EXISTING WHEEL STOPS TO BE RE-INSTALLED / MOVED 600mm FROM THE FRONT STALL
8. CROSSHAIR - DENOTES SETTING OUT LINE., ARROW - DENOTES LAYOUT DIRECTION OF SUCCEEDING BOLLARDS TYPICALLY SPACED @ 4'-6" UNLESS OTHERWISE NOTED
9. ACCESSIBLE WHEELCHAIR RAMP
10. HANDICAP STALL - AS PER NBC A-3.8.3.23(1) "PERMIT REQUIRED" SIGN
11. ACCESS AISLE LINES TO BE PAINTED WHITE - AS PER NBC A-3.8.3.23.(1)

KEYNOTES ARE APPLICABLE TO THE PROGRAM AND ARE ONLY APPLICABLE TO THIS SITE IF PRESENT

LEGEND

- DEMO
- EXISTING
- EXISTING PARKING STALL (FADED - NOT VISIBLE)
- NEW
- REMOVED
- RELOCATED



KEY PLAN

SITE INFORMATION

LEGAL DESCRIPTION

LOT 1, BLOCK 1, PLAN 971 1779 WITHIN
THE SW 1/4 SEC 22 TWP 25 RGE 1 W5M

MUNICIPAL ADDRESS

150 96AVE NE
CALGARY AB T2Z 4J1

ZONING

XX

AREAS:

TOTAL SITE AREA = 6078.68m² (1.502acres) (0.607ha.)
TOTAL BUILDING AREA AREA: = 375.37m²
TOTAL CONCRETE APRON: = 524.36m²
TOTAL ASPHALT AREA = 3261.71m²

BUILDING AREAS:

C-STORE : =93.34m²

PARKING STALL AFFECTED:

	SIZE:	COUNT:
REGULAR :	VARIES X 5340	= 3 STALL
BARRIER FREE:	VARIES x 5340 W/1620 AISLE	= 2 STALL
TOTAL PARKING :		= 5 STALLS

GENERAL NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS U.N.O.
2. DO NOT SCALE DRAWING.
3. ALL SITE DIMENSIONS ARE SUBJECT TO VERIFICATIONS
4. BOLLARDS ARE TO BE PLACED IN ALL PARKING STALLS ADJACENT TO BUILDING. IF ANY PART OF A STALL IS ADJACENT TO THE BUILDING BUT NOT THE ENTIRE WIDTH, EXTEND BOLLARDS TO COVER ENTIRE STALL. AS SHOWN ON THIS PLAN
5. GC TO ENSURE BARRIER-FREE ACCESS IS NOT RESTRICTED AND A MINIMUM OF 1100mm AISLE MUST BE PROVIDED AND MAINTAINED.
6. ANY DIGGING OR ANYTHING IN THE GROUND WOULD HAVE TO HAVE AN BC ONE CALL SYSTEM AND HAVE THE UNDERGROUND UTILITIES MARKED.

SCOPE OF WORK

SCOPE OF WORK IS LIMITED TO ADDITION OF BOLLARDS TO SITE ONLY. NO OTHER CHANGES TO EXISTING SITE PLAN OR CONFIGURATION OF SITE

MATTERPORT LINK

https://my.matterport.com/show/?m=qapntcYbGDc

1 NEW PARKING BOLLARD PLAN
SCALE 1:200



2 ELEVATION 1
N.T.S



3 ELEVATION 2
N.T.S

Rev. #	Date	Description
	07/17/2026	ISSUED FOR CLIENT REVIEW
	08/26/2026	ISSUED FOR CLIENT REVIEW

7-ELEVEN, INC.
3200 HACKBERRY RD. IRVING TX 75063

7-11 #32741
150 - 96 AVENUE NE.
CALGARY, ALBERTA

PARKING BOLLARD PLAN AND DETAILS

ctm Design Services Ltd
210, 3A5 Midpark Way SE, Calgary, Alberta, T2X 1P1
TEL: 403.640.0990 • Fax 403.259.6556 • www.ctmdesign.ca

Job#:	2026021
Scale:	NTS
Date:	2026-06-17
Drawn By:	KJ
Checked By:	TW

Documents prepared by CTM Design Services are to be used only for the specific project and specific use for which they are intended. Use of documents on other projects, by owner or any other party, without the expressed, written consent of CTM Design Services is prohibited and unlawful. Use in a way other than that specifically intended, user will hold CTM Design Services harmless from all claims and losses.

PERMITTING DRAWINGS
PERMIT SUBMISSION

SHEET:
SP1