



Kollaard Associates

Engineers

210 Prescott Street, Unit 1
P.O. Box 189
Kemptville, Ontario K0G 1J0

Civil • Geotechnical •
Structural • Environmental •
Hydrogeology •

(613) 860-0923

FAX: (613) 258-0475

REPORT ON

**HYDROGEOLOGICAL INVESTIGATION
AND TERRAIN EVALUATION
PROPOSED RESIDENTIAL SUBDIVISION
3200 REIDS LANE
OSGOODE WARD, CITY OF OTTAWA
ONTARIO**

FILE # 210064

Submitted to:

Crestview Innovations Inc.
12 Escade Drive
Nepean, ON
K2G 6R9

REVISION 3 March 17, 2025

DISTRIBUTION

1 digital copy Crestview Innovations Inc.



**Professional Engineers
Ontario**

Authorized by the Association of Professional Engineers
of Ontario to offer professional engineering services.



TABLE OF CONTENTS

TABLE OF CONTENTS	ii
1.0 INTRODUCTION.....	1
1.1 PRE-CONSULTATION PROCESS	2
2.0 FIELD PROCEDURES	2
2.1 TERRAIN EVALUATION	2
2.2 GROUNDWATER SUPPLY INVESTIGATION	4
3.0 TERRAIN EVALUATION.....	5
3.1 SOIL AND GROUNDWATER CONDITIONS	5
3.1.1 Shallow Groundwater Sampling	8
3.1.2 Discussion of Elevated Nitrates in the Receiving Aquifer	10
3.1.3 Land and Water Use Conflicts	11
3.2 CLASS IV SEWAGE DISPOSAL SYSTEMS	16
3.2.1 Sewage System Envelopes	16
3.2.2 Leaching Bed Design Considerations	18
3.3 GROUNDWATER IMPACT ASSESSMENT.....	18
3.3.1 Criteria	18
3.3.2 Site Conditions Evaluation.....	19
3.3.3 Step 3 Assessment.....	21
4.0 GROUNDWATER SUPPLY INVESTIGATION.....	24
4.1 SUPPLY AQUIFER.....	24
4.2 WATER QUALITY	25
4.3 WATER QUALITY IN NEIGHBOURING WELLS.....	28
4.3 WATER QUANTITY	32
4.3.1 Test Well TW1	33
4.3.2 Test Well TW2	33
4.3.3 Test Well TW3	34
4.3.4 Interference Effects	34
4.4 GROUNDWATER FLOW DIRECTIONS	36
4.4.1 RECEIVING AQUIFER.....	37
4.4.2 BEDROCK WATER SUPPLY AQUIFER	37
4.5 DEVELOPMENT IMPACTS AND NEIGHBOURING LAND USES.....	38
4.5.1 Impact to Surface Water Quality and Quantity	39
4.6 WELL CONSTRUCTION METHODOLOGY	39
4.7 POST DEVELOPMENT MONITORING PROGRAM	40
5.0 SUMMARY AND CONCLUSIONS	41
6.0 RECOMMENDATIONS.....	48



TABLE OF CONTENTS continued

RECORDS OF BOREHOLES BH1 - BH11

TABLE I	– Field Water Quality Measurements for Test Wells
TABLE II	– Summary of Water Chemistry for Test Wells and Sampled Wells
TABLE III	– Heavy Metals Testing of Test Wells
TABLE IV	– Summary of Pumping Test Results and Well Parameters
TABLE V	– Mutual Well Interference Assessment at a Central Well
TABLE VI	– Well Interference Assessment at Property Boundary
TABLE VII	– Measured Drawdown in Observation Wells during Pumping Tests
TABLE VIII	– Storativity Estimate using Observation Well Data
TABLE IX	– Summary of Background Nitrogen Testing
TABLE X	– Groundwater Elevations in Receiving and Water Supply Aquifers
FIGURE 1	– Key Plan
FIGURE 2	– Site Plan
FIGURE 3	– Area Well Locations
FIGURE 4	– Cross Section East-West
FIGURE 5	– Cross Section North-South
FIGURES 6A&B	– Interpreted Groundwater Flow Directions
FIGURE 7	– Lot Development Plan
ATTACHMENT A	– Surficial and Bedrock Geology Maps
ATTACHMENT B	– MOE Water Well Records
ATTACHMENT C	– Grain Size Analyses of Soil Samples
ATTACHMENT D	– Results of Laboratory Nitrogen Species Testing of Receiving Aquifer Samples
ATTACHMENT E	– Septic Effluent Dilution Calculations
ATTACHMENT F	– Results of Laboratory Testing of Test Well Water Samples
ATTACHMENT G	– Result of Laboratory Testing of Existing Neighbouring Well Water Samples
ATTACHMENT H	– Pumping Test Data for Test Well TW1
ATTACHMENT I	– Pumping Test Data for Test Well TW2
ATTACHMENT J	– Pumping Test Data for Test Well TW3
ATTACHMENT K	– Observation Well Charts used for Storativity Estimates
ATTACHMENT L	– Lateral and Vertical Gradients in Receiving Aquifer



1.0 INTRODUCTION

Kollaard Associates Inc. was retained by Crestview Innovations Inc. of Ottawa, Ontario to undertake a hydrogeological investigation and terrain evaluation for a site located on Reids Lane. The site is located within Part of Lots 27 & 28, Concession 1, in Osgoode Ward, in the City of Ottawa, Ontario (See Key Plan, Figure 1).

The site consists of an area of 3.5 hectares (35,436 square metres) located on the north side of Osgoode Main Street within the village boundary of Osgoode Ward, Ottawa, Ontario. The site includes two parcels, one of which is the main parcel at 3200 Reids Lane (~33,681.56 m²) and the other being the Reids Lane parcel (~1754.63 m²). It is proposed to subdivide the site into some 7, average 0.40 hectare lots (minimum 0.4 hectare) for single family dwelling construction purposes. The proposed dwellings will be serviced by private septic systems and wells. The subject site consists mostly of open fields with scattered trees. There are no watercourses on the subject property.

The site is bordered on the west by the Osgoode Link Pathway (a former rail corridor), on the south and north sides by existing residential development and on the east by a municipally-owned woodlot. The existing dwellings to the north and south are serviced by private septic systems and wells.

Based on a review of the surficial geology map for the site area, it is expected that the site is underlain by coarse-textured glaciomarine deposits of sand, gravel, minor silt and clay, predominantly consisting of foreshore and basinal deposits. The bedrock geology map indicates that the bedrock underlying the site consists of dolostone and sandstone of the Beekmantown Group (Attachment A). The site and surrounding areas for at least 500 metres are within similar overburden stratigraphy and bedrock geology. There is no variability in the hydrogeological conditions in the study area and no faults, geological boundaries or significant changes to the overburden stratigraphy were identified within at least 500 metres of the subject site.



1.1 Pre-consultation Process

Hydrogeological Pre-consultation was carried out between Colleen Vermeersch of Kollaard Associates Inc. and Claire Milloy of Rideau Valley Conservation Authority who was to be the peer review agency on behalf of the City of Ottawa. This meeting was carried out by phone on March 8, 2021. This included background information being provided (by RVCA) from existing hydrogeological reports for adjacent subdivisions and discussion of background water wells sampling. At that time, the consultant asked the peer review authority regarding whether screened overburden wells on older residential dwellings near the site (driven point wells) were to be sampled as part of establishing the water quality for existing development. At that time, Claire Milloy indicated that only existing representative wells should be tested. The existing representative wells being in the same aquifer as the target aquifer for the proposed development. As such, the existing background wells that were sampled included only drilled, bedrock wells considered to be in the same aquifer as the future water supply.

An additional consultation and work plan were discussed with the peer review consultant (Mr. R. Chown of BluMetric) regarding the presence of nitrates in the receiving aquifer. The consultation occurred on October 12, 2023, and the work plan was accepted at that time.

2.0 FIELD PROCEDURES

The objectives of this study were:

- to determine the shallow subsurface soil and groundwater conditions relative to the design of Class IV septic sewage disposal systems
- to investigate the potential quantity and quality of groundwater available from drilled wells for domestic supply

2.1 Terrain Evaluation

The field work for the terrain evaluation was carried out on February 3 and 4, 2021, during which time a total of six boreholes (numbered BH1 to BH6, inclusive) were put down across the site. The



boreholes were advanced using a track mounted drill rig equipped with a 200 mm hollow stem auger owned and operated by CCC Drilling of Ottawa, Ontario. The approximate locations of the boreholes are provided in Site Plan, Figure 2.

The boreholes were put down throughout the site. The boreholes were advanced to depths of approximately 4.4 to 9.75 metres below the existing ground surface using 200 mm hollow stem augers. Borehole BH1 was continued to a depth of about 14.52 metres below the existing ground surface as a probe hole until bedrock was encountered. A member of our engineering staff recorded the soils types, depths to strata changes, and groundwater conditions at each borehole location. Groundwater conditions at the boreholes were noted at the time of drilling. Groundwater was also measured at a later date in standpipes installed within three of the boreholes at the time of drilling. The water levels in the standpipes were measured on February 12, 2021, and water samples were obtained from the standpipes for testing of background nitrogen levels. Surficial soil samples were obtained from Boreholes BH1, BH3 and BH5 for laboratory grain size distribution analysis. Two soil samples of underlying soils were also obtained from BH2 and BH4 and underwent hydrometer analysis. All particle analysis results are provided as Attachment C.

To obtain representative samples of the upper groundwater at the site for background testing of nitrogen species, three monitoring wells were installed using the *ASTM Standard D5092-04(2010) Standard Practice for Design and Installation of Groundwater Monitoring Wells*. The monitoring wells installed at BH1, BH3 and BH5 were tested for nitrogen species including nitrites, nitrates, Total Kjeldahl Nitrogen (TKN) and ammonia. Subsequent to the findings of the previous report (May 2023) and peer review comments, additional groundwater evaluation was carried out to characterize background nitrates at the site. On October 17, 2023, an additional five boreholes were constructed using a drill rig. The additional wells were constructed by augering to the desired well depths (generally 3 metres). The soils were characterized using split spoon sampling at 18" lifts, advancing 6" between lifts from 3 metres until silty clay was encountered. All of the additional boreholes were completed as monitoring wells with 5' screen. The Records of Borehole Logs are provided herein.

Monitoring Well Sampling Procedure

The sampling procedure was carried out using sampling protocols and methods described in "*Association of Professional Geoscientists of Ontario Guidance for Environmental Site Assessments under 153/04 (as amended), April 2011*". On February 12, 2021, the static water levels were



measured in each of the standpipes. The standpipes were subsequently purged of approximately three well volumes, and allowed to recover between purgings, prior to water samples being obtained and tested for nitrogen species, including nitrites, nitrates, TKN and ammonia. As no drilling fluids were used during borehole construction, the purging of three well volumes was considered to be sufficient to obtain groundwater samples that were representative of the groundwater in the shallow aquifer. The standing water in the monitoring well was purged using a mechanical displacement pump. The additional monitoring wells were developed on October 23, 2023. The wells were purged using a similar procedure.

2.2 Groundwater Supply Investigation

During the original investigation, to determine the quantity and quality of groundwater available for domestic water supply, three test wells, numbered TW1, TW2 and TW3, were pump tested and sampled. The approximate locations of the test wells are shown on the attached Site Plan, Figure 2. Air Rock Drilling Company Limited of Richmond, Ontario, drilled all three water supply wells on the subject property for the purpose of this hydrogeological investigation on April 26 and 27, 2021. To establish the existing water quality in the area, three offsite neighbouring wells were sampled for water quality. The existing wells that were sampled were considered to be representative of the well construction and aquifer for the future subdivision wells. As such, the existing wells were to be drilled bedrock wells and well records were obtained and matched to the sampled wells. In addition, a review of area well records surrounding the site was carried out. As the site is located in a village, there were a total of about 33 water supply wells identified within about 150 metres of the site. The locations of the test wells, neighbouring sampled wells and other area well records are provided herein as Well Locations, Figure 3. The well records for the wells and the Certificates of Compliance for the test wells are provided herein as Attachment B.

The water well records for the test wells supplied by the well driller indicate that nominal 15 centimetre inside diameter steel casings were installed through the overburden and were set well into the bedrock and grouted in place. The wells were drilled to final depths using a 15 centimetre diameter bit and completed as an open hole in the bedrock. TW1 and TW2 were drilled into the bedrock to final depths of some 76.2 and 74.4 metres, respectively, below the existing ground surface. TW3 was drilled to a depth of 30.5 metres. All three test wells were cased and grouted 3.0 metres into the bedrock with casing lengths of between 18.9 and 20.1 metres.



Pumping tests were conducted on TW1, TW2 and TW3 on May 12, May 10 and May 5, 2021, respectively. The testing consisted of 6 hour duration constant discharge rate pumping tests. During the pumping tests, water level measurements were made on a regular basis to monitor the drawdown of the water level in the wells in response to pumping. After the pumping period, the pump was shut off and the recovery of the water level in the test well was monitored for a period of time. During the pumping tests, water levels at adjacent test wells were monitored, using pressure transducers, to determine the potential interference effects between the wells.

Groundwater samples were collected from the test wells at about hour 3 and at hour 6 of the pumping tests to characterize groundwater quality. The groundwater samples from the test wells were collected and prepared/preserved in the field using appropriate techniques and submitted to Eurofins Environmental Laboratory in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the Ministry of the Environment (MOE) guideline entitled Procedure D-5-5, Technical Guideline for Private Wells: Water Supply Assessment, August 1996 in addition to select heavy metals. The temperature, pH, turbidity, sulphide and residual chlorine levels of the groundwater were measured at periodic intervals during the pumping tests. The equipment used for field testing consists of a Hanna Instrument turbidity and free chlorine meter (HI Model 93414), which is calibrated on a regular basis to ensure adequate performance.

Water samples were obtained from three wells servicing existing dwellings located in close proximity to the site at 5560 Lombardy and 5566 Lombardy Drive, located northeast of the site and 5529 Osgoode Main Street, located south of the site. The groundwater samples from the three wells were collected and prepared/preserved in the field using appropriate techniques and submitted to Eurofins Environmental Laboratory in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the Ministry of the Environment (MOE) guideline entitled "Technical Guideline for Water Supply Assessment for Subdivision Development on Individual Private Wells," dated July 1992.

3.0 TERRAIN EVALUATION

3.1 Soil and Groundwater Conditions

This section provides a summarized account of the subsurface soil and groundwater conditions on the subject property based on the information obtained at the borehole locations. Details of the subsurface conditions at the borehole locations are presented in the attached Record of Boreholes.



It is noted that in some cases the stratigraphic boundaries within the overburden represent a transition between soil types rather than an exact plane of geologic change. Subsurface conditions differing somewhat from those reported can be expected to exist at the site.

The six original borehole locations encountered either fill (consisting of topsoil, sand and gravel), or topsoil. Underlying the surficial organic and/or fill layers, the engineering staff identified the predominant surficial soil type at the site as fine to medium sand. Kollaard Associates Inc. (KAI) characterizes soil as fine to medium sand based on textural indicators for grain size. The sand layer was identified to be between 0.7 and 3.0 metres in thickness, where fully penetrated. The sand layer transitioned from red brown to grey at depths of 0.40 metres below ground surface at BH2 and BH3, and between 0.9 and 1.8 metres at the other borehole locations. BH1 was terminated in sand and continued to presumed bedrock as a probe hole. No soils information below 3.7 metres depth is available from that borehole. Large boulders and/or possible bedrock occur at or below 14.5 metres depth at that location. Below the sand deposit at the other five boreholes (BH2-BH6), a layer of grey sandy silty clay was encountered, of between 0.4 and 1.2 metres in thickness. A sand layer of between 0.7 and 1.4 metres in thickness was encountered below the silty sandy clay layer at BH2, BH3, BH4 and BH6. A deposit of grey silty clay was encountered at boreholes BH2, BH4 and BH6. The thickness of this silty clay layer was 2.6 to 3.3 metres at BH2 and BH6. BH4 was terminated within the silty clay layer at a depth of 9.7 metres below existing ground surface. BH2 and BH6 encountered glacial till below the silty clay layer and were terminated on practical refusal on bedrock at depths of 9.0 and 6.7 metres, respectively.

Additional soils information was obtained by BH7-BH11, which were constructed in order to install additional groundwater monitoring standpipes. At those boreholes, the soil conditions consisted of a sand deposit of about 4 to 6 metres in thickness overlying silty clay. These boreholes were terminated within silty clay at 4.4 to 8.2 metres depth.

Kollaard Associates Inc. (KAI) characterizes the receiving aquifer at the site as the red to grey fine to medium sand layer and upper portions of the sandy clay or sandy silty clay that was encountered below the sand at five of the borehole locations. The surficial soil is fine to medium sand based on textural indicators for grain size. Three representative samples were obtained from BH1, BH3 and BH5 from depths of 0.8 to 1.4 metres and submitted to a lab for grain size analyses.



The result of two hydrometer tests (ASTM D422 and D2216) on sample of subsurface silty sand soil (based on initial borehole descriptor) from BH4 at depth of ~5.0 metres indicates the sample consists of fine sand with some silt and trace clay.

The results of a hydrometer test (ASTM D422 and D2216) on a sample of subsurface glacial till soil from BH2 at 8.0 metres depth are reported in the Table below.

The results of the laboratory testing are located in Attachment C.

The hydraulic conductivity was estimated for the coarse grained samples using the particle size analyses, as follows.

$$k = 0.35 (D_{15})^2$$

Where k = hydraulic conductivity, in cm/s

D_{15} = the particle diameter where 15% of soil is passing, in mm

Sample	Description	Depth (m)	% Gravel	% Sand	% Silt & Clay	D_{15} (mm)	K (cm/s)
BH1-SS2	Fine to medium SAND	0.76 - 1.37m	0.0	96.5	3.5	0.26	2.4×10^{-2}
BH2-SS9	GLACIAL TILL (sandy silt, trace clay)	7.62 - 8.22m	17.7	32.1	45.2S 5.0C	NA	$\sim 1 \times 10^{-5}$
BH3-SS2	Fine to medium SAND	0.76 - 1.37m	0.0	94.9	5.1	0.27	2.5×10^{-2}
BH4-SS7	Fine to medium SAND	4.52 - 5.18m	0.0	85.9	10.1S 4.0C	0.08	2.2×10^{-3}
BH5-SS2	Fine to medium SAND	0.76 - 1.37m	0.0	96.7	3.3	0.29	2.9×10^{-2}

Based on the above noted information, the hydraulic conductivity of the fine to medium sand is expected to be $\sim 2.6 \times 10^{-2}$ cm/s. With depth (as in BH4), the percentage of fines increase and the deeper sand deposit has a hydraulic conductivity of 2×10^{-3} cm/s. The sand encountered at the site is considered to be a soil of medium permeability.



A sample of glacial till was also obtained (BH2-SS9). As this was a fine grained soil, the hydraulic conductivity was estimated using the hydrometer analysis and comparing it to the USGS Table 3 (supplemental Tables in the OBC). The sample is described by USGS as ML which includes inorganic silts and very fine sands. The coefficient of permeability was estimated based on the shape of the curve and the low percentage of clay to be about 1×10^{-5} cm/s and would be considered medium permeability of 20 to 35 min/cm. This corresponds to a sandy glacial till soil.

Groundwater monitoring wells were installed in three boreholes (BH1, BH3 and BH5) during the initial investigation. A total of 5 additional boreholes (BH7 – BH11) were completed with monitoring wells in October 2023. The attached Table X provides groundwater elevations in the Monitoring Wells. The interpreted groundwater flow directions in the receiving aquifer are provided on Figure 6a. This indicates shallow unconfined groundwater flow direction is to the northwest.

Water levels in the water supply wells at the site were recorded after the wells were constructed on May 5, 2021 and again on March 3, 2022, as follows.

Test Well	Top of Casing Elevations (masl)	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
			May 5, 2021	March 3, 2022
TW1	93.17	92.78	86.45	86.07
TW2	93.08	92.60	86.55	86.09
TW3	91.90	91.34	87.37	87.22

The interpreted groundwater flow direction in the deeper (bedrock) water supply aquifer is to the southeast, as shown on the attached Figure 6b.

3.1.1 Shallow Groundwater Sampling

During the initial investigation, a total of three (3) monitoring wells were installed in boreholes. Subsequent to the initial findings, where elevated nitrates were identified to be present at one of the monitoring wells, an additional five monitoring wells were installed on the site. The purpose of the shallow monitoring wells was to establish groundwater flow direction in the receiving aquifer at the site and to measure the existing nitrogen levels. The additional wells were to establish lateral and



vertical extent of nitrogen impacts that were present at BH1 (MW1) and to confirm the groundwater flow directions in the receiving aquifer.

All monitoring wells were constructed using the *ASTM Standard D5092-04(2010) Standard Practice for Design and Installation of Groundwater Monitoring Wells*. The testing includes nitrogen species nitrates, nitrites, Total Kjeldahl Nitrogen and ammonia. For details on construction and purging procedures see Section 2.1. For monitoring well locations, see Site Plan, Figure 2. The monitoring well construction logs are provided within the Record of Boreholes BH1-BH11 at the end of this document. Monitoring wells were installed in BH1, BH3, BH5, and BH7-BH11, inclusive.

The initial three shallow monitoring wells on the site were sampled on two occasions, February 12, 2021 and March 3 and 11, 2022. Due to the elevated nitrate levels at BH1 (MW1), repeated testing was carried out at that location on June 17, 2022 and February 9, 2023. The nitrate levels persisted in that location and did not decline over time. As such, a work plan was presented to the peer review consultant and additional monitoring wells BH7-BH11 were constructed to determine the lateral and vertical extent of nitrogen impact. The laboratory results are provided as Attachment D and a summary of background nitrogen levels is provided as Table IX.

The monitoring wells BH8, BH9, BH10 and BH11 were screened within the first soil stratigraphic unit identified at the site which is the fine to medium sand. The wells were screened over a 5 feet interval with tops of screens at depths of between 2.4 to 4.0 metres. These monitoring wells were installed to intercept the water table (receiving aquifer) and to capture the down gradient and cross gradient areas from BH1.

The monitoring well at BH7 was installed into the second stratigraphic unit identified at the site which was identified to be a silty clay deposit. It is located in close proximity to BH1 to determine whether the nitrogen impacts were present at depth. The monitoring well was sealed at the interface between the sand and clay in order to obtain a representative water sample from the second soil unit. This well was screened from about 6.6 to 8.1 metres within silty clay.



3.1.2 Discussion of Elevated Nitrates in the Receiving Aquifer

Lateral Migration of Nitrates Across Subject Property

The nitrate levels in the most up gradient monitoring well onsite (BH1) have fluctuated from about 5.8 mg/L to 19.3 mg/L in four sampling events from 2021 to 2023. All other monitoring wells (total of six in shallow receiving aquifer screened at about the same depth as BH1) have nitrate levels which are either below reporting limits (i.e. <0.10 mg/L) or less than 1 mg/L.

Groundwater flow directions and hydraulic gradients at the site are discussed (Section 4.4) and indicate that lateral groundwater flow at the site occurs at about 1.2 m/day. As the nitrates at BH1 have been elevated since at least 2021 and the travel time to other monitoring wells is between ~40 to ~90 days, there has been no change or increase in nitrates in the down gradient wells. As such, the nitrates in that location at BH1 are not spreading over time and are isolated to that location. It is possible that the elevated nitrates at BH1 are due to a former barn building in that area (based on aerial photographs and a previous Phase I ESA at the site).

Vertical Migration of Nitrates from Surficial Aquifer to Bedrock Water Supply Aquifer

A deeper standpipe (installed at BH7 and screened from ~6.7 to 8.2 metres) within the upper portion of the silty clay layer and in close proximity of BH1 had no nitrates detected at that depth. This indicates that the deeper overburden near BH1 is not impacted from the nitrates present within the shallow aquifer.

Based on the sampling of the onsite bedrock water supply wells, offsite bedrock wells and driven point wells that exist along Osgoode Main Street, there is no indication that nitrates are migrating vertically from the unconfined surficial aquifer to the deeper confined bedrock aquifer at or up gradient of the site.

The concentration of nitrates at the closest bedrock wells (5503 and 5529 Osgoode Main) to the driven point wells (3216 Reids Lane, 5535 Osgoode Main and 5519 Osgoode Main) indicates no detectible nitrates in the bedrock wells despite nitrate levels of 12 to 31 mg/L in the driven point wells. This indicates that there is no vertical migration of the surficial contaminants downward to the bedrock aquifer. Glacial till and silty clay soils underlie the surficial sand aquifer and are sufficiently thick to act as an aquitard. The bedrock wells are considered to be under confined aquifer



conditions based on the pumping tests carried out at the site. These soil conditions and the presence of the confining unit or aquitard between the aquifers, have demonstrated that the deeper bedrock water supply aquifer is protected from the presence of elevated nitrates in the surficial aquifer.

Based on the above noted information, it is considered that the bedrock water supply aquifer is protected from nitrate impact from the surficial aquifer at the site. This means that the future wells at the site are protected from the increased nitrates that may occur in the surficial aquifer under post development conditions. This has been established by evaluating the conditions on the up gradient lands which have been developed at a much higher density and yet have not affected the target water supply aquifer in the existing development.

3.1.3 Land and Water Use Conflicts

The following summarizes former uses of the subject property and the current and historical uses of properties within the site vicinity which have been evaluated in terms of the potential for groundwater contamination on the subject property.

Dillon Consulting completed a Phase I Environmental Site Assessment (ESA) in November 2016, with subsequent reports regarding debris removal, subsurface investigation, groundwater monitoring and decommissioning of monitoring wells. Based on a review of those reports, the following is noted.

- The Phase I ESA identified a former Imperial Oil fuel depot which was located offsite on an adjacent property near the southwest corner of the subject site. The offsite property was part of the former Canadian Pacific railway and the source for onsite minor soil and groundwater impacts in that portion of the site. Dillon reviewed Phase I and II ESA reports that were prepared by AMEC in 2001 and 2003 for an offsite property identified as 'Former Imperial Oil Facility, Main Street at CP Rail Right-of-Way, Osgoode, ON. Dillon indicates that ..."activities at the Imperial Oil site encroached upon the subject site".
- Fill materials and debris piles across the site represent on site potential sources of contamination.
- Former retail fuel outlets or service garages existed at 5514, 5491, 5543 and 5566 Osgoode Main Street. These are identified as up gradient to the subject property with potential for groundwater contamination (due to PHCs and/or VOCs).



- A soil and groundwater investigation was carried out November 2017 with a total of four soil samples plus one duplicate sample were collected and tested for metals, select VOCs, PAHs and PCBs. Some of the soil samples exceeded the standards for PAHs, lead and arsenic. A total of five groundwater monitoring wells were installed across the site. Those wells were screened in the upper overburden aquifer at depths of between about 0.9 to 5 metres. The overburden groundwater flow direction was estimated to be to the north. Water samples were tested for metals, select VOCs (BTEX), PHCs and PAHs. The only exceedance was vanadium at three locations, which were slightly above the allowable limits for potable water. The source of vanadium was considered to be the silty clay soils which are known to have naturally occurring elevated vanadium levels. The report concludes that the groundwater at the site was not impacted by debris and fill materials that caused soil impacts. The report recommended additional testing of groundwater to confirm the initial testing results.
- In July 2018, the five monitoring wells were retested and the only exceedances were vanadium, at the same three locations. A subsequent review by the MOECC agreed that there was no groundwater impacts from the debris and fill materials at the site and the wells could be abandoned. A subsequent monitoring well decommissioning was carried out and records of well abandonment were provided and registered with the MOECC.

Kollaard Associates Inc. carried out a Phase I Environmental Site Assessment for the site on October 19, 2022, in accordance with O. Reg. 153/04, which is the required standard for development approval. It was confirmed at that time, based on reviews of historical aerial photographs, chains of title for the two legal properties comprising the site, and site visits, that the only previous use of the subject property was for farming purposes. As such, there was no trigger for the property to require a Record of Site Condition. There were Potentially Contaminating Activities at the site, namely that illegal dumping had occurred on the subject property. The Phase I ESA findings are summarized below:

The results of the Phase I ESA indicate that there are two significant environmentally related issues identified at the subject site. The following APECs are identified to be present at the site based on one historical activity at the site and on one of the adjacent properties.

As such, Kollaard Associates considers that there are two APECs on the subject site as follows:



- APEC 1: Fill and/or Debris impacting soil: There were soil impacts noted (by Dillon previous investigations) at three locations of the subject property related to debris from illegal dumping which occurred between 1987 and 2000. Of a total of four soil samples, two samples had exceedances for PAHs, one had an exceedance for arsenic and one had an exceedance for lead. These soil samples were collected by Dillon Consulting in 2017.
- APEC 2: The former fuel depot impacted soil at the southwest corner of the site from Total Petroleum Hydrocarbons (as noted by AMEC, 2003). Updated soil testing is necessary for PHCs F1-F4 to determine if soil impacts remain at the site. Previous soil impacts were measured in one soil sample collected in 2003 by AMEC.
- No documentation has been provided to indicate whether any soil excavation had occurred subsequent to the previous soil investigations. Kollaard Associates Inc. proposes to update the soils testing to determine whether any soil impacts remain on site.
- A previous environmental investigation carried out by Dillon Consulting included groundwater sampling of a total of five monitoring wells that included two wells near the former fuel depot in the southwest corner of the site and three monitoring wells installed by Dillon Consulting near the former debris piles. In December 2017 and subsequently in July 2018, all the wells were tested for the following parameters; metals, Volatile Organic Compounds (VOCs), PHC F1-F4, semi-volatiles (PAHs). The concentrations of the above noted parameters were all within the Table 2 Standards (O. Reg. 153/04 Table 2 Standards 2011, for potable groundwater).
- The report concluded that based on the second round of groundwater testing (subsequent to the previous testing that occurred in December 2017) that groundwater was not impacted from the fill and debris that were encountered in the shallow soils at the property.
- Based on the above noted APECs, updated soil sampling for PHC F1-F4 at APEC 2 and PAHs and metals at APEC 1 is necessary to confirm whether there are soil impacts since the time of the previous investigations. Kollaard Associates Inc. considers that no further groundwater investigation is necessary, based on the review of the Dillon investigations, which included groundwater monitoring.

Kollaard Associates Inc. carried out a Phase 2 Environmental Site Assessment on January 24, 2023. The following summarizes the findings of that study:



- The field program for the Phase II ESA was carried out by putting down a total of eight (8) test pits to address two APECs. APEC 1 is identified in three areas where fill materials were previously identified to contain the following one or more of the following contaminants above allowable limits arsenic, lead (metals) and PAHs. APEC 2 is located in the southwest corner of the property adjacent to a former bulk fuel storage facility where previous soil contamination at that location consisted of Petroleum Hydrocarbon fractions F1 to F4 (PHCs). The soil analytical results were compared against Ontario Ministry of the Environment (MECP) "Soil, Groundwater and Sediment Standards for Use under Part XV.1 of the Environmental Protection Act, dated April 15, 2011, Table 2: Full Depth Generic Site Condition Standards in a Potable Ground Water Condition for Residential/Parkland/Institutional Use for coarse textured soils.
- Based on the results of the Phase II ESA the following summary and conclusions are provided:
- APEC 1: The fill materials present at the site are within allowable limits for PAHs and metals, with the exception of one sample. A total of twelve (12) samples of the fill materials within APEC 1 were obtained from a total of six test pits on November 7, 2022. These were tested for metals and PAHs. No presence of PAHs above method reporting limits was reported for a total of ten (10) samples. Two samples obtained from TP3 had the presence of PAHs, including one sample which had an exceedance of two PAHs identified as benzo(a)pyrene and dibenz(a,h)anthracene. That test pit (TP3) encountered some asphalt pieces mixed in with fill materials. A second visit was carried out and one additional soil sample was obtained from below the fill materials and in the native soils. There was no presence of PAHs or metals above method reporting limits in the deeper sample obtained within the same test pit. The exceedance encountered in one sample (TP3-2) is due to the presence of asphalt in the soil sample rather than representative of the fill materials/soils present at the site. It is considered that once the asphalt is removed from the site, the remaining soils can remain on site. It is recommended that the asphalt be removed from the site by separating it from the soils and disposing or recycling the asphalt accordingly. The fill materials that are considered to be soil have been characterized and are acceptable for reuse on the site, once sorting has occurred to separate the asphalt pieces. As such, it is considered that the appropriate reuse of fill materials can be addressed and managed through the Excess Soil Regulations and no further soil characterization is necessary.



- APEC 2: The soils adjacent to the former fuel storage property have a presence of PHCs F1-F4 and BTEX (gasoline compounds) within allowable limits. At APEC 2, two test pits were put down with a total of four soil samples obtained and tested for both PHC F1-F4 and select VOCs (benzene, toluene, ethylbenzene and xylene). There was a presence of PHC F3 and F4 within one sample (TP8-1). However, the levels encountered were within the allowable limits. A deeper sample obtained from the same test pit encountered no presence of any PHCs or BTEX compounds. A second test pit (TP7) encountered no presence of any PHCs or BTEX. As such, the soil impacts from the former fuel storage facility are within allowable limits. No further assessment or soil characterization is considered necessary.
- Due to the presence of solid waste encountered throughout the site, the following Phase II ESA recommendation is made. There is solid waste present at the site on the ground surface in various locations, which was not fully assessed due to the limitations of vegetation that has since obscured visual and physical access to the debris. Debris that was observed includes metals, concrete, wood, plastic bottles, tin, roofing shingles and other solid waste. The underlying soils and groundwater have been assessed and are not impacted by the solid waste present on the ground surface at the site. Any solid waste should be disposed of at an appropriately licensed landfill at the time of development.

The majority of former offsite sources of contamination, namely retail fuel outlets and automotive garages are no longer active, with the exceptions of 5543 Osgoode Main Street and 5566 Osgoode Main Street (Drummond's Gas Bar). These properties are sufficiently distant, between 40 and 140 metres to the east and southeast of the subject property, such that it is unlikely that there would be any impact on the subject site. The Drummond's gas station had all the previous tanks removed and has been updated with new tanks. Current gas stations are far less likely to cause impacts due to the use of double-walled insulated tanks which are usually constructed using fibreglass that does not degrade and leak, compared to the former use of steel tanks. It should also be noted that many of the existing water supply wells servicing dwellings on Osgoode Main Street are sand point wells. If there were issues with hydrocarbon impacts from nearby commercial development, those wells are much more likely to be impacted. Based on the review of the above noted reports and the current development near the site, there are no concerns with respect to the quality of groundwater supply at the site from the offsite land uses and the historical use of the site.



A review of Permit to Take Water Mapping for a 1 kilometre radius around the site indicates that there are no major water taking activities in the area. The area surrounding the site is mostly developed, with the exception of a vacant parcel to the east. The recent groundwater pumping tests at the site indicate that there is sufficient water supply at the site to support development. As such, there are no concerns with existing development impacting the quantity of water supply at the site.

3.2 Class IV Sewage Disposal Systems

This section discusses the implications of the site-specific terrain conditions in terms of the feasibility of installing Class IV sewage disposal systems within the proposed subdivision.

3.2.1 Sewage System Envelopes

The septic system envelope area (septic envelope) represents the area on a lot set aside for the construction of the leaching bed and is for the leaching bed only and does not include that area required for the septic tank or the isolation/separation distances required by the Ontario Building Code. The deposit or disposal of any materials or the placement of any structure or the operation of any equipment, other than material, structures or equipment required for the construction of the sewage system within or upon the septic envelope is prohibited.

The size of the septic envelopes are a function of the percolation time of the native soil in the vicinity of the septic envelope and/or the fill used for construction of a septic bed and the daily effluent loading to the septic bed. The native sandy soil at the site is of medium permeability, with an approximate percolation rate of 4 to 6 min/cm (based on Supplementary Guideline Table 2 Approximate Relationships of Soil Types to Permeability and Percolation rate in the Ontario Building Code). The groundwater table at the site is expected to be within 0.9 metres of the ground surface, based on shallow groundwater monitoring wells.

As a conservative approach to determining the expected largest septic system envelope required to service a single family dwelling at this site, a septic system envelope size was calculated assuming a partially raised bed using a percolation rate of 8 minutes per centimetre for the imported sand required and a daily sewage flow of 3000 litres. A design flow of 3000 litres per day is suitable for a



five bedroom dwelling with 250 square metres of finished area and 30 fixture units. The following formulae were used to calculate the size of the septic envelope:

The larger of

$$A = \frac{Q}{8} \quad \text{OR} \quad A = \frac{1.6QT}{200} \text{ plus}$$

4:1 Leaching Bed Side Slopes

Where Q = daily sewage flow for the proposed dwelling (i.e., 3,000 litres per day)
 T = percolation rate of imported fill material

The size of the septic envelopes, based on the conservative approach described above, is approximately 375 square metres. In view of the minimum proposed lot sizes of about 4055 square metres, and average lot sizes of about 4290 square metres, sufficient area exists at each of the proposed lots for the construction of a conventional septic system that meets the requirements of the Ontario Building Code.

Prior to establishing the actual septic envelope (leaching bed) location on any particular lot, several test holes should be excavated to determine the consistency/variability of the overburden in the vicinity of the proposed septic envelope and percolation rate tests should be carried out to determine the actual envelope area and whether imported mantles are required.

Other site-specific considerations with respect to the locations of the septic envelopes (leaching beds) on the proposed lots are as follows:

- assuming that shallow groundwater flow within the upper overburden is from topographically higher areas to topographically lower areas, the septic envelopes should be situated in the topographically lower areas with the wells on the topographically higher areas
- the separation distances between septic envelopes and properly constructed drilled and cased wells should be at least twice the grade raise plus 15 metres for partially to fully raised beds as required by the Ontario Building Code



3.2.2 Leaching Bed Design Considerations

The design of leaching beds is a combination of a number of interrelated factors including effluent discharge volume, properties of the soil materials in the leaching bed, length of distribution lines and the subsurface conditions. The construction of individual septic disposal systems on the proposed lots should be carried out in accordance with the specifications set out in the Ontario Building Code.

The design must ensure that the bottom of the absorption trenches is at least 0.9 metres above bedrock or soils that are unsuitable for treatment of septic effluent (those with excessively low permeability), and at least 0.9 metres above the seasonally high groundwater table.

Based on the soil and groundwater conditions at the site, partially raised septic system leaching beds are likely to be used. The actual leaching bed type appropriate for each lot will depend on the individual lot specific soil and groundwater conditions.

Any partially raised leaching beds should be constructed of imported sand having a percolation time of between 6 and 8 minutes per centimetre with less than 5 percent passing the #200 (0.074 mm) sieve. It is recommended that gradation analyses be carried out on any potential sand fill prior to leaching bed construction in order to verify that the percolation time of the fill material is acceptable.

3.3 Groundwater Impact Assessment

3.3.1 Criteria

The Ministry of the Environment (MOE) Procedure D-5-4 provides guidelines for evaluating "the ability of the lands identified by and restricted to the development document, to treat sewage effluent to meet acceptable limits". The guideline requires that the representative background nitrate levels in the receiving groundwater be determined. Where background levels are greater than 10 milligrams per litre the ministry indicates development of the site should not be supported unless it can be demonstrated that existing levels of nitrates are the results of historical agricultural practices on the site. In addition, the guideline requires demonstration that the site is not obviously hydrogeologically sensitive such as karstic areas, areas of fractured bedrock exposed at the surface, areas of thin soil cover or areas of highly permeable soils.



The guideline indicates that the assessment involves a three step process.

Step 1 regards lot size considerations. Where the lot size for each private residence within the development is an average of one hectare or larger and no lot is smaller than 0.8 hectares, and provided the site is not hydrogeologically sensitive, the risk that impact limits may be exceeded by individual systems is considered acceptable.

Step 2 is in regards to septic system isolation considerations. Developments are considered low risk when it can be demonstrated that sewage effluent is hydrogeologically isolated from existing or potential supply aquifers. For this case the most probable groundwater receiver for sewage is to be defined through information obtained through a test pit or test hole program, and the most probable lower hydraulic or physical boundary of the groundwater receiving sewage effluent is to be defined. The guideline indicates hydrogeologic information concerning lands up to 500 metres beyond the actual development boundary may be required. When it can be demonstrated that the sewage will not enter supply aquifers the lot density of the proposed development is determined based on the space required to install a suitable septic system at each lot in accordance with the Ontario Building Code.

Step 3 is in regards to contaminant attenuation considerations. For this case, it is required to assess the risk that the on-site sewage systems within the proposed development will cause a concentration of nitrate in groundwater above 10 milligrams per litre at the down gradient boundary of the site.

3.3.2 Site Conditions Evaluation

In order to evaluate the background water quality conditions in the receiving aquifer, three shallow monitoring wells were installed at the site and tested for nitrogen species. The construction details are provided in Section 2.1, the Records of Boreholes are appended to the report and groundwater levels are reported in Section 3.1. Background nitrogen concentrations from the shallow groundwater receiving effluent were reported (Section 3.1.1) and the original laboratory testing results are in Attachment D. The Site Plan, Figure 2, shows the locations of the monitoring wells.



The Ministry of the Environment, Conservation and Parks (MECP) Guideline D-5-4 indicates that:

“.....where nitrate concentrations between 0 and 10 mg/l are found, the MOECC may also decide not to support development if the proponent’s consultant cannot provide a reasonable explanation for the existing levels of nitrate concentrations in the groundwater. However, if it can be demonstrated that existing levels of nitrates are the result of historical agricultural practices on the site (for example farming, feed lot, etc.), the proponent may be able to argue that the nitrate levels will decline after development”

The background nitrate levels were generally less than reporting limits <0.10 mg/L N-NO₃ up to 0.72 mg/L N-NO₃), with the exception of the monitoring well, BH1, which had levels of ~6 to 20 mg/L N-NO₃. The location of BH1 is where there was a former large building (likely a barn) and may have been locally impacted by nitrogen or nitrogen. All of the down gradient monitoring wells (Table IX) indicate that nitrate levels are very low and have continued to be low from 2021 to the present time. The hydraulic gradients ~1.2 m/day would indicate that if the nitrate levels were spreading laterally, there would be impact in the down gradient wells over time. As the levels did not show an increase, the nitrates impacts are considered to be isolated.

The site is not obviously hydrogeologically sensitive as no karstic areas, areas of fractured bedrock exposed at the surface or areas of highly permeable soils are indicated to be present at the site. Three soil samples of the surficial sandy soils were obtained and laboratory grain size distribution analysis was carried out. The surficial soils consist mainly of fine sand with low silt/clay content (3 to 5%) which has an average estimated hydraulic conductivity of ~ 2.6 x 10⁻² cm/s (Section 3.1). The soil can be characterized as poorly graded sand. This is considered to be a soil of medium permeability.

The subsurface soils were also sampled. A sample of silty sand from BH4 had 14% fines (silt and clay sized particles) and the underlying glacial till at BH2 contained 50% fines. The silty clay was not sampled, however, it is expected to be of low permeability as it would be considered a fine grained soil. The underlying soils are of medium to low permeability.



The surficial and underlying soils at the site are of medium to low permeability and the overburden thickness at the site is at least 15 metres or more in thickness. Based on the soils information, the site is not considered to be hydrogeologically sensitive.

The water supply aquifer at the site is considered to be confined, based on the following:

- The piezometric surfaces in the three water supply wells (see cross sections, Figures 4 and 5) are above the top of the aquifer (bedrock elevation); and
- the shape of the drawdown response curve observed in the pumping tests closely resembles the ideal response of a confined aquifer; and
- the storativity coefficient calculated using the drawdown response in adjacent wells is $\sim 2.0 \times 10^{-4}$, whereas specific yield in an unconfined aquifer is typically orders of magnitude higher; and
- Based on the depth and type of soils onsite, there is a confining unit consisting of silty clay and/or glacial till which are some 9 metres to 15 metres in thickness.

As the water supply aquifer is confined, this is indicative that there is some confining unit that prevents direct vertical migration of surface water into the water supply at depth. This is also indicative that the site is not hydrogeologically sensitive.

The minimum lot size proposed for the development is about 0.40 hectares. Accordingly, the above noted "Step 1" does not apply to this site. Hydrogeological isolation between the receiving and water supply aquifers was not evaluated for this site. Thus, "Step 3" was addressed for this site.

3.3.3 Step 3 Assessment

The most probable groundwater receiver for sewage effluent is the red to grey fine to medium sand layer and upper portions of the sandy clay or sandy silty clay that was encountered below the sand at five of the borehole locations. To obtain a general indication as to the potential impact of septic effluent on the properties adjoining the proposed development, a nitrate dilution model was used. A daily effluent loading of 1000 litres per day per septic system was assumed and the expected impact of septic systems at this site was determined by considering the attenuation of nitrate in the effluent from an assumed 40 milligrams per litre (mg/l) (NO_3 as N) after the septic system treatment to the property boundary by dilution as a result of the infiltration of meteoric water only. The



following provides the basis whereby the infiltration reduction factors for the site were chosen for the dilution calculations.

Topographic, soil and land cover infiltration factors were selected from *Table 2* of the MOE *Hydrological Technical Information Requirements for Land Development Applications*. The following is a discussion of each of the infiltration reduction factors chosen for the site.

A soil infiltration factor of 0.40 for open sandy loam is appropriate for the septic effluent dilution calculations, based on the permeability of the soils encountered across the site. Given the continuous nature of the sandy overburden at the site, with between 3 and 5 % silt/clay content in all three sieve analyses, and all six borehole logs describe the surficial soil as fine to medium sand, a terrain map was not considered to be required to delineate the terrain distribution across the property.

The site is characterized by rolling terrain with highest elevations within the southeast portion of the site sloping to the northwest. The steepest slope across the site is to the northwest of about 6 metres over one kilometre and average slope across the site is to the northwest of about 3.0 metres per kilometre. The site is considered to be rolling with a slope infiltration factor of 0.20. Using *Table 10* of the Thornthwaite and Mather *Instructions and Tables for Computing Potential Evapotranspiration and the Water Balance*, a soil water holding capacity of 100 millimetres was provided for the sandy overburden at the site. The value was chosen based on the combination of mainly pasture (deep-rooted crops) in fine sand. However, post-development, it is expected that the site will be mainly grassed (shallow-rooted crops) and the soil is fine sand. The corresponding soil water holding capacity of the site for post development conditions is expected to be between about 50-75 millimetres. The selection of 100 millimetres is conservative, as it overestimates the applicable soil moisture retention for the soils, which results in underestimating the available moisture for infiltration.

The type of land cover observed at the site at the time of site visits and by use of satellite imagery consists mostly of cultivated lands, although there are scattered trees and shrubs across the site. It is expected that the post-development conditions at the site will consist mainly of grassy areas with few trees and shrubs. The land cover infiltration factor of 0.10 was selected, which corresponds to cultivated lands. This is a conservative prediction as it does not account for the



mature trees which may be retained or the landscape trees and shrubs that will likely be cultivated on properties post development.

In order to determine water surplus estimates for the site area, a water surplus model was obtained using published information from Environment Canada (EC) for the City of Ottawa. The water balance model output the average yearly moisture surplus value, based on monthly moisture surplus averages for the period from 1939 to 2021. The expected moisture surplus or net potential infiltration for the site area was estimated at 379 millimetres. The water balance model output data, provided by EC, are provided as Attachment E.

Hard Surfaced Areas post-development were calculated as follows. The total roadway area for the site is 1965 square metres, as provided by Novatech. The other hard surfaced areas are as follows; dwellings (320 square metres), driveways (996 square metres ~ 142 square metres per lot) and miscellaneous impervious areas of 700 square metres (~100 square metres per lot). These allow for other impervious areas on each lot such as decks, pools, etc. The total hard surfaced areas using these values for post-development conditions are 5,901 m².

Post-development conditions include a stormwater management pond, roadside ditches and grassed swales as well as downspouts from the roofs of the dwellings. All of these measures reduce runoff and promote groundwater infiltration on site. The natural background conditions at the site are sandy soil which is expected to readily infiltrate precipitation. The performance of grassed swales in these conditions could be as much as 50%, which reduces the impact of the hard surfaced areas significantly. Even when runoff exceeds the capacity of the swales and roadside ditches, the stormwater pond is also designed to infiltrate groundwater. The use of lot level conveyances and infiltration are not considered in the calculations for sewage dilution. As such, the sewage attenuating capacity of the site is expected to be higher than what is predicted herein.

The results of the sewage dilution calculations indicate that the expected concentration of nitrate at the site boundary due to the proposed 7 sewage systems is about 9.9 milligrams per litre (Attachment E). This is within the Ministry of the Environment acceptable nitrate impact limit of 10 milligrams per litre.

Based on the impact assessment, the development of the site on private sewage disposal systems is not expected to have an adverse impact on groundwater resources in the site area.



4.0 GROUNDWATER SUPPLY INVESTIGATION

4.1 Supply Aquifer

As mentioned above, a bedrock geology map for the site area indicates that dolostone and sandstone of the Beekmantown Group underlie the site.

Area Well Record Review

A review of area well records was carried out including an area surrounding the site of some 150 metres indicating some 32 wells, five of these being non water supply wells (shallow monitoring wells for geotechnical/environmental purposes) and one well record which was a well casing extension above grade. The location of all 34 water wells registered with the Ontario Well Records database are provided in a map (Attachment B) and the information of each well record is tabulated in Table III, describing well casing lengths, well depths, description of overburden stratigraphy and bedrock types and yield information. Based on a review of area water well records, the predominant soil type consists of sand overlying till (variably described as sand/gravel/clay/hardpan/till/stones) with total overburden depths ranging from ~8 to 17 metres. The area well record review indicates that of the 34 water wells that are present within 150 metres of the site, twenty (20) wells have encountered sufficient well yields at depths of 10 to 31 metres depth. A total of nine (9) wells have been drilled to depths of 73 to 104 metres and have encountered sufficient well yields. Some five (5) wells have been drilled to depths of between 36 and 41 metres. Well yields were generally tested at rates of greater than 22 L/minute up to 76 L/minute and available drawdowns for the area wells were at least 3.7 or more metres up to 40 or more metres. Water quality was described as fresh (16 wells), untested (14 wells) and mineralized (1 well) or sulphur and mineralized (1 well). Water quality descriptions were included in some 18 well records, with 16 of these reporting water quality as fresh and two reporting water quality to be mineralized or sulphur and minerals. The well depths of these two wells are reported to be 24 to 27 metres.



Onsite Well Record Review

The MOE well records for the test wells indicate the primary material encountered was limestone during drilling for all three test wells. Well Records for Onsite Wells are provided in Attachment B. Geological cross-sections of the site were prepared using soils and bedrock information from the MOE well records for the test wells and the Records of Boreholes. The geological cross sections are provided as Figures 4 and 5.

The test wells noted the following conditions:

TW1 and TW2 indicate water bearing fractures at depths of some 72 to 74 metres within limestone with sandstone mix and were drilled to depths of some 74 to 76 metres.

TW3 encountered water bearing fractures at depths of about 21 and 28 metres within limestone and was drilled to a final depth of 30 metres.

The test wells were found to be representative of other area wells where the majority (20 of 34 wells) have found sufficient yield within the upper limestone aquifer and some wells (9 of 34 wells) have been drilled deeper into the limestone aquifer to encounter a second fracture zone at or below 73 metres.

4.2 Water Quality

The results of the chemical, physical and bacteriological analyses of water samples obtained from the test wells are provided as Attachment F and field water quality data is provided in Table I. A summary of the laboratory test results is attached as Tables II and III. The water quality as determined from the results of the analyses is favourable. The water meets all the Ontario Drinking Water Standards (ODWS) health and aesthetic parameters tested for at the test wells except for the following:

- hardness at all of the wells
- total dissolved solids at all of the wells
- hydrogen sulphide at TW1 and TW2
- iron at TW2 and TW3



- organic nitrogen at TW1 and TW3
- sodium above 20 mg/l at all of the wells

Hardness

The water samples from all of the test wells are considered hard by water treatment standards. Water with hardness above 80 to 100 milligrams per litre as CaCO_3 is often softened for domestic use. The hardness at the test wells ranges from about 211 to 310 milligrams per litre. Water softening by conventional sodium ion exchange will reduce hardness and scaling on fixtures. However, it may also introduce relatively high concentrations of sodium into the drinking water, which may contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. Where ion exchange water softeners are used, a separate unsoftened water supply could be used for drinking and culinary purposes.

Total Dissolved Solids

The total dissolved solids (TDS) were measured at 539 to 618 milligrams per litre, the three test wells, above the ODWS of 500 milligrams per litre. The Ryznar Stability Indices (RSI) and Langelier Saturation Indices (LSI) were calculated for the samples and gave RSI values of between 7.1 and 7.5 and LSI values between 0.25 and 0.5. The values of RSI that are close to 7 and slightly above 7, indicate that the formation of calcium carbonate (i.e. scaling) does not lead to a protective corrosion inhibitor film on metal fixtures and pipes. However, there RSI value is less than 8, indicating that the water is not corrosive either. LSI values are corresponding positive, but close to zero, which indicates that the water has borderline scale potential, such that minor changes in the water quality, temperature could change the scale or corrosive potential of the water. The effect of elevated TDS levels on drinking water depends on the individual components, which are principally chlorides, sulphates, calcium, magnesium and bicarbonates. Depending on which parameters are elevated, TDS exceedances can include hardness, taste, mineral deposition or corrosion. In this case, all the test well water samples have high levels of hardness and elevated chlorides (155 to 180 mg/l) albeit within the operational guideline for hardness and the aesthetic objective (AO) for chlorides. Chloride is less than the AO and consequently the water palatability is still considered to be good. Therefore, the effect of elevated TDS is considered to be mostly associated with elevated hardness, which can cause mineral deposition, due to the potential for scale to form. As hardness is the cause of the elevated TDS, it is considered that treatment to reduce hardness (ion exchange water softeners) will reduce the mineral deposition associated with the TDS levels.



Hydrogen Sulphide

Hydrogen sulphide levels at TW1 and TW2 are above the aesthetic objective of 0.05 mg/l. TW1 had sulphide levels of 1.10 mg/l and TW2 had lower levels at 0.24 to 0.27 mg/l. Hydrogen sulphide produces an odour and can affect the taste of water. When present in water with iron, it can also cause black staining of laundry items, black deposits on pipes and fixtures. Treatment to reduce sulphide includes aeration. Higher levels of sulphide where iron staining is also an issue (rust staining) may require treatment using chlorination followed by iron filter. Based on the sulphide levels at the site, it is considered that aeration is sufficient to reduce sulphide in the treated water. Well construction recommendations are also made later in this document to ensure that excessive sulphide levels are avoided in future wells at the proposed subdivision.

Three offsite wells were sampled and also had exceedances for hydrogen sulphide. The highest level was at 5560 Lombardy Drive with a hydrogen sulphide level of 8.3 mg/l. The well record for that well indicated that water fractures were encountered at 41 metres depth. In addition, a report for the adjacent subdivision located west of the site entitled "*Report on Site Conditions and Hydrogeology for Top Drawer Holdings Ltd., Proposed Subdivision, Village of Osgoode, March 1978 by Oliver, Mangione, McCalla & Associates Ltd.*" was reviewed with regards to water quality. That report indicated that one of the test wells, drilled to 44 metres depth encountered sulphur water at a depth of about 38 metres depth. Based on this and the occurrence of high levels of hydrogen sulphide at one of the offsite wells (5560 Lombardy Drive), Kollaard Associates Inc. is providing well construction recommendations to ensure that the future wells avoid very elevated levels of hydrogen sulphide that are associated with the water fractures encountered at 38 to 41 metres depth.

Iron

The level of iron at TW2 and TW3 was elevated for the first water samples obtained after three hours (iron levels of 0.46 and 0.54 mg/l), compared to the AO of 0.3 mg/l. However, by the end of the pumping tests, the iron levels were within aesthetic objectives for all three test wells and ranged from 0.11 to 0.21 mg/l. Three other area wells that were sampled also had iron levels within the acceptable limit of 0.3 mg/l. As a result, iron is considered to be within the aesthetic objective of 0.3 mg/l. It should also be noted that water softening to reduce hardness can also decrease iron.



Organic Nitrogen

Organic nitrogen levels at TW1 and TW3 were 0.20 and 0.17 mg/l, respectively, compared to the operational guideline (OG) of 0.15 mg/l. Organic nitrogen is calculated by subtracting the ammonia from the Total Kjeldahl Nitrogen. Organic nitrogen has an OG due to its interaction with chlorine used in water treatment causing taste problems in the treated water. There is a correlation between DOC and organic nitrogen. Organic nitrogen levels above 0.15 mg/l are associated with DOC levels of 0.6 mg/l or greater. As groundwater is typically not treated using chlorine, the potential presence of organic nitrogen in some wells does not require treatment.

Sodium

The sodium levels at all three test wells were between 64 and 98 mg/l, above the 20 milligrams per litre advisory level, whereby the local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets. The sodium levels were well within the aesthetic objective of 200 mg/l.

4.3 Water Quality in Neighbouring Wells

During the initial investigation in April and May 2021, a letter was circulated to all the residents on Lombardy Drive that were closest to the site as well as canvassing along Osgoode Main Street carried out by Kollaard Associates Inc. This included the following addresses 5531, 5533, 5535, 5537, 5538, 5549, 5554, 5560 and 5566 Lombardy Drive. On Osgoode Main Street, door to door canvassing was carried out on two occasions at all the properties that border the site from the south (5495 – 5535 Osgoode Main Street). One home owner (5529 Osgoode Main Street) indicated that they would provide a water sample and complete a well questionnaire. Other residents were either not home when canvassing occurred or did not respond to the letter that was dropped off at their property. One home owner responded to the letter but declined to contribute a water sample. Through canvassing, the presence of driven point (aka sand point) wells was noted at some of the dwellings along Osgoode Main Street. During pre-consultation with RVCA, it was indicated that these wells were not required to be sampled as the water quality in these wells is obtained from the overburden aquifer and is not representative of the water supply aquifer that is targeted for the proposed subdivision.

Neighbours of the site along Lombardy Drive and Osgoode Main Street were canvassed with regards to their servicing. At that time, some of the property owners/tenants along Osgoode Main



Street indicated that the wellheads were either below grade or that sand point wells were in use. One property owner indicated that they do not have a sewage system but a holding tank. The following three wells were sampled as the owners indicated that they had drilled wells and sewage systems.

5529 Osgoode Main Street

- water treatment: iron filter
- water potability: owner drinks water and indicates sulphur odour is present sometimes
- routine bacterial testing: Not since purchase (6 years previous), at which time results were acceptable
- septic system type, age, location and performance: conventional sewage system replaced within last 10 years and no issues
- Well location in east side yard and sewage system in rear yard

5560 Lombardy Drive

- water treatment: aeration, chlorination, iron filter, water softener
- water potability: owner indicates sulphur is a nuisance and treatment equipment maintenance is excessive and problematic. A lot of frustration as adjacent neighbours don't have similar water quality complaints/issues and onerous treatment costs.
- routine bacterial testing: No, but no issues
- septic system type, age, location and performance: original conventional sewage system in front yard, ~5 years old
- Well location in back yard and sewage system in front yard

5566 Lombardy Drive

- water treatment: proprietary filter media, iron filter and water softener
- water potability: Owner indicates sulphur is present.
- routine bacterial testing: No, but no issues
- septic system type, age, location and performance: original conventional sewage system in front yard, ~5 years old



- Well location in back yard and sewage system in front yard

A summary of the water quality obtained from the neighbouring wells and copies of well records (where available) are provided as Table II and Attachment B. The original laboratory test results are provided as Attachment G.

Well records for the wells at 5560 and 5566 Lombardy Drive were available for review. The well records indicate that the well depths are 49 metres and 73 metres, respectively. The well at 5529 Osgoode Main Street is much older and no well record could be confirmed. The well cap could not be removed at the time of the site visit to confirm well depth. However, based on the similarity of water quality in that well to the subject wells, it is considered to be obtaining water from the same formation as other bedrock wells in the area. The test wells on the site are between 30 metres in depth (TW3) and 74 and 76 metres in depth for TW1 and TW2, respectively.

The water quality at the existing wells was generally similar to that of the recently constructed test wells, with exceedances of TDS, hardness and hydrogen sulphide. The exception is the well at 5560 Lombardy Drive, which had very high levels of hydrogen sulphide. That well had a hydrogen sulphide level of 8.3 mg/l in the raw water. At the time of sampling the treated water was also sampled to confirm that hydrogen sulphide could be treated to within the aesthetic objective. The treated water had a hydrogen sulphide level of <0.01 mg/l.

Sampling of Driven Point (Sand point) Wells

Well records review indicates that these wells are not documented and the depths of these wells could not be established with any certainty. However, based on the soil types present in the onsite boreholes and monitoring wells, the sand layer at the site extends to maximum depths of between ~ 4 to 6 metres. The water table is high (less than 2 metres below ground surface) and as driven point wells are generally installed into the water table, they can vary in depth from about 2.5 metres to about 7.6 metres. If driven by weighted hammer or high-pressure water (rather than hand driven), the wells can extend to 15 metres when soil conditions permit (i.e. provided that compacted clay and till or boulders are not encountered). In this case, the maximum depth of driven point wells in this area is probably up to 6 metres as the silty clay underlying the sand would not yield sufficient water and would likely clog the well screens. These wells are highly vulnerable to contamination as there is no separation between any source of contaminants from the surface and the well inlet.



These wells are also susceptible to water shortages during low recharge seasons (summer, drought) and the small diameter (typically 2.5 to 5.0 cm) limits the amount of water available for domestic use.

In order to evaluate the possible source of the nitrates in the shallow receiving water encountered onsite, several water supply wells located up gradient of the site along Osgoode Main Street were sampled for nitrogen species. The civic addresses where water samples were obtained are provided on Figure 3. These dwellings are indicated to be serviced with driven point (i.e. sand point) wells, based on the information provided by the home owners. As driven point wells are not typically exposed at ground surface (connected to plumbing pipes below the frost line) visual confirmation of well locations could not be made. A total of four nearby wells were sampled, as follows: 3216 Reids Lane, 5503, 5519 and 5535 Osgoode Main Street. The original laboratory results are provided as Attachment D. The laboratory results indicate the following nitrate levels in three of the four sampled wells; 12.3 mg/L at 5535 Osgoode Main Street, 30.8 mg/L at 3216 Reids Lane and 22.3 mg/L at 5519 Osgoode Main Street. The nitrate level was <0.10 mg/L at 5503 Osgoode Main Street. This well was later confirmed to be a drilled bedrock well (based on a matching well record using the online database which indicates a drilled well was constructed at that address in 2003). As such, the well at 5503 Osgoode Main Street is not obtaining water from the same aquifer as the other properties and that is why the nitrates were not present in that water sample.

The above noted properties that exist along Osgoode Main Street are all undersized with regards to space for sewage systems and potential for sewage impacts. Although depth of driven point wells could not be determined as no well records were available for review The lot sizes of these properties vary from 0.04 to 0.15 hectares (~0.10 to 0.37 acres). It is considered that these lot sizes are not sufficient to attenuate the nitrates from sewage systems to within acceptable limits. Generally, lot sizes of about 0.4 hectares are necessary to sufficiently dilute sewage effluent, based on the sandy soil conditions in the area. It is understood that some of these properties are not large enough to have sewage systems and at least one of them (3216 Reids Lane) is serviced using a sewage holding tank as the site cannot accommodate a sewage system. These properties have been developed for up to 100 years or more. Generally, they cannot be developed further as the lot sizes are too small to allow for adequate servicing and lot density is not expected to change. As such, the up gradient properties along Osgoode Main Street represent a stable source of nitrogen in the receiving aquifer that has been present for a long time. There have been no significant



changes to development in the area up gradient of the subject site, which has been fully developed dating back to before the earliest available aerial photograph was reviewed for the site (1976 using the City of Ottawa online GeoMaps). As such, it is considered to be a steady state plume, rather than an advancing plume. This is supported by calculating the travel time of groundwater across the site, which provides an indicator of how long the dissolved nitrates in the groundwater up gradient of the site could take to travel across the subject property. This calculation (see below) indicates that it could take from ~1 to ~3 years for sewage effluent from offsite (at or near 3216 Reids Lane) to migrate across the subject property. As the properties have been developed for significantly longer than that, the source of contaminant is considered to be in a steady state (i.e. the contaminant input is not increasing or decreasing). The monitoring wells at the site did not encounter elevated nitrates except for one location.

Further discussion with regards to the proposed development and risk of water quality impacts to or from these properties along Osgoode Main Street is provided (Section 4.4 and 4.5).

4.3 Water Quantity

The rawdown and recovery data and plots for TW1, TW2 and TW3 are provided as Attachments H, I and J, respectively. The drawdown and recovery data provided were measured with reference to the top of the well casing at each test well location.

The pumping test data for the test wells were analyzed using the method of Cooper and Jacob (1946). Although the assumptions on which these equations are based are not strictly met, this method provides a reasonable estimate of the aquifer transmissivity. The analysis of the data obtained during the pumping tests is summarized in the attached Table IV. The water levels in observation wells were monitored during the pumping tests at TW1, TW2 and TW3 and the data are provided as Table VII. Where observation well drawdown had occurred, with interference between TW1 and TW2 during the pumping tests at those wells, corresponding curves of that data are provided as Attachment K. TW3 was too distant from TW2 and TW3 for any significant drawdown to be measured.

The following sections discuss the results of the analysis of the data obtained during the pumping tests with respect to test well yields.



4.3.1 Test Well TW1

The six hour duration pumping test was carried out at a discharge rate of 65 litres per minute. The static water level prior to testing was about 6.86 metres below the top of the well casing and the water level after six hours of pumping was about 8.24 metres below the top of the well casing for a total drawdown at the end of pumping of 1.38 metres. The available drawdown in the well is about 36 metres. The specific capacity of the well at this pumping rate is approximately 68 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 288 m²/day. Based on the recovery data the aquifer transmissivity is estimated to be 192 m²/day. The average transmissivity of the bedrock aquifer in the area of TW1 is estimated to be 240 m²/day. At the end of pumping, 95 percent recovery of the total drawdown in the static water level created during pumping occurred in about 14 minutes.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 65 litres per minute and that during the course of the six hour pumping period about 4 percent of the available drawdown in the test well was utilized.

4.3.2 Test Well TW2

The six hour duration pumping test was carried out at a discharge rate of 62 litres per minute. The static water level prior to testing was about 6.68 metres below the top of the well casing and the water level after six hours of pumping was about 7.72 metres below the top of the well casing for a total drawdown at the end of pumping of about 1.04 metres. The available drawdown in the well is about 36.6 metres. The specific capacity of the well at this pumping rate is approximately 86 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 181 m²/day. Based on the pumping test recovery data, the transmissivity of the aquifer is estimated to be 203 m²/day. The average transmissivity of the bedrock aquifer in the vicinity of TW2 is calculated to be about 192 m²/day. At the end of pumping 95 percent recovery of the total drawdown in the static water level created during pumping occurred within about 75 minutes.



Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 62 litres per minute and that during the course of the six hour pumping period about 3 percent of the available drawdown in the test well was utilized.

4.3.3 Test Well TW3

The six hour duration pumping test was carried out at a discharge rate of 65 litres per minute. The static water level prior to testing was about 4.53 metres below the top of the well casing and the water level after six hours of pumping was about 4.76 metres below the top of the well casing for a total drawdown at the end of pumping of 0.23 metres. The available drawdown in this well is about 20.5 metres. The specific capacity of the well at this pumping rate is approximately 410 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 192 m²/day. Based on the pumping test recovery data, the transmissivity of the aquifer is estimated to be 203 m²/day. The average transmissivity of the bedrock aquifer in the vicinity of TW3 is calculated to be about 192 m²/day. At the end of pumping 90 percent recovery of the total drawdown in the static water level created during pumping occurred after 111 minutes. After 7 hours and 25 minutes, the static water level had recovered 100%.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 65 litres per minute and that during the course of the six hour pumping period about 1 percent of the available drawdown in the test well was utilized.

4.3.4 Interference Effects

During pumping of the test wells, observation well drawdown was observed in each of the other test wells to measure interference effects. The data were obtained from pressure transducer loggers and confirmed with manual measurements. The transducer data is provided as Table 7. The mutual interference effects were calculated for a centrally located well (Lot 2) and the well interference at the property boundary was calculated for the down gradient property line along the north side of the site.



In order to estimate the maximum interference between future wells at the site, calculations were carried out to predict the cumulative thirty year drawdown due to the proposed 7 domestic wells at a central well in the proposed subdivision. The cumulative drawdown at the test wells was calculated for a thirty year pumping rate of 1100 litres per day which allows for four persons per household. The following formula was used for the calculation:

$$s = \frac{2.3Q}{4\pi T} \log\left(\frac{2.25Tt}{r^2 S}\right)$$

where Q = 30 year pumping rate, 1100 L/day
T = average transmissivity, 203 m²/day
t = duration, 30 years
S = storativity, 2.4 x 10⁻⁴
s = expected drawdown due to each of the other 6 wells
r = distance between the observation well and the pumped well, m

The results of the calculations indicate the thirty year drawdown at a centrally located well due to the interference from the other 6 wells in the subdivision is about 0.038 metres. The mutual well interference at the property boundary due to the 7 proposed wells was also estimated to determine the impact of the proposed development on water supply outside of the site. The expected thirty year drawdown at the site boundary was found to be about 0.044 metres.

Attachment B contains MOE Well Records of surrounding existing wells that were available for review. The indicated depths of the existing wells range from about 24 to 73 metres and accordingly are within an aquifer similar to the test wells which range in depth from about 30 to 76 metres. Based on the estimated thirty year drawdown noted above, the expected drawdown is minimal. All wells for which the MOE Well Records were obtained have sufficient available drawdown such that the slight drop in water level that may occur should have no significant impact on water supply at our adjacent to the proposed subdivision. This provides reasonable assurance of adequate water supply in the proposed subdivision as well as at the existing wells.

TW1 observation well interference

During the pumping of TW1, pressure transducer logging was carried out at TW2 and TW3, located some 45 metres and 117 metres distance, respectively, from TW1. Total drawdown observed at TW2 and TW3 was about 0.39 metres and 0.00 metres, respectively. There was no drawdown response at TW3, which is considered to be due to the greater distance between that well and the



pumped well. In fact, water levels rose slightly in that well during the test and then declined shortly after the test was completed (during recovery interval). It is possible that the water level rose due to the change (i.e. drop) in pressure at the piezometric surface that occurred as a result of the pumping of the adjacent well. The drop in pressure can contribute to a small rise in water levels of adjacent wells, due to the decrease in pressure head. This is indicative that there is a likely connection between the wells, but that the distance between them did not contribute to a drop in water level.

TW2 observation well interference

During the pumping of TW2, pressure transducer logging was carried out at TW1 and TW3, located some 45 metres and 117 metres distance, respectively, from TW2. Total drawdown observed at TW1 and TW3 was about 0.42 metres and 0.04 metres, respectively.

TW3 observation well interference

During the pumping of TW3, pressure transducer logging was carried out at TW1 and TW2, located some 117 metres and 118 metres distance, respectively, from TW3. There was no measurable drawdown response in either observation well during the pumping test at TW3. This was considered to be due to the distance between this well and the other wells.

Based on the interference observations, especially that between TW1 and TW3, which are constructed on adjacent proposed lots some 45 metres apart, it is considered that the level of interference is acceptable and will not cause unacceptable drawdown in adjacent future wells at the property.

4.4 Groundwater Flow Directions

The groundwater flow directions and gradients in the receiving and water supply aquifers were determined based on the results of a topographic survey of the site and using the static water levels measured at the standpipes (overburden receiving aquifer) and test wells (bedrock water supply aquifer). The site is located in the Rideau Valley watershed, however, the South Nation watershed exists across most of Osgoode Village and the lands to the east and south are in that watershed.

Water levels were measured on several occasions and are provided in the attached Table X.



4.4.1 Receiving Aquifer

The static water level elevations measured on various dates for the following monitoring wells installed at BH1, BH3, BH5, BH7-BH11, inclusive, are reported in Table X. Based on that data, the receiving aquifer flow direction is indicated to be northwest across the site (see Figure 6A), generally following the topographic slope at the site. The hydraulic gradients were also calculated (Attachment L) and indicated that the average lateral groundwater flow is about 1.2 metres per day. Vertical hydraulic gradient was established at the location of BH1, based on the installation of a deep standpipe (BH7) and indicate that there is a downward gradient at that location. The vertical groundwater flow is about 0.5 m/day.

Based on the gradients and the permeability of the sandy soil (calculated in Section 3.1), groundwater flow across the site migrates in a lateral direction of about 1.2 m/day (based on water elevations taken February 27, 2024). The groundwater flow direction is expected to be to the northwest across the site. The groundwater flow direction in the shallow aquifer is consistent with the topographical slopes at the site and the local influence of the Rideau River to the west/northwest.

4.4.2 Bedrock Water Supply Aquifer

The static water elevations at TW1, TW2 and TW3 are provided below. Based on that data, the supply aquifer groundwater flow direction is indicated to be east-southeast across the site (see Figure 6b). A review of Source Protection Mapping for communal wells in Wellhead Protection Areas for Richmond, Kemptville and Greely (Shadow Ridge subdivision) all indicate that the regional groundwater flow direction in those areas is predominantly eastward, which follows a similar trend that was measured in the onsite water supply wells. As such, the groundwater flow direction observed in the onsite wells is considered to be representative of the regional flow directions which are predominantly eastward.

Test Well	Top of Casing Elevations (masl)	Ground Surface Elevations (masl)	Groundwater Elevations (masl)	
			May 5, 2021	March 3, 2022
TW1	93.17	92.78	86.45	86.07
TW2	93.08	92.60	86.55	86.09



TW3	91.90	91.34	87.37	87.22
-----	-------	-------	-------	-------

The site is located on the border of the RVCA and SNC watersheds. The regional groundwater trend in South Nation is primarily eastward in the western part of that watershed.

4.5 Development Impacts and Neighbouring Land Uses

A description of existing and historical land uses at and near the site with the potential to impact the water supply at the site was previously noted (Section 3.1.2 Land and Water Use Conflicts). The existing land use up gradient of the site in terms of the deeper bedrock aquifer (i.e west-northwest) consists of scattered single family dwellings and agricultural lands, with the Rideau River some 2.4 kilometres to the west. The results of the water quality testing at the test wells indicate that there is no significant impact on the deeper aquifer at the site due to the surrounding residential and agricultural development.

The topographical slopes and the shallow groundwater flow direction within the overburden at the site are to the northwest, based on the shallow monitoring wells installed as part of the current hydrogeological and terrain investigation. A review of current and historical land uses in the area suggests that the up gradient land (to the south and southeast) is fully developed with residential and commercial development including up gradient potential sources of contamination, especially hydrocarbons, due to current and former automotive garages and service stations. Previous environmental investigation was carried out by Dillon Consulting which included soil and groundwater testing. In 2017 and 2018, two rounds of groundwater testing were carried out on five shallow monitoring wells installed across the subject property. The overburden groundwater flow direction was estimated to be to the north, based on those monitoring wells. Water samples were tested for metals, select VOCs (BTEX), PHCs and PAHs. The concentrations of the above noted parameters were all within the Table 2 Standards (O. Reg. 153/04 Table 2 Standards 2011, for potable groundwater). Since that time, there has been no new development of properties that could cause hydrocarbon contamination at the subject site. It is considered that there are no current impacts at the site from up gradient sources. All three drilled water supply wells installed at the site were tested on March 4, 2022, for PHCs F1-F4 and VOCs. None of the tested parameters were measured above the method reporting limits, indicating that there was no presence of any of these parameters in the water supply wells.



Based on the sampling of sand point wells up gradient of the site, and the nitrate level in one onsite shallow monitoring well, there are elevated nitrogen (nitrate) levels in the receiving aquifer up gradient of the site and an isolated elevated groundwater nitrate level onsite. The monitoring wells onsite have not observed any increase in nitrates at the site, despite the elevated nitrates in the up gradient properties.

4.5.1 Impact to Surface Water Quality and Quantity

There are no surface water bodies at the site or within at least 250 metres or more. The closest water body is an unnamed watercourse that exists some 280 metres east-northeast of the site that is a tributary to the Doyle Creek municipal drain. Since the receiving aquifer at the site flows to the northwest, it is unlikely that the post development site could impact the surface water body that is up gradient of the site.

4.6 Well Construction Methodology

Future wells drilled on the site should be constructed with a minimum 6 metres length of casing through the overburden and set at least 3 metres into the sound bedrock. The steel casing placed in the auger holes should be pressure grouted or displacement grouted into place. The material used to seal the annular space could consist of either a cement grout or a commercially available bentonite grout product. Cement grout mixtures should be allowed to set for a minimum two day period for normal cement or twelve hours for a high early strength cement prior to advancing the well further into bedrock. If a bentonite grout product is used, drilling need only be suspended for a few hours depending on the product used. Bentonite grout has the additional advantage of remaining flexible when set and therefore will not crack or shrink thereby ensuring as well as possible that surface water or shallow groundwater will not migrate along the annular space and into the well bore.

Once the casing has been sealed, the well should be advanced uncased in the bedrock until a water supply of sufficient quantity and quality is encountered, as per the following Table.

Target Depths (in order of	Bedrock Description	Target Fracture	Target Well Depth	Well Yields	Comments
-------------------------------	------------------------	--------------------	----------------------	----------------	----------



preference)		depths (metres)	(metres)	(L/min)	
1	Upper Limestone	20 to 31	30 to 31	60 to 65	If insufficient well yields then proceed to Target Aquifer 2
2	Deeper Limestone with possible secondary sandstone mix	72 to 75	74 to 76	60 to 65	Water quality will yield hydrogen sulphide in the range of 0.3 to 1.2 mg/L, requiring treatment using aeration.

Avoidance Depths	Bedrock Description	Avoidance Fracture depths (metres)	Comments
Between Target Aquifer 1 and 2	Limestone	36 to 41	Proceed to Target Aquifer 2. If water fractures are encountered at these depths, they are likely to encounter hydrogen sulphide levels of 8 mg/L, which requires oxidizing chemicals and/or filtration, possible other pre-treatment, costly and requires significant maintenance.

The completed well should then be developed to maximize the yield. The well casings should be completed at least 400 millimetres above the highest point on the finished ground surface within three metres radially from the well after surface drainage is directed away from the well. The casing should be fitted with a pitless adapter to facilitate below ground plumbing and electrical connections. Surface grading should be completed to direct surface water away from the well in order to ensure that water will not collect or pond in the vicinity of the well.

4.7 Post Development Monitoring Program

The results of this investigation indicate acceptable existing and expected impact on the groundwater quality at this site based on the assessment of existing neighbouring land uses and the proposed development. The existing background nitrate impacts within the receiving aquifer at the site are generally acceptable for development. The elevated nitrate levels encountered in the up gradient portion of the site are from long time development on undersized properties that have been developed for greater than fifty years. This is considered to be a stable source that is not advancing or increasing on the subject site. There is also no indication of nitrate impacts in the bedrock water supply aquifer in the existing development up gradient of the site, based on the



testing of two bedrock wells that are located up gradient of the site or in the water supply wells that are located onsite. This combined with the soil conditions at the site indicate that a confining unit/aquitard of silty clay and glacial till soils is present at the site. This is reasonable assurance that there is sufficient protection of the water supply at the site from existing and future sewage systems.

The local hydrogeological conditions and existing water quantity and quality all indicate that the impact of the proposed development will not significantly impact the overall groundwater quality and quantity at the site. Septic effluent dilution calculations, which by experience are known to be a conservative estimate of actual impact, indicate that septic system impact at the site is within MECP requirements. There are only seven residential lots proposed for development. Accordingly, a groundwater monitoring program is not considered necessary for this site.

It is understood that a dedicated well, constructed similarly to the drilled water wells that were constructed onsite is to be provided for the City of Ottawa. The proposed location of the dedicated monitoring well is shown on the *Novatech Preliminary Grading and Site Servicing Plan, Project No. 119089, Drawing No. 119089-PGR, Rev #7*. It is located adjacent to the road near Lot 7.

5.0 SUMMARY AND CONCLUSIONS

The report findings indicate that there is sufficient water quality and quantity to supply the proposed development, with appropriate treatment recommendations. The interference calculations indicate that the impact to water supply on the existing development is within allowable limits.

The groundwater impact assessment indicates that the proposed development impact will not cause Based on the terrain evaluation and groundwater supply investigation at the proposed residential subdivision and the subsequent analysis of the data collected, the following summary and conclusions are provided:

- 1) Class IV sewage disposal systems with partially raised leaching beds will likely be used at this site depending on the lot specific soil and groundwater conditions. The leaching beds should be constructed to conform to the specifications set out in the Ontario Building Code. Any partially raised leaching beds should be constructed of imported sand having a



percolation time of between 6 and 8 minutes per centimetre with less than 5 percent passing the #200 (0.074 mm) sieve. It is recommended that gradation analyses be carried out on any potential sand fill prior to leaching bed construction in order to verify that the percolation time of the fill material is acceptable.

- 2) There is a sufficient groundwater supply of acceptable drinking water quality in the bedrock aquifer system to satisfy the water requirements of the proposed subdivision. It is indicated that most wells will be drilled to depths of about 30 metres to 76 metres and that individual well yields of 62 to 65 litres per minute will be typical. The following Table provides well construction details to be followed for any future wells on the subject property:

Target Depths (in order of preference)	Bedrock Description	Target Fracture depths (metres)	Target Well Depth (metres)	Well Yields (L/min)	Comments
1	Upper Limestone	20 to 31	30 to 31	60 to 65	If insufficient well yields then proceed to Target Aquifer 2
2	Deeper Limestone with possible secondary sandstone mix	72 to 75	74 to 76	60 to 65	Water quality will yield hydrogen sulphide in the range of 0.3 to 1.2 mg/L, requiring treatment using aeration

Avoidance Depths	Bedrock Description	Avoidance Fracture depths (metres)	Comments
Between Target Aquifers 1 and 2	Limestone	36 to 41	If water fractures are encountered at these depths, they may encounter high hydrogen sulphide levels of ~ 8 mg/L, treatment requires oxidizing chemicals and/or filtration, possible other pre-treatment, costly and requires significant maintenance

The area well record review indicates that of the 34 water wells that are present within 150 metres of the site, twenty (20) wells have encountered sufficient well yields at depths of 10 to 31 metres depth. A total of nine (9) wells have been drilled to depths of 73 to 104 metres and have encountered sufficient well yields. Some five (5) wells have been drilled to depths of between 36 and 41 metres.



The study findings recommend the following with regards to construction and placement of water supply wells at the site:

- The well water supply at the site is suitable to provide in excess of 3000 litres/day, which is sufficient for a typical single family dwelling. The minimum well yield, as per MOE D-5-5, is 22.7 litres per minute (5 igpm).
 - Well Placement: Wells should be located at least twice the grade raise plus 15 metres from the fully raised leaching beds, and at least 15 metres from septic tanks. Clearance distances for treatment units and distribution piping shall conform to OBC Tables 8.2.1.6. A and 8.2.1.6. B. Wells should be located such that surface water will not pool around the wellhead and the ground surface around the well should be the highest point for at least 3 metres radially outward.
 - Well casings should be extended a minimum of 0.4 metres above the final finished ground surface at the well.
 - Casing for wells shall extend through the overburden and set into the sound bedrock. The typical casing depth will be between some 18 to 21 metres, depending on the bedrock depth at each well location.
 - Grouting procedure:
 - the annulus of the casing should be pressure injection grouted from the bottom of the casing up
 - the material used to seal annular space could consist of either a cement grout or a commercially available bentonite grout product and should be allowed to set prior to advancing the well further into bedrock; minimum two day period for normal cement, minimum twelve hours for a high early strength cement, or a few hours for a bentonite grout, depending on the product used
 - the well grouting operation and well casing length should be inspected and approved by an experienced hydrogeologist or geotechnical engineer to ensure that the grouting procedure and casing length are in accordance with the site hydrogeological investigation report and Ont. Reg. 903
- 3) There is a sufficient groundwater of acceptable drinking water quality in the bedrock aquifer system at this site as it meets all the ODWS concentrations for all health related chemical, physical and bacteriological parameters tested except for the following:



- **Hardness:**

Future wells at the site are expected to have hardness levels of between about 211 to 310 milligrams per litre. The recommended water treatment consists of ion exchange water softeners and maintaining a separate unsoftened water supply for drinking and culinary purposes.
- **Total dissolved solids:**

Some future wells at the site may slightly exceed the aesthetic objective of 500 mg/l for TDS at levels of 539 to 618 milligrams per litre. The Ryznar Stability Indices (RSI) and Langelier Saturation Indices (LSI) were calculated for the samples where TDS exceed with RSI of 7.1 to 7.5, and LSI of 0.25 and 0.50, indicate that the formation of calcium carbonate (i.e. scaling) does not lead to a protective corrosion inhibitor film on metal fixtures and pipes. However, there RSI value is less than 8, indicating that the water is not corrosive either. LSI values are corresponding positive, but close to zero, which indicates that the water has borderline scale potential, such that minor changes in the water quality, temperature could change the scale or corrosive potential of the water. The noted levels of TDS and the individual components that contribute to it include hardness and elevated chlorides (155 to 180 mg/l) albeit within the operational guideline for hardness and the aesthetic objective (AO) for chlorides. Treatment that removes hardness (i.e. water softeners) will reduce the scale potential. The palatability of water with chlorides less than the aesthetic objective of 250 mg/l are considered to be good.
- **Hydrogen Sulphide:**

Future wells constructed to depths of 36 metres and deeper are expected to encounter hydrogen sulphide above the aesthetic objective of 0.05 mg/l, at levels of ~ 0.24 to 1.10 mg/l. Hydrogen sulphide produces an odour and can affect the taste of water. When present in water with iron, it can also cause black staining of laundry items, black deposits on pipes and fixtures. Well construction methods are provided to ensure that very high levels of hydrogen sulphide can be avoided. This requires that wells that are deeper than 30.5 metres should be constructed to at least 72 metres to ensure that the water fractures that produce excessive hydrogen sulphide levels (up to 8 mg/l) are avoided. Treatment to reduce sulphide includes aeration. Higher levels of sulphide where iron staining is also an issue (rust staining) may require treatment using chlorination followed by iron filter. Based on the sulphide levels at the site, it is



considered that aeration is sufficient to reduce sulphide in the treated water. The type of treatment should be established on a case-by-case basis by a water treatment specialist based on the analysis of chemical parameters tested for each individual well. Through consultation with a water treatment company, based on the hydrogen sulphide levels noted at two of the test wells, the recommended treatment is air capsulate unit (i.e. Zentec Air Capsulate Filter). These units can be supplied by any water treatment company or their equivalent in other brands. The typical cost of the system is ~ \$2,200 plus installation fees. These systems typically have a warranty of up to 20 years and have a regenerative filter so there is little maintenance or replacement parts.

- Organic Nitrogen:

Organic nitrogen levels may be slightly elevated at 0.17 to 0.20 mg/l, in some future wells, compared to the operational guideline (OG) of 0.15 mg/l. Organic nitrogen is calculated by subtracting the ammonia from the Total Kjeldahl Nitrogen. Organic nitrogen has an OG due to its interaction with chlorine used in water treatment causing taste problems in the treated water. There is a correlation between DOC and organic nitrogen. Organic nitrogen levels above 0.15 mg/l are associated with DOC levels of 0.6 mg/l or greater. As groundwater is typically not treated using chlorine, the potential presence of organic nitrogen in some wells does not require treatment.

- Sodium:

The sodium levels at all three test wells were between 64 and 98 mg/l, above the 20 milligrams per litre advisory level, whereby the local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets. The sodium levels were well within the aesthetic objective of 200 mg/l. It is recommended that if water softeners are used to treat hardness and TDS levels, that an untreated drinking water tap is installed in the kitchen to ensure that excessive sodium levels in treated water are not consumed. The City of Ottawa public health should be notified of the sodium exceedance in the raw water supply.

- 4) Mutual water level interference effects between neighbouring wells in the proposed subdivision are expected to be minimal. The impact of future wells at the proposed subdivision on neighbouring existing wells is expected to be minimal.



- 5) Future wells drilled on this property should be constructed with casing through the upper portion of bedrock and set into the sound bedrock. Minimum casing lengths of about 18 to 21 metres are typical depending on depth to bedrock at each well location. The annulus of the casing should be grouted using a pressure injection method. Casing and grouting should extend to at least 6 metres below the existing ground surface. Well casings should be extended a minimum of 0.4 metres above the final finished ground surface at the well. Ontario Building Code setbacks shall be maintained.
- 6) It is considered that the type of existing surrounding land use adjacent to the subject property should not impact the subject site from a water supply or water quality point of view.
- 7) Based on the terrain assessment and including construction recommendations and mitigative measures proposed for this development, the groundwater impacts from the proposed 7 lots at this site are within acceptable limits established by the MECP and there is no adverse impact on the use of groundwater on existing and future down gradient properties.
- 8) The study findings recommend the following with regards to construction of septic systems at the site:
 - Partially raised leaching beds will likely be required at this site depending on the lot specific soil and groundwater conditions.
 - Leaching beds should be constructed to conform to the specifications set out in the Ontario Building Code.
 - Imported sand with a percolation time of between 6 and 8 minutes per centimetre and less than 5 percent passing the #200 (0.074 mm) sieve should be used to construct the raised leaching beds.
 - In situ percolation rate tests and/or gradation analyses should be carried out on any potential sand fill or native sand material prior to leaching bed construction in order to verify that the percolation time is acceptable.
 - The locations of sewage systems and wells should be placed in accordance with the Lot Development Plan with sewage systems located on the west sides of the lots with wells in the east side of the lots. This will ensure that wells are up gradient of sewage systems on



each lot and maximize separation distances between sewage systems and wells on adjacent properties.

- Any change to the placements of the wells and/or sewage systems on any individual lot shall ensure that there is no impairment to the placement of wells and sewage systems on adjacent lots and that the other lots can still follow the Preliminary Grading & Site Servicing Plan.
- The wells must be accessible for servicing in future. This is interpreted as a minimum 3 to 5 metres of space between the front and rear yards where a drill rig could access the rear yard. Based on the side yard setbacks of at least 3 to 5 metres that are provided in the attached Lot Development Plan, it is considered that this is sufficient space to ensure well access.

Test Well Abandonment:

There are currently three test wells that were drilled on the subject site including TW1 (Lot 7), TW2 (Lot 6) and TW3 (Lot 1). These wells can be used as future water supply wells provided that the following is verified and/or carried out:

- wells shall be minimally three metres from the property lines in order to ensure that positive drainage is occurring away from the well head;
- wells shall meet or exceed the minimum separation distances to sewage systems and sewage tanks indicated by the Ontario Building Code; and
- wells should be protected from damage during construction.

Existing on-site monitoring wells, including the boreholes BH1, BH3 and BH5, should be properly decommissioned in accordance with Ontario Well Regulation 903. A record of well abandonment should be produced for each well, prior to any construction at the site.

- 9) The maximum building footprint, based on the Terrain Study, is 600 m², which includes driveways and single family dwellings. Larger building envelopes and/or coach houses and/or ground source heat pumps have not been evaluated as part of the Hydrogeology and Terrain Study. Any proposed use of these systems and/or larger building footprints and coach houses would require a hydrogeological assessment and/or terrain analysis.



- 12) Homeowners should be provided with information regarding well water testing, well maintenance and water and energy conservation. Homeowners should be referred to the MOE publication *Water Supply Wells – Requirements and Best Management Practices* manual, April 2015. Additional information and links on water conservation measures are offered at the wellaware.ca website.

6.0 RECOMMENDATIONS

The following recommendations are made, based on the report findings:

1) Well Construction:

- All wells drilled on this property shall be constructed in accordance with Ontario Well Regulations 903. The well casing shall extend through the overburden and sealed into the bedrock with suitable sealant. The typical casing depth will be between some 18 to 21 metres, depending on the bedrock depth at each well location.
- It is recommended that drinking water wells be drilled to the target depths, as noted below in order of preferred water supply, and well construction should proceed as follows:
 - TARGET DEPTH 1:
The preferred target depth is within the upper limestone aquifer where well yields in the range of 60 to 65 L/minute are anticipated. Where well yield is not sufficient, effort should be made, including surging or fracturing of the well at the preferred Target Depth 1 (as described in the Table below), to improve yield. If sufficient well yield is not achieved, then proceed to drill well as noted for Target Depth 2.
 - TARGET DEPTH 2:
The well should be extended to the second target depth, where limestone and sandstone mix are encountered, as noted below.
 - AVOIDANCE DEPTH:
Most area wells are not drilled to these depths. If insufficient water is encountered at Target Depth 1, wells should be drilled to the Target Depth 2.



Target Depths (in order of preference)	Bedrock Description	Target Fracture depths (metres)	Target Well Depth (metres)	Well Yields (L/min)	Comments
1	Upper Limestone	20 to 31	30 to 31	60 to 65	If insufficient well yields then proceed to Target Aquifer 2
2	Deeper Limestone with possible secondary sandstone mix	72 to 75	74 to 76	60 to 65	Water quality will yield hydrogen sulphide in the range of 0.3 to 1.2 mg/L, requiring treatment using aeration

Avoidance Depths	Bedrock Description	Avoidance Fracture depths (metres)	Comments
Between Target Aquifers 1 and 2	Limestone	36 to 41	If water fractures are encountered at these depths, they may encounter high hydrogen sulphide levels of ~ 8 mg/L, treatment requires oxidizing chemicals and/or filtration, possible other pre-treatment, costly and requires significant maintenance.

- The locations of the existing test wells on Proposed Lots 1, 6 and 7 are considered to be suitable such that these wells can remain in place and be used as the water supply wells for those lots as shown in the Lot Development Plan, provided that all development setbacks and Ontario Building Code setback distances are maintained. If any water supply well(s) is to be abandoned, it shall be decommissioned by a licensed well contractor and a record of well abandonment shall be provided to the City and the Ministry of the Environment, Conservation and Parks prior to any building permit being issued for that lot.
- Grouting procedure:
 - Certificate of Well Compliance shall be provided to the City of Ottawa and be certified by a Professional Geoscientist or a Professional Engineer and shall be constructed and located as per the Lot Development Plan (Figure 7) and this report including provision of a Certificate of Well Compliance to the City of Ottawa for any new future well(s); and
 - The entire annulus of the casing should be pressure injection grouted from the bottom of the casing up; and



- The material used to seal annular space could consist of either a cement grout or a commercially available bentonite grout product and should be allowed to set prior to advancing the well further into bedrock.

2) The wells must be accessible for servicing in future. This is interpreted as a minimum 3 to 5 metres of space between the front and rear yards where a drill rig could access the rear yard. Based on the side yard setbacks of at least 3 to 5 metres that are provided in the attached Lot Development Plan, it is considered that this is sufficient space to ensure well access.

3) Water Quality and Quantity:

The water quality at the site meets all health and aesthetic objectives except for the following:

➤ *Sodium*

Sodium is above the medical advisory level of 20 mg/L for those who require a sodium reduced diet. When sodium levels exceed 20 mg/L, the local Medical Officer of Health should be informed so that the information can be relayed to local physicians. Sodium levels in untreated raw drinking water are expected to be ~60 to 100 mg/L.

➤ *Hardness and Total Dissolved Solids*

Future wells at the site are expected to have hardness levels of between about 211 to 310 milligrams per litre. Total dissolved solids may be present above 500 mg/L, due to excessive hardness and the water has scale forming potential. Recommended treatment consists of water softeners and maintaining a separate unsoftened water supply, if desired, for drinking and culinary purposes.

➤ *Hydrogen Sulphide*

For wells that obtain water from the deeper target depth, they are expected to encounter hydrogen sulphide above the aesthetic objective of 0.05 mg/l, at levels of ~ 0.24 to 1.10 mg/l. Hydrogen sulphide produces an odour and can affect the taste of water. When present in water with iron, it can also cause black staining of laundry items, black deposits on pipes and fixtures. Well construction methods are provided to ensure that very high levels of hydrogen sulphide can be avoided. This requires that wells that are deeper than 30.5 metres should be constructed to at least 72 metres to ensure that the water fractures that produce excessive hydrogen sulphide levels (up to 8 mg/l) are avoided. Where hydrogen sulphide is present, it is recommended that the type of treatment should be



established on a case-by-case basis by a water treatment specialist based on the analysis of chemical parameters tested for that individual well. An aeration system (i.e. Zentec Air Capsulate Filter). These units can be supplied by any water treatment company or their equivalent in other brands. The typical cost of the system is ~ \$2,200 plus installation fees. These systems typically have a warranty of up to 20 years and have a regenerative filter so there is little maintenance or replacement parts.

- 4) The City of Ottawa requires that a dedicated monitoring well, constructed similarly to the drilled water wells that are proposed for water supply is to be provided onsite in an accessible location for the City to use for monitoring purposes. It is understood that it is the developer's requirement to drill this well and the well must be equipped with water level and barometric dataloggers, to the satisfaction and at no cost to the City. The City will have unlimited access to this well to monitor groundwater conditions. The proposed location of the dedicated monitoring well is shown on the *Novatech Preliminary Grading and Site Servicing Plan, Project No. 119089, Drawing No. 119089-PGR, Rev #7*. It is located adjacent to the road near Lot 7. Well siting shall ensure that the grading, casing and well construction is in accordance with the construction recommendations in this report and O. Reg. 903.
- 5) Sewage Systems:
 - The proposed sewage systems to service each lot shall be partially raised Class IV leaching beds, depending on the lot specific soil and groundwater conditions. The use of Level IV treatment systems may be installed if desired to achieve higher treatment and reduce space requirements.
 - The proposed sewage systems shall be located in the general locations as shown in the Lot Development Plan (Figure 7). While the exact placement of the dwelling, well and sewage system on each lot may vary somewhat from what is shown, the general layout shall be maintained.
- 6) The maximum building footprint for each lot is 320 square metres.
- 7) Coach houses or Secondary dwelling units would require an evaluation of the well water quality, quantity and the adequacy of the existing septic system and groundwater impact assessment at the time of application for a building permit for the secondary unit or coach house.



- 8) Open loop groundwater heat pumps are not approved for use on this property due to the proximity of neighbouring wells and potential for well interference.
- 9) Homeowners shall be made aware of their responsibilities with regards to well maintenance in accordance with O. Reg. 903 and proper sewage system construction and maintenance requirements. Homeowners are referred to the following resources:
 - MOE publication *Water Supply Wells – Requirements and Best Management Practices* manual, April 2015 available at <<https://www.ontario.ca/document/water-supply-wells-requirements-and-best-practices>>. Additional information and links on water conservation measures are offered at the *wellaware.ca* website.
 - Ontario Wastewater Association <https://www.owa.org/homeowner-resources/> for sewage system information and maintenance resources.

Regards,

Kollaard Associates Inc.



Colleen Vermeersch, P. Eng.



BOREHOLE BH01

PROJECT: Proposed Residential Subdivision

PROJECT NUMBER: 210064

CLIENT: Crestview Innovations Inc.

DATE OF BORING: 2021-02-10


LOCATION: 3200 Reids Lane

SHEET: 1 of 1

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST blows/300 mm					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION		
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o												
								0	20	40	60	80	100	0	20	40			60	80
0.00	Topsoil (FILL)	0.00		92.89	1	SS	WH													
0.15	Yellow brown sand and gravel (FILL)	0.15		92.74	2	SS	WH													
0.30		0.30		92.59																
0.70	TOPSOIL	0.70		92.19																
1.37	Red brown fine to medium SAND, trace silt	1.37		91.52	3	SS	WH													
	Grey fine to medium SAND				4	SS	WH													
					5	SS	WH													
3.66	Borehole continued as probehole	3.66		89.23																
14.52	Practical refusal on large boulder or bedrock	14.52		78.37																



Water observed in borehole at approximately 1.5 metres below the existing ground surface, February 4, 2021. Water measured in standpipe at approximately 0.5 metres below the existing ground surface, February 12, 2021.

DEPTH SCALE: 1 to 100

LOGGED: DT

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: SD



BOREHOLE BH02

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2021-02-04

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	TOPSOIL	0.00		91.16	1	SS	WH												
	Grey fine to medium SAND	0.40		90.76	2	SS	WH												
2.0	Grey SILTY CLAY, some sand	1.80		89.36	3	SS	WH												
	Grey fine to medium SAND, some silt, trace clay	2.60		88.56	4	SS	WH												
					5	SS	WH												
4.0	Grey SILTY CLAY	3.86		87.30	6	SS	WH												
					7	SS	WH												
6.0																			
					8	SS	WH												
8.0	Grey silty sand, trace to some gravel, cobbles and boulders, trace clay (GLACIAL TILL)	7.15		84.01	9	SS	WH												
					10	SS	WH												
	End of borehole in GLACIAL TILL	8.99		82.17															

▽

Water observed in borehole at approximately 1.8 metres below the existing ground surface, February 4, 2021.

BOREHOLE BH03

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane





PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2021-02-04

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST blows/300 mm					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o											
								0	20	40	60	80	100	0	20	40			60
	TOPSOIL	0.00		89.39	1	SS	WH												
	Grey fine to medium SAND	0.40		89.99															
	Grey SILTY CLAY, some sand	1.10		89.29	2	SS	WH												
2.0					3	SS	WH												
	Grey fine to medium SAND, some silt, trace clay	2.33		88.06	4	SS	WH												
	End of borehole in SAND	2.89		87.50															

Water observed in borehole at approximately 0.9 metres below the existing ground surface, February 4, 2021. Water measured in standpipe at approximately 1.4 metres below the existing ground surface, February 12, 2021.

DEPTH SCALE: 1 to 75

LOGGED: DT

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: SD



BOREHOLE BH04

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2021-02-03

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
0.0	Topsoil (FILL)	0.00		92.54	1	SS	WH												
	Yellow brown sand and gravel (FILL)	0.15		92.39															
1.0	TOPSOIL	1.15		91.39	2	SS	WH												
	Red brown fine to medium SAND, trace silt	1.30		91.24															
2.0	Grey fine to medium SAND	1.80		90.74	3	SS	WH												
	Grey fine to medium SAND																		
4.0	Grey SILTY CLAY, some sand	3.60		88.94	4	SS	WH												
6.0	Grey fine to medium SAND, some silt, trace clay	4.72		87.82	5	SS	WH												
8.0	Grey SILTY CLAY	6.09		86.45	6	SS	WH												
					7	SS	WH												
					8	SS	WH												
					9	SS	WH												
					10	SS	WH												
					11	SS	WH												

Water observed in borehole at approximately 1.5 metres below the existing ground surface, February 4, 2021.

End of borehole in SILTY CLAY 9.75 82.79

DEPTH SCALE: 1 to 75

LOGGED: DT

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: SD



BOREHOLE BH05

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2021-02-03

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	TOPSOIL	0.00		91.37	1	SS	8												
	Red brown fine to medium SAND	0.45		90.92	2	SS	12												
	Grey fine to medium SAND	1.20		90.17	3	SS	4												
2.0					4	SS	3												
	Grey SILTY CLAY, some sand	3.20		88.17	5	SS	2												
4.0					6	SS	32												
	End of borehole in SILTY CLAY	4.42		86.95															

Water observed in borehole at approximately 1.2 metres below the existing ground surface, February 3, 2021. Water measured in standpipe at approximately 1.7 metres below the existing ground surface, February 12, 2021

DEPTH SCALE: 1 to 75

LOGGED: DT

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: SD



BOREHOLE BH06

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2021-02-04

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	TOPSOIL	0.00		89.32	1	SS	2												
	Red brown fine to medium SAND, trace silt	0.35		89.97															
	Grey fine to medium SAND	0.90		89.42	2	SS	4												
2.0	Grey SILTY CLAY, some sand	1.90		88.42	3	SS	5												
	Grey fine to medium SAND, some silt, trace clay	2.29		88.03	4	SS	20												
	Grey SILTY CLAY	3.00		87.32	5	SS	2												
4.0																			
					6	SS	WH												
6.0	Grey silty sand, some gravel, cobbles and boulders, trace clay (GLACIAL TILL)	5.64		84.68															
					7	SS	2												
	End of borehole in GLACIAL TILL	6.70		83.62															

Water observed in borehole at approximately 0.9 metres below the existing ground surface, February 4, 2021.

DEPTH SCALE: 1 to 75

LOGGED: DT

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: SD



BOREHOLE BH07

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2023-10-17

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	Augered through sand materials	0.00		92.92															
1.0																			
2.0																			
3.0																			
4.0	Grey fine to medium SAND	3.05		89.87	1	SS	5												
5.0																			
6.0					2	SS	5												
7.0					3	SS	16												
8.0					4	SS	6												
	Grey SILTY CLAY	6.10		86.82	5	SS	1												
					6	SS	1												
	End of borehole in SILTY CLAY	8.23		84.69															

Groundwater measured in standpipe at about 1.7 metres below the existing ground surface, October 23, 2023.

DEPTH SCALE: 1 to 50

LOGGED: CI

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: CV



BOREHOLE BH08

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2023-10-17

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	Augered through sand materials	0.00		90.87															
1.0																			
2.0																			
3.0																			
4.0	Grey fine to medium SAND	3.05		87.82	1	SS	13												
5.0	Grey SILTY CLAY	4.57		86.30	3	SS	WH												
	End of borehole in SILTY CLAY	5.18		85.69															

Groundwater measured in standpipe at about 0.3 metres below the existing ground surface, October 23, 2023.

DEPTH SCALE: 1 to 50

LOGGED: CI

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: CV



BOREHOLE BH09

PROJECT: Proposed Residential Subdivision

PROJECT NUMBER: 210064

CLIENT: Crestview Innovations Inc.

DATE OF BORING: 2023-10-17

LOCATION: 3200 Reids Lane

SHEET: 1 of 1

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	Augered through sand materials	0.00		91.91															
1.0																			
2.0																			
3.0																			
	Grey fine to medium SAND, some silt	3.05		88.86	1	SS	15												
4.0	Grey SILTY CLAY	3.81		88.10	2	SS	WH												
	End of borehole in SILTY CLAY	4.42		87.49															

Groundwater measured in standpipe at about 0.2 metres below the existing ground surface, October 23, 2023.

DEPTH SCALE: 1 to 50

LOGGED: CI

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: CV

BOREHOLE BH10

PROJECT: Proposed Residential Subdivision

PROJECT NUMBER: 210064

CLIENT: Crestview Innovations Inc.

DATE OF BORING: 2023-10-17

LOCATION: 3200 Reids Lane

SHEET: 1 of 1

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
0.00	Augered through sand materials	0.00	[Strata Plot: Sand]	91.71															
1.0																			
2.0																			
3.0																			
3.05	Grey fine to medium SAND, some silt, trace clay	3.05	[Strata Plot: Sand]	88.66	1	SS	2												
4.0					2	SS	8												
5.0					3	SS	21												
5.33	Grey SILTY CLAY	5.33	[Strata Plot: Silty Clay]	86.38	4	SS	WH												
5.94	End of borehole in SILTY CLAY	5.94	[Strata Plot: Silty Clay]	85.77															

Groundwater measured in standpipe at about 0.8 metres below the existing ground surface, October 23, 2023.

DEPTH SCALE: 1 to 50

LOGGED: CI

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: CV

BOREHOLE BH11

PROJECT: Proposed Residential Subdivision

CLIENT: Crestview Innovations Inc.

LOCATION: 3200 Reids Lane

PENETRATION TEST HAMMER: 63.5 kg, Drop, 0.76 mm

PROJECT NUMBER: 210064

DATE OF BORING: 2023-10-17

SHEET: 1 of 1

DATUM: GEODETIC

DEPTH SCALE (meters)	SOIL PROFILE			SAMPLES			UNDIST SHEAR STRENGTH x Cu. kPa x					DYNAMIC CONE PENETRATION TEST					MOISTURE CONTENT (%)	PIEZOMETER OR STANDPIPE INSTALLATION	
	DESCRIPTION	DEPTH (m)	STRATA PLOT	ELEV. (m)	NUMBER	TYPE	BLOWS/0.3m	REM SHEAR STRENGTH o Cu. kPa o					blows/300 mm						
								0	20	40	60	80	100	0	20	40			60
	Augered through sand materials	0.00		91.83															
1.0																			
2.0																			
3.0																			
4.0	Grey fine to medium SAND, some silt, trace clay	3.05		88.78	1	SS	2												
5.0					2	SS	8												
					3	SS	5												
	Grey SILTY CLAY	5.33		86.50	4	SS	WH												
	End of borehole in SILTY CLAY	5.94		85.89															

Groundwater measured in standpipe at about 1.4 metres below the existing ground surface, October 23, 2023.

DEPTH SCALE: 1 to 50

LOGGED: CI

BORING METHOD: Power Auger

AUGER TYPE: 200 mm Hollow Stem

CHECKED: CV

TABLE I
FIELD WATER QUALITY MEASUREMENTS
FOR TEST WELLS

	Hours Since Pumping Test Started	Temp. (°C)	pH	Conductivity (µS)	TDS (ppm)	Turbidity (NTU)	Free Chlorine (mg/l)
TW 1	1	9.3	7.7	980	497	1.9	0.0
	2	9.3	8.0	990	500	0.6	-
	3	9.5	7.9	988	478	0.8	0.0
	4	9.6	7.7	940	480	0.6	-
	5	9.4	7.8	960	480	0.4	-
	6	9.4	7.7	955	385	0.6	0.0
TW 2	1	9.5	8.3	666	337	1.6	0.0
	2	9.5	7.9	788	395	0.7	-
	3	9.5	7.8	788	400	1.0	0.0
	4	9.5	7.3	840	430	1.0	-
	5	9.5	7.8	775	400	0.6	-
	6	9.5	7.8	850	430	0.6	0.0
TW 3	1	9.4	7.5	832	400	8.1	0.0
	2	9.4	7.3	855	435	4.5	-
	3	9.5	7.8	885	445	1.7	0.0
	4	9.4	7.8	880	447	0.9	-
	5	9.5	7.6	903	463	0.6	-
	6	9.5	7.4	880	445	0.5	0.0

TABLE II

SUMMARY OF SUBDIVISION WATER CHEMISTRY FOR TEST AND SAMPLED WELLS

Parameter	Guideline	TW1		TW2		TW3		5529 Osgoode Main	5560 Lombardy	5566 Lombardy
		3hr	6hr	3hr	6hr	3hr	6hr			
Alkalinity [mg/l]	OG 500	143	142	139	140	154	157	132	172	178
Chloride [mg/l]	AO/MCCRT 250	178	180	155	165	167	173	163	222	187
Colour [TCU]	AO 5 MCCRT 7	<2	<2	<2	<2	<2	2	2	<2	<2
Conductivity [uS/cm]		951	945	829	879	879	916	862	1160	1050
DOC [mg/l]	AO 5	1.8	2.0	1.8	2.1	1.9	1.9	1.8	1.2	1.5
Fluoride [mg/l]	MAC 1.5	0.83	0.85	0.94	0.89	0.17	0.16	1.19	1.48	0.69
Hydrogen Sulphide [mg/l]	AO 0.05	1.10	1.10	0.27	0.24	<0.01	<0.01	1.22	8.30 (raw) <0.01 (treated)	0.30
Ammonia [mg/l]		0.307	0.303	0.290	0.307	0.171	0.168	0.387	0.381	0.320
Nitrite [mg/l]	MAC 1.0	<0.50	<0.50	<0.10	<0.10	<0.10	<0.10	<0.10	<0.50	<0.50
Nitrate [mg/l]	MAC 10.0	<0.50	<0.50	<0.10	<0.10	<0.10	<0.10	<0.10	<0.50	<0.50
pH		8.19	8.20	8.05	8.01	8.01	8.08	8.21	8.35	8.17
Phenols [mg/l]		<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010
Sulphate [mg/l]	AO 500	44	44	47	41	49	50	23	46	60
Tannin & Lignin [mg/l]		0.1	0.1	0.1	0.2	0.7	0.6	<0.10	0.2	0.4
TDS [mg/l]	AO 500	618	614	539	571	571	595	560	754	682
TKN [mg/l]		0.391	0.504	0.272	0.323	0.184	0.337	0.503	0.698	0.505
Organic Nitrogen [mg/l]	AO 0.15	0.08	0.20	0.00	0.02	0.01	0.17	0.12	0.32	0.18
Turbidity [NTU]	AO 5.0	2.2	1.1	5.7	1.2	3.2	1.5	2.4	28.3	1.8
Hardness [mg/l]	OG 100	229	229	211	233	298	310	161	170	234
Ion Balance		1.01	1.01	0.97	1.01	1.00	1.02	0.88	1.03	1.03
Calcium [mg/l]		44	44	40	44	65	68	30	35	46
Magnesium [mg/l]		29	29	27	30	33	34	21	20	29
Potassium [mg/l]		11	11	11	11	4	4	9	9	10
Sodium [mg/l]	AO 200	98	98	78	80	64	67	78	171	126
Iron [mg/l]	AO 0.3	0.16	0.11	0.46	0.14	0.54	0.21	0.20	0.11	0.07
Manganese [mg/l]	AO 0.05	0.01	0.01	0.02	0.01	0.01	0.01	0.01	<0.01	0.01

TABLE III

SUMMARY OF HEAVY METALS TESTING IN SUBDIVISION TEST WELLS

Parameter	Guideline	TW1		TW2		TW3	
		3hr	6hr	3hr	6hr	3hr	6hr
Aluminum [mg/l]	OG 0.1	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
Arsenic [mg/l]	IMAC 0.01	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Boron [mg/l]	IMAC 5.0	0.53	0.54	0.57	0.58	0.06	0.06
Barium [mg/l]	MAC 1.0	0.08	0.07	0.26	0.20	0.32	0.33
Cadmium [mg/l]	MAC 0.005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
Cobalt [mg/l]	*0.0038	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002
Chromium [mg/l]	MAC 0.05	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Copper [mg/l]	AO 1.0	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Mercury [mg/l]	MAC 0.001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
Lead [mg/l]	MAC 0.010	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Antimony [mg/l]	IMAC 0.006	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005
Selenium [mg/l]	MAC 0.05	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium [mg/l]	** 7.0	3.92	3.87	3.28	3.64	0.662	0.677
Uranium [mg/l]	MAC 0.02	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Vanadium [mg/l]	*0.0062	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc [mg/l]	AO 5.0	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01

Guideline refers to Ontario Drinking Water Standards, Objectives and Guidelines except where noted

* O. Reg 153/04 standard Table 2 for potable groundwater

** Health Canada health related maximum

TABLE IV

SUMMARY OF PUMPING TEST RESULTS AND WELL PARAMETERS

Well	Tp (m ² /day)	Tr (m ² /day)	Tav (m ² /day)	Q (m ³ /day)	SC (m ³ /day/m)	ho m	hf m	Td m	TD m	CS m	AD m
TW1	288	192	240	94.3	68.3	6.86	8.24	1.38	76.20	0.60	36.4
TW2	181	203	192	88.9	85.7	6.68	7.72	1.04	74.37	0.60	36.6
TW3	192	163	177	94.3	409.8	4.53	4.76	0.23	30.48	0.60	20.5

Average Transmissivity: 203 m²/day

Well	% Available Drawdown Used
TW1	3.79%
TW2	2.83%
TW3	1.12%

- Note:
- Tp: Transmissivity as calculated from pumping data (m²/day)
 - Tr: Transmissivity as calculated from recovery data (m²/day)
 - Tav: Average transmissivity (average of pumping and recovery) (m²/day)
 - Q: Test pumping rate (m³/day)
 - SC: Specific Capacity (m³/day/m)
 - ho: Static water level (below top of casing) at beginning of pumping test (metres)
 - hf: Water level (below top of casing) at end of 6 hour pumping test (metres)
 - Td: Total drawdown (metres)
 - TD: Total depth of well (below ground surface) (metres)
 - CS: Casing stickup above ground surface (metres)
 - AD: Approximate available drawdown (metres)

TABLE V
MUTUAL WELL INTERFERENCE AT CENTRAL LOT

Storativity 2.4.E-04 based on storativity estimate using drawdown in observation wells (cooper-jacob straight-line)

Transmissivity 203 m²/day average calculated value using cooper-jacob

T 2.E-03 m²/s

Q 1100 L/day

Q 1.27E-05 m³/s

Duration 30 years

Duration 946080000 s

2.3Q/(4πiT) 0.0010

Lot	Distance [m]	30 Year Drawdown [m]
1	47.8	0.007
3	49.5	0.007
4	138	0.006
5	110	0.006
6	108	0.006
7	126	0.006
Cumulative aquifer drawdown at centre well [metres]		0.038

TABLE VI
WELL INTERFERENCE AT PROPERTY BOUNDARY

Storativity	2.4.E-04	based on storativity estimate using drawdown in observation wells (cooper-jacob straight-line)
Transmissivity	203 m ² /day	average calculated value using cooper-jacob
T	2.E-03 m ² /s	
Q	1100 L/day	
Q	1.27E-05 m ³ /s	
Duration	30 years	
Duration	946080000 s	
2.3Q/(4πiT)	0.0010	

Lot	Distance [m]	30 Year Drawdown [m]
1	29.2	0.007
2	55.7	0.007
3	100	0.006
4	192	0.006
5	158	0.006
6	145	0.006
7	145	0.006
Cumulative aquifer drawdown at north property corner [m]		0.044

TABLE VII

DRAWDOWN IN OBSERVATION WELLS
DURING PUMPING TESTS

DATE: 5-May-21
 PUMPED WELL: TW3
 OBSERVATION WELL: TW1
 DISTANCE BETWEEN PUMPED WELL AND OBSERVATION WELL, r: 117.2 metres
 PUMPING RATE, Q: 94.3 m3/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-6.73	
15	-6.73	0.00
30	-6.73	0.00
45	-6.74	0.01
60	-6.75	0.02
75	-6.76	0.03
90	-6.74	0.01
105	-6.73	0.00
120	-6.72	0.00
135	-6.72	-0.01
150	-6.72	-0.01
165	-6.74	0.01
180	-6.74	0.02
195	-6.74	0.02
210	-6.74	0.01
225	-6.74	0.01
240	-6.74	0.01
255	-6.74	0.01
270	-6.74	0.01
285	-6.73	0.01
300	-6.73	0.00
315	-6.74	0.01
330	-6.74	0.01
345	-6.73	0.00
360	-6.74	0.02
375	-6.76	0.03
390	-6.73	0.00
405	-6.73	0.00
420	-6.73	0.01

TABLE VII (continued)

DATE 5-May-21
 PUMPED WELL: TW3
 OBSERVATION WELL: TW2
 DISTANCE BETWEEN PUMPED
 WELL AND OBSERVATION WELL, r: 117.6 metres
 PUMPING RATE, Q: 94.3 m³/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-6.63	0
15	-6.63	0.00
30	-6.63	0.00
45	-6.63	0.00
60	-6.64	0.01
75	-6.65	0.03
90	-6.66	0.03
105	-6.64	0.01
120	-6.63	0.00
135	-6.63	0.00
150	-6.62	-0.01
165	-6.62	-0.01
180	-6.64	0.01
195	-6.65	0.02
210	-6.65	0.02
225	-6.64	0.01
240	-6.64	0.01
255	-6.64	0.02
270	-6.64	0.01
285	-6.64	0.01
300	-6.64	0.01
315	-6.63	0.00
330	-6.64	0.01
345	-6.64	0.01
360	-6.63	0.00
375	-6.65	0.02
390	-6.67	0.04
405	-6.63	0.00
420	-6.63	0.01

TABLE VII (continued)

DATE 10-May-21
 PUMPED WELL: TW2
 OBSERVATION WELL: TW1
 DISTANCE BETWEEN PUMPED
 WELL AND OBSERVATION WELL, r: 45 metres
 PUMPING RATE, Q: 88.9 m³/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-7.07	0
15	-7.39	0.32
30	-7.41	0.34
45	-7.43	0.36
60	-7.44	0.37
75	-7.44	0.37
90	-7.44	0.37
105	-7.45	0.38
120	-7.45	0.38
135	-7.46	0.39
150	-7.46	0.39
165	-7.46	0.39
180	-7.47	0.40
195	-7.47	0.40
210	-7.48	0.40
225	-7.49	0.42
240	-7.49	0.42
255	-7.49	0.42
270	-7.49	0.42
285	-7.49	0.42
300	-7.49	0.42
315	-7.50	0.43
330	-7.50	0.43
345	-7.50	0.43
360	-7.50	0.43
375	-7.19	0.12
390	-7.17	0.10
405	-7.17	0.10
420	-7.17	0.10
435	-7.15	0.08
450	-7.14	0.07
465	-7.14	0.07
480	-7.13	0.06
495	-7.15	0.08
510	-7.14	0.07
525	-7.14	0.07
540	-7.14	0.07
555	-7.13	0.06
570	-7.13	0.06
585	-7.13	0.06
600	-7.13	0.05
615	-7.13	0.06
630	-7.12	0.05
645	-7.12	0.04
660	-7.14	0.07
675	-7.11	0.04
690	-7.10	0.03
705	-7.09	0.02
720	-7.09	0.02
735	-7.08	0.01
750	-7.08	0.01

TABLE VII (continued)

DATE 10-May-21
 PUMPED WELL: TW2
 OBSERVATION WELL: TW3
 DISTANCE BETWEEN PUMPED
 WELL AND OBSERVATION WELL, r:
 PUMPING RATE, Q:

117.6 metres
 88.9 m³/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-4.61	0
15	-4.61	0.00
30	-4.65	0.03
45	-4.61	0.00
60	-4.60	-0.02
75	-4.61	0.00
90	-4.61	0.00
105	-4.61	-0.01
120	-4.60	-0.01
135	-4.61	-0.01
150	-4.62	0.01
165	-4.62	0.01
180	-4.60	-0.01
195	-4.63	0.02
210	-4.64	0.03
225	-4.63	0.02
240	-4.65	0.04
255	-4.64	0.03
270	-4.62	0.01
285	-4.61	0.00
300	-4.61	0.00
315	-4.61	0.00
330	-4.61	0.00
345	-4.60	-0.02
360	-4.60	-0.02
375	-4.59	-0.02
390	-4.60	-0.02
405	-4.60	-0.02
420	-4.61	0.00
435	-4.62	0.01
450	-4.61	0.00
465	-4.61	0.00
480	-4.62	0.00
495	-4.61	0.00

TABLE VII (continued)

DATE 12-May-21
 PUMPED WELL: TW1
 OBSERVATION WELL: TW2
 DISTANCE BETWEEN PUMPED
 WELL AND OBSERVATION WELL, r: 44.6 metres
 PUMPING RATE, Q: 94.3 m³/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-6.73	0
15	-7.02	0.29
30	-7.03	0.30
45	-7.04	0.31
60	-7.04	0.31
75	-7.06	0.33
90	-7.06	0.33
105	-7.06	0.33
120	-7.07	0.34
135	-7.07	0.34
150	-7.07	0.34
165	-7.08	0.35
180	-7.09	0.36
195	-7.10	0.37
210	-7.09	0.36
225	-7.09	0.36
240	-7.09	0.36
255	-7.09	0.36
270	-7.11	0.38
285	-7.11	0.38
300	-7.11	0.38
315	-7.11	0.38
330	-7.12	0.39
345	-7.12	0.39
360	-7.12	0.39
375	-6.80	0.07
390	-6.80	0.06
405	-6.78	0.05
420	-6.78	0.05
435	-6.77	0.04
450	-6.77	0.04
465	-6.76	0.03
480	-6.77	0.04
495	-6.75	0.02
510	-6.77	0.04
525	-6.75	0.02
540	-6.74	0.01
555	-6.73	0.00

TABLE VII (continued)

DATE 12-May-21
 PUMPED WELL: TW1
 OBSERVATION WELL: TW3
 DISTANCE BETWEEN PUMPED
 WELL AND OBSERVATION WELL, r:
 PUMPING RATE, Q:

117.2 metres
 94.3 m³/day

Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
0	-4.65	0
15	-4.66	0.00
30	-4.64	-0.02
45	-4.64	-0.01
60	-4.63	-0.02
75	-4.63	-0.02
90	-4.62	-0.03
105	-4.61	-0.04
120	-4.62	-0.03
135	-4.60	-0.05
150	-4.61	-0.05
165	-4.60	-0.05
180	-4.62	-0.04
195	-4.62	-0.04
210	-4.61	-0.04
225	-4.60	-0.05
240	-4.61	-0.04
255	-4.62	-0.04
270	-4.62	-0.03
285	-4.61	-0.04
300	-4.62	-0.04
315	-4.62	-0.04
330	-4.61	-0.04
345	-4.63	-0.03
360	-4.61	-0.04
375	-4.61	-0.04
390	-4.60	-0.06
405	-4.61	-0.04
420	-4.61	-0.04
435	-4.62	-0.04
450	-4.63	-0.03
465	-4.61	-0.04
480	-4.64	-0.01
495	-4.63	-0.02
510	-4.66	0.01
525	-4.65	0.00

TABLE VIII
ESTIMATE OF STORATIVITY BY COOPER-JACOB METHOD

A curve of drawdown versus time was generated for observation wells as an adjacent well was pumped (see Table 7 and Attachment K)

Based on the Cooper-Jacob formula, the following values of storativity were calculated.

Pump well	Observation Well	r (m)	Q (m ³ /day)	t ₀ (min)	T (m ² /day)	S
TW2	TW1	44.6	88.9	1.4	180.7	2.0E-04
TW1	TW2	44.6	94.3	1.2	288	2.7E-04
						2.4E-04

TABLE IX - BACKGROUND NITROGEN IN SURFICIAL AQUIFER

LOCATION	Units	MW1					
DATE		12-Feb-21	03-Mar-22	17-Jun-22	08-Feb-23	20-Nov-23	28-Feb-24
N-NH3	mg/L	<0.010	<0.010	0.02	<0.020	<0.020	<0.020
TKN	mg/L	0.393	0.737	0.292	0.572	0.674	0.5
N-NO2	mg/L	0.17	0.16	<0.10	0.14	0.19	0.12
N-NO3	mg/L	5.8	19.7	8.11	19.3	18.8	15.6

LOCATION	Units	MW3		
DATE		12-Feb-21	03-Mar-22	20-Nov-23
N-NH3	mg/L	<0.010	0.028	<0.020
TKN	mg/L	0.331	0.397	0.374
N-NO2	mg/L	<0.10	<0.10	<0.10
N-NO3	mg/L	<0.10	<0.10	0.28

LOCATION	Units	MW5			
DATE		12-Feb-21	03-Mar-22	20-Nov-23	28-Feb-24
N-NH3	mg/L	0.031	<0.010	0.047	<0.020
TKN	mg/L	0.245	0.309	0.494	0.31
N-NO2	mg/L	<0.10	<0.10	<0.10	<0.10
N-NO3	mg/L	<0.10	0.72	<0.10	0.34

LOCATION	Units	MW7		MW8		MW9		MW10		MW11	
DATE		20-Nov-23	28-Feb-24	20-Nov-23	28-Feb-24	20-Nov-23	28-Feb-24	20-Nov-23	28-Feb-24	20-Nov-23	28-Feb-24
N-NH3	mg/L	0.023	<0.020	1.11	0.037	0.065	0.087	0.032	0.224	0.208	0.155
TKN	mg/L	0.703	0.676	1.46	0.229	0.503	0.524	0.415	0.806	0.569	0.442
N-NO2	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
N-NO3	mg/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.22	<0.10	<0.10	<0.10	<0.10

TABLE X GROUNDWATER ELEVATIONS-RECEIVING AQUIFER AND WATER SUPPLY AQUIFER

Location	Ground Surface elevation metres	Casing elev metres	Stick up metres	Water Elevations				
				12-Feb-21	03-Mar-22	23-Oct-23	20-Nov-23	27-Feb-24
BH1	92.89	93.85	0.96	92.5	91.33	-	91.38	91.65
BH3	90.39	91.49	1.1	89.25	90.37	-	-	89.69
BH5	91.37	92.50	1.13	89.64	90.13	-	-	90.68
BH7	92.92	93.98	1.06	-	-	91.22	91.36	91.62
BH8	90.87	91.86	0.99	-	-	90.57	90.64	90.4
BH9	91.02	91.91	0.89	-	-	90.82	90.76	90.61
BH10	91.71	92.64	0.93	-	-	90.91	90.82	90.74
BH11	91.83	92.74	0.91	-	-	90.43	-	91.15

KEY PLAN

FIGURE 1



NOT TO SCALE

FIGURE 2

- TW1
- Approximate Water Well Location
- Approximate Borehole (Monitoring Well) Location
- BH1 (MW1)

NOTE: This drawing to be read in conjunction with accompanying report.

2	cv	10/07/25	per Novatech
1	cv	11/01/23	additional MW
REV.	NAME	DATE	DESCRIPTION

 **Kollaard Associates**
Engineers

PO, BOX 189, 210 PRESCOTT ST (613) 860-0923
KEMPTVILLE ONTARIO info@kollaard.ca
K0G 1J0 FAX (613) 258-0475
http://www.kollaard.ca

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION

LOCATION: 3200 REIDS LANE
OSGOODE, ONTARIO

DRAWING: SITE PLAN

DESIGNED BY: — DATE: AUGUST 2021



DRAWN BY: CV SCALE: 1:1000

KOLLAARD FILE NUMBER: 210064



FIGURE 3

BH1 (MW1)

-  Existing Borehole (Well) Location
-  Existing water well Location

NOTE: This drawing to be read in conjunction with accompanying report.

REV.	NAME	DATE	DESCRIPTION



PO, BOX 189, 210 PRESCOTT ST (613) 860-0923
 KEMPTVILLE ONTARIO info@kollaard.ca
 KOG 1J0 FAX (613) 258-0475
 http://www.kollaard.ca

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION


LOCATION: 3200 REIDS LANE
 OSGOODE, ONTARIO

DRAWING: AREA AND SAMPLED WELL LOCATIONS


DESIGNED BY: — DATE: AUGUST 2021

DRAWN BY: CV SCALE: 1:2000

KOLLAARD FILE NUMBER: 210064



CROSS-SECTION KOLLAARD 210064-CROSSSECTION GPJ GINT STD CANADA GDT 21-8-19



NOTE: This drawing to be read in conjunction with accompanying report

SPECIAL NOTE: This drawing was prepared based on our interpretation of the soils present in the boreholes drilled. The information shown on this cross section between borehole locations must not be relied upon for any purpose.

FIGURE 4

- TOPSOIL**
- Yellow brown sand and gravel (FILL)**
- Red brown fine to medium SAND, trace silt**
- Grey fine to medium SAND**
- Grey sandy CLAY, trace silt**
- Grey SILTY SAND**
- Grey SILTY CLAY**
- Grey silty sand, trace to some gravel, cobbles and boulders, trace clay (GLACIAL TILL)**
- LIMESTONE BEDROCK**

Kollaard Associates
Engineers
210 Prescott Street, Unit 1 613-860-0923
P.O. Box 189 info@kollaard.ca
Kemptville, Ontario
K0G 1J0 Fax: 613-258-0475

CLIENT:
Miles Yang

PROJECT:
Proposed Residential Subdivision

LOCATION:
3200 Reids Lane.
Osgoode, Ottawa, Ontario

DRAWING:
East-West Cross Section

DESIGNED BY: CV	DATE: July 2021
DRAWN BY: CI	SCALE: 1:100

PROJECT NUMBER:
210064

CROSS-SECTION KOLLAARD 210064-CROSSSECTION GPJ GINT STD CANADA GDT 21-8-19




FIGURE 5

- TOPSOIL**
- Yellow brown sand and gravel (FILL)**
- Red brown fine to medium SAND, trace silt**
- Grey fine to medium SAND**
- Grey sandy CLAY, trace silt**
- Grey SILTY SAND**
- Grey SILTY CLAY**
- Grey silty sand, trace to some gravel, cobbles and boulders, trace clay (GLACIAL TILL)**
- LIMESTONE BEDROCK**

Kollaard Associates
Engineers
210 Prescott Street, Unit 1 613-860-0923
P.O. Box 189 info@kollaard.ca
Kemptville, Ontario
K0G 1J0 Fax: 613-258-0475

CLIENT:
Miles Yang

PROJECT:
Proposed Residential Subdivision

LOCATION:
3200 Reids Lane.
Osgoode, Ottawa, Ontario


DRAWING:
North-South Cross Section

DESIGNED BY: CV **DATE:** July 2021

DRAWN BY: CI **SCALE:** 1:100

PROJECT NUMBER:
210064

FIGURE 6A



- TW1
- Existing Water Well Location
- BH1
- Approximate Borehole (Monitoring Well) Location
- 91.30
- GW ELEVATION
- ←
- Approximate Receiving Aquifer Flow Direction

NOTE: This drawing to be read in conjunction with accompanying report.

REV.	NAME	DATE	DESCRIPTION

K Kollaard Associates
Engineers

PO, BOX 189, 210 PRESCOTT ST (613) 860-0923
KEMPTVILLE ONTARIO info@kollaard.ca
KOG 1J0 FAX (613) 258-0475
http://www.kollaard.ca

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION

LOCATION: 3200 REIDS LANE
OSGOODE, ONTARIO


DRAWING: INTERPRETED GROUNDWATER FLOW RECEIVING AQUIFER

DESIGNED BY: DATE: APRIL 2024

DRAWN BY: CV SCALE: 1:1000

KOLLAARD FILE NUMBER: 210064

FIGURE 6B



- TW1
- Existing Water Well Location
- BH1 (MW1)
- Approximate Borehole (Monitoring Well) Location
- 91.30 GW ELEVATION
- Approximate Water Supply Aquifer Flow Direction

NOTE: This drawing to be read in conjunction with accompanying report.

REV.	NAME	DATE	DESCRIPTION

Kollaard Associates
Engineers

PO, BOX 189, 210 PRESCOTT ST (613) 860-0923
KEMPTVILLE ONTARIO info@kollaard.ca
K0G 1J0 FAX (613) 258-0475
http://www.kollaard.ca

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION

LOCATION: 3200 REIDS LANE
OSGOODE, ONTARIO


DRAWING: INTERPRETED GROUNDWATER FLOW
WATER SUPPLY AQUIFER


DESIGNED BY: — DATE: AUGUST 2021


DRAWN BY: CV SCALE: 1:1000


KOLLAARD FILE NUMBER: 210064

FIGURE 7

TW1
 Approximate Water Well Location

 Proposed Water Well Location

 Proposed sewage system

 Proposed house

NOTE: This drawing to be read in conjunction with accompanying report.

2	CV	07/24	revised per Novatech
1	CV	02/23	setback distances
REV.	NAME	DATE	DESCRIPTION

 **Kollaard Associates**
Engineers

PO, BOX 189, 210 PRESCOTT ST (613) 860-0923
 KEMPTVILLE ONTARIO info@kollaard.ca
 K0G 1J0 FAX (613) 258-0475
 http://www.kollaard.ca

CLIENT: MILES YANG

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION

LOCATION: 3200 REIDS LANE
OSGOODE, ONTARIO

DRAWING: LOT DEVELOPMENT PLAN

DESIGNED BY: - DATE: AUGUST 2021

DRAWN BY: CV SCALE: 1:1000

KOLLAARD FILE NUMBER: 210064







ATTACHMENT A

SURFICIAL AND BEDROCK GEOLOGY MAPS

BEDROCK GEOLOGY MAP




Ontario Geological Survey of Ontario, Bedrock Geology Map MRD 126-REV1, issued 2011

 **Oxford Formation (Beekmantown Group):**
Primary Lithology: dolostone
brown-grey to green-grey, thin- to thick-bedded,
very fine- to medium-grained dolostone; with
local thin glauconitic shale beds, and interbeds
of quartz sandstone and shaly dolostone

Project No. 210064

Date June 2024

SURFICIAL GEOLOGY MAP



	Coarse-textured glaciomarine deposits: sand, gravel, minor silt and clay		Glaciofluvial Deposits: river deposits and delta topset facies
	Till: Silty sand to sand-textured till on Precambrian terrain		Organic Deposits: Peat, muck, marl


Ontario Geological Survey of Ontario, Bedrock Geology Map MRD 128-REV, issued 2010



ATTACHMENT B

CERTIFICATE OF WELL COMPLIANCES AND MOE WATER WELL RECORDS FOR TEST
WELLS AND AREA WELL RECORDS

REGIONAL WELLS MAP



NOT TO SCALE



Kollaard Associates
Engineers

Project No. 210064

Date July 2025



Well Tag#: **A318366** (Below)
A318366

Measurements recorded in: Metric Imperial

Page _____ of _____

Well Owner's Information

First Name _____ Last Name/Organization **Crestview Innovation Inc.** E-mail Address _____ Well Constructed by Well Owner

Mailing Address (Street Number/Name) **12 Escade Drive** Municipality **Ottawa** Province **ON** Postal Code **K2G 6R9** Telephone No. (inc. area code) _____

Well Location

Address of Well Location (Street Number/Name) **3200 Reids Lane** Township **Osgode** Lot **P/L 27+28 1** Concession _____

County/District/Municipality **Ottawa Carleton** City/Town/Village **Osgoode** Province **Ontario** Postal Code _____

UTM Coordinates: Zone **18** Easting **452113** Northing **4999346** Municipal Plan and Sublot Number **4R-20040 (Parts 4+5)** Other **TW# 1**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)
				From To
	Sand	Cobble		0' 25'
	Clay			25' 38'
	Gravel		(Packed)	38' 56'
Grey	Limestone			56' 180'
Grey	Limestone	w/ Grey Sandstone Mix		180' 244'
Grey	Limestone	w/ Grey Sandstone Mix		244' 250'

* Test Well # 1 of 3 *

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
66' 56'	Neat cement	9.36
56' 0'	Bentonite slurry	21

Results of Well Yield Testing

After test of well yield, water was:	Draw Down	Recovery
<input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: X	Static Level	30.2'
	1	27.9
	2	28.9
	3	29.2
	4	29.4
	5	29.5
Pump intake set at (m/ft) 240		
Pumping rate (l/min/GPM) 20		
Duration of pumping 1 hrs + 0 min		
Final water level end of pumping (m/ft) 30.2'		
If flowing give rate (l/min/GPM) X		
Recommended pump depth (m/ft) 140'		
Recommended pump rate (l/min/GPM) 20		
Well production (l/min/GPM) 20		
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial
 Other, specify **As Subject**

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	Status of Well
			From To	
6 1/4"	Steel	.188"	+2' 86'	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify
6"	Open Hole		66' 250'	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)
			From To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
244 (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify			
		0' 66'	9 3/4"
		66' 250'	6"

Well Contractor and Well Technician Information


Business Name of Well Contractor **Air Rock Drilling Co. Ltd.** Well Contractor's Licence No. **7681**

Business Address (Street Number/Name) **6659 Franktown Road** Municipality **Richmond**

Province **ON** Postal Code **K0A 2Z0** Business E-mail Address **air-rock@sympatico.ca**

Bus. Telephone No. (inc. area code) **8138382170** Name of Well Technician (Last Name, First Name) **Hanna, Jeremy**

Well Technician's Licence No. **T3632** Signature of Technician and/or Contractor _____ Date Submitted **2021 05 31**



Comments: **1/2 HP - 10 GPM Set @ 140 ft**

Well owner's information package delivered Yes No

Date Package Delivered **2021 04 27** Date Work Completed **2021 04 28**

Ministry Use Only
 Audit No. **2355079**
 Received _____

CERTIFICATE OF WELL COMPLIANCE



I (Jeremy Hanna) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION INC.

Location: # 3200 REIDS LANE, Osgoode
Part 27
LOT: 228 CON: 1 PLAN # 4R-20040 SITE # Part 415

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 26th Day of APRIL, 2021

Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11th day of May, 2021

(Engineer)

TAG A 318366
TW# 1 of 3
2021241

Shaping our future together
Ensemble, formons notre avenir

City of
Client 5
8743 Vir



Kollaard Associates

Engineers
P.O. Box 189
210 Prescott Street, Unit 1
Kemptville, Ontario K0G 1J0



Measurements recorded in: Metric Imperial

Page ___ of ___

Well Owner's Information

First Name: _____ Last Name/Organization: **Crestview Innovation Inc.** E-mail Address: _____ Well Constructed by Well Owner

Mailing Address (Street Number/Name): **12 Escade Drive** Municipality: **Ottawa** Province: **ON** Postal Code: **K2G 6R9** Telephone No. (inc. area code): _____

Well Location

Address of Well Location (Street Number/Name): **3200 Reids Lane** Township: **Osgoode** Lot: **P/L 27428 1** Concession: _____

County/District/Municipality: **Ottawa Carleton** City/Town/Village: **Osgoode** Province: **Ontario** Postal Code: _____

UTM Coordinates: Zone: **18** Easting: **452078** Northing: **4999307** Municipal Plan and Sublot Number: **4R-20040 (Parts 4+5)** Other: **TW#2**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)
From	To			From To
	Sand & Gravel	Boulders & Clay, Gravel		0' 52'
Grey & Black	Limestone			52' 180'
Grey & Black	Limestone	w/ Gray & White Sandstone Mix		180' 238'
Grey & Black	Limestone	w/ Gray & White Sandstone Mix		238' 244'

* Test Well #2 of 3 *

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
52' / 52'	Neat cement	10.9
52' / 0'	Bentonite slurry	21

Results of Well Yield Testing

After test of well yield, water was:
 Clear and sand free
 Other, specify **Not tested**

If pumping discontinued, give reason: _____

Draw Down	Recovery		
Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
	Static Level: 22.5'		27.8'
1	26.7	1	22.5
2	27.2	2	22.5
3	27.5	3	
4	27.6	4	
5	27.7	5	
10	27.7	10	
15	27.7	15	
20	27.8	20	
25	27.8	25	
30	27.8	30	
40	27.8	40	
50	27.8	50	
60	27.8	60	

Pump intake set at (ft): **220**

Pumping rate (l/min/GPM): **20**

Duration of pumping: **1** hrs + **0** min

Final water level end of pumping (m/ft): **27.8**

If flowing give rate (l/min/GPM): **X**

Recommended pump depth (m/ft): **140'**

Recommended pump rate (l/min/GPM): **20**

Well production (l/min/GPM): **20**

Abandoned? Yes No

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify _____

Construction Record - Casing

Inside Diameter (m/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
6 1/4"	Steel	.188"	+2'	62'	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
6"	Open Hole		62'	244'	

Construction Record - Screen

Outside Diameter (m/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Hole Diameter	
		Depth (m/ft)	Diameter (m/in)
		From	To
238'		0' 62'	9 3/4"
		62' 244'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: **Air Rock Drilling Co. Ltd.** Well Contractor's Licence No.: **7681**

Business Address (Street Number/Name): **655 Franktown Road** Municipality: **Richmond**

Province: **ON** Postal Code: **K0A 2Z0** Business E-mail Address: **air-rock@sympatico.ca**

Bus. Telephone No. (inc. area code): **8138382170** Name of Well Technician (Last Name, First Name): **Hanna, Jeremy**

Well Contractor's Licence No.: **13532** Signature of Technician and/or Contractor: _____ Date: **2021** Dec **05** 31

Map of Well Location

Please provide a map below following instructions on the back.

Comments: **1/2 HP 10 GPM set @ 140 FT**

Well owner's information package delivered: Yes No

Date Package Delivered: **2021** Nov **29**

Date Work Completed: **2021** Oct **27**

Ministry Use Only: Audit No. **2355078**

Received: _____

CERTIFICATE OF WELL COMPLIANCE



I (Jeremy Hanna) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION INC.

Location: # 3200 REIDS LANE, Osgoode

Part 27
LOT: 28 CON: 1 PLAN # 4R-20040 SITE # Part 415

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 27TH Day of APRIL, 2021

Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11th day of May, 2021,

TAG A318392
TW#2 of 3
2021242

(Engineer)

Shaping our future together
Ensemble, formons notre avenir

City of Ottawa
Client Service Centre
8263 Victoria Street



Kollaard Associates

Engineers
P.O. Box 189
210 Prescott Street, Unit 1
Kemptville, Ontario K0G 1J0



CERTIFICATE OF WELL COMPLIANCE



I (**Jeremy Hanna**) AIR ROCK DRILLING CO. LTD. - DO HEREBY CERTIFY

that I am licensed to drill water wells in the Province of Ontario, and that I have supervised the drilling of the water well on the property of :

OWNER: CRESTVIEW INNOVATION INC.

Location: # 3200 REIDS LANE, Osgoode

Part 27
LOT: 228 CON: 1 PLAN # 4R-20040 SITE # Part 415

Ottawa-Carleton / Geographical Township of Osgoode

I CERTIFY FURTHER that, I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to this site and City Standards.

AND DO HEREBY CERTIFY THAT the said well has been drilled, cased, grouted (cement or bentonite) as applicable and constructed in strict conformity with the standards required.

Signed this 26th Day of APRIL, 2021

Jeremy Hanna (T3632)

Air Rock Drilling Co. Ltd. (C-7681)

The Engineer on behalf of the Landowner set out above, Certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O.Reg 903, this report and the Hydrogeological Report with regards to casing length and grouting requirements.

Signed this 11th day of May, 2021

(Engineer)

TAG A318365
TW# 2 of 3
2021240.

Shaping our future together
Ensemble, formons notre avenir

City of Ottawa
Client Services
8243 Victoria



Kollaard Associates

Engineers
P.O. Box 189
210 Prescott Street, Unit 1
Kemptville, Ontario K0G 1J0



Measurements recorded in: Metric Imperial

Page ___ of ___

Well Owner's Information

First Name: Last Name/Organization: Crestview Innovation Inc. E-mail Address: Well Constructed by Well Owner

Mailing Address (Street Number/Name): 12 Escade Drive Municipality: Ottawa Province: ON Postal Code: K2G 6R9 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): 3200 Reids Lane Township: Osgoode Lot: P/L 27-28-1 Concession:

County/District/Municipality: Ottawa Carleton City/Town/Village: Osgoode Province: Ontario Postal Code:

UTM Coordinates: Zone: Easting: Northing: Municipal Plan and Sublot Number: Other: (Parts 4+5) TW3

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m) From, To. Includes handwritten note: *Test Well # 3 of 3*

Annular Space table with columns: Depth Set at (m) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/H)

Results of Well Yield Testing table with columns: Draw Down (min), Water Level (m/ft), Recovery (min), Water Level (m/ft). Includes handwritten notes and a graph.

Method of Construction and Well Use table with checkboxes for Cable Tool, Rotary, Boring, etc.

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material, Wall Thickness (cm/in), Depth (m/ft) From, To.

Construction Record - Screen table with columns: Outside Diameter (m/in), Material, Slot No., Depth (m/ft) From, To.

Water Details and Hole Diameter table with columns: Water found at Depth (m/ft), Kind of Water, Hole Diameter (Depth, Diameter).


Well Contractor and Well Technician Information: Business Name of Well Contractor: Air Rock Drilling Co. Ltd. Well Contractor's Licence No.: 7681

Business Address (Street Number/Name): 6659 Franktown Road Municipality: Richmond

Province: ON Postal Code: K0A 2Z0 Business E-mail Address: air-rock@sympatico.ca

Bus. Telephone No. (inc. area code): 6138382170 Name of Well Technician (Last Name, First Name): Hanna, Jeremy

Well Technician's Licence No.: 13632 Signature of Technician and/or Contractor: Date Submitted: 05 31



Comments: 1/2 HR 10 GPM @ 80 ft

Ministry Use Only table with columns: Well owner's Information package delivered, Date Package Delivered, Date Work Completed, Audit No.: 2355080

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1533843

Municipality 15009

Con. CON

OTTAWA-CARLETON

County or District: **Carleton**
 Township/Borough/City/Town/Village: **OSGOODE (Ottawa)**
 Con block tract survey, etc.: **1 Plan 393**
 Lot: **46 & 47**
 Address: **5503 OSGOODE Main St.**
 Date completed: **9 day of 03**

21
 10 12 17 18 24 25 26 30 31 47

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown Sand			Packed	0	14
Grey Clay			thick	14	30
Grey Clay & stones			HARD Pan	30	50
Grey Limestone			MED HARD	50	80
54' of 6 1/4" casing 1 DRIVE SHOE 1 WELL CAP 2 Bags of Bentonite Quick Grout					

31
 32
 10 14 15 21 32 43 54 65 75 80


41 WATER RECORD	
Water found at - feet	Kind of water
68 ¹³	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty 3 <input checked="" type="checkbox"/> Sulphur 4 <input checked="" type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas
15-18	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty 3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas
20-23	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty 3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas
25-28	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty 3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas
30-33	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty 3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic	.188	0	53 ¹⁶
6"	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic		53	80
17-18	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			20-23
24-25	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			27-30

Sizes of opening (Slot No.)	Diameter inches	Length feet
Material and type		Depth at top of screen feet

61 PLUGGING & SEALING RECORD		
<input checked="" type="checkbox"/> Annular space		<input type="checkbox"/> Abandonment
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)
From	To	
0	53	Bentonite Quick Grout
18-21	22-25	
26-29	30-33	

71 PUMPING TEST	
Pumping test method 1 <input type="checkbox"/> Pump 2 <input checked="" type="checkbox"/> Bailer	Pumping rate 12 GPM
Static level 26 feet	Water level end of pumping 60 feet
Water levels during 15 minutes: 40 feet 30 minutes: 60 feet 45 minutes: 60 feet 60 minutes: 60 feet	Duration of pumping 1 Hours
If flowing give rate GPM	Pump intake set at 70 feet
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Water at end of test <input checked="" type="checkbox"/> Clear <input type="checkbox"/> Cloudy
	Recommended pump setting 70 feet
	Recommended pump rate 10 GPM



54 FINAL STATUS OF WELL

1 Water supply
 2 Observation well
 3 Test hole
 4 Recharge well
 5 Abandoned, insufficient supply
 6 Abandoned, poor quality
 7 Abandoned (Other)
 8 Dewatering
 9 Unfinished
 10 Replacement well

55-56 WATER USE

1 Domestic
 2 Stock
 3 Irrigation
 4 Industrial
 5 Commercial
 6 Municipal
 7 Public supply
 8 Cooling & air conditioning
 9 Not use
 10 Other

57 METHOD OF CONSTRUCTION

1 Cable tool
 2 Rotary (conventional)
 3 Rotary (reverse)
 4 Rotary (air)
 5 Air percussion
 6 Boring
 7 Diamond
 8 Jetting
 9 Driving
 10 Digging
 11 Other

OSGOODE Main St.
 George St.
 244318

Name of Well Contractor: **B. MOORE WELL DRILLING 6455**
 Well Contractor's Licence No.: **6455**
 Address: **Box 436 OSGOODE ON. K0A 2W0**
 Name of Well Technician: **BOB MOORE**
 Well Technician's Licence No.: **7-0319**
 Signature of Technician/Contractor: **BOB MOORE**
 Submission date: **9 day of 03**

MINISTRY USE ONLY

Data source: **6455**
 Contractor: **6455**
 Date received: **JUN 10 2003**
 Date of inspection: _____
 Inspector: _____
 Remarks: _____

CSS.ES3

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: Baresite Construction Last Name / Organization: Baresite Construction E-mail Address: _____ Well Constructed by Well Owner

Mailing Address (Street Number/Name): 2354 Summerside Drive Municipality: Manotick Province: ON Postal Code: K4M 1B4 Telephone No. (inc. area code): 613 457 4422

Well Location

Address of Well Location (Street Number/Name): 5572 Lombardy Drive Township: Osgoode Lot: pt 1+2+22 Concession: 3715171

County/District/Municipality: Ottawa City/Town/Village: Osgoode Province: Ontario Postal Code: _____

UTM Coordinates: Zone 18 Easting 452172 Northing 4999621 Municipal Plan and Sublot Number: RP4R-14828 pt lot #32+33 on Plan 4m.830 Other: _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Fill		Soft	0	2'
Black	Topsoil		Soft	2'	3'
Grey	Sand, Stones		Packed	3'	54'6"
Grey	Limestone		Hard	54'6"	101'

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
From: 59'6" To: 49'6"	Cement Pressure Grouted	13.54
From: 49'6" To: 0	Bentonite Pressure Grouted	20.31

Results of Well Yield Testing

After test of well yield, water was:	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Static Level	15.6		16.3
If pumping discontinued, give reason:	1	15.7	1	15.9
	2	15.7	2	15.9
Pump intake set at (m/ft): <u>90'</u>	3	15.8	3	15.9
Pumping rate (l/min / GPM): <u>19 gpm</u>	4	15.8	4	15.8
Duration of pumping: <u>1 hrs + 0 min</u>	5	15.9	5	15.8
Final water level end of pumping (m/ft): <u>16.3</u>	10	15.9	10	15.7
If flowing give rate (l/min / GPM):	15	16.0	15	15.7
	20	16.1	20	15.7
Recommended pump depth (m/ft): <u>80'</u>	25	16.2	25	15.6
Recommended pump rate (l/min / GPM): <u>10 gpm</u>	30	16.2	30	↓
Well production (l/min / GPM):	40	16.1	40	
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <u>165</u>	50	16.1	50	
	60	16.3	60	

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify _____
 Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
97/8"	Mud		0	59'6"	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
6 1/4"	Steel	.188	0	59'6"	
6 1/8"	Open Hole		59'6"	101'	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water:	Hole Diameter	
	<input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
75' (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		From	To
Water found at Depth: 93' (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		0	59'6" 97/8"
Water found at Depth: (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		59'6"	101' 6 1/8"

Well Contractor and Well Technician Information

Business Name of Well Contractor: 1425486 Ontario Ltd. of a Splash Well Drilling Well Contractor's Licence No.: 4877


Business Address (Street Number/Name): PO BOX 1083 Municipality: Prescott

Province: ON Postal Code: K0E1T0 Business E-mail Address: _____

Bus. Telephone No. (inc. area code): 613/925 4885 Name of Well Technician (Last Name, First Name): Ferguson, Todd

Well Technician's Licence No.: TA 78 Signature of Technician and/or Contractor: Todd Ferguson Date Submitted: 2014/05/30

Map of Well Location



Comments: 165 Chlorine after Drilling & Chlorine after Yield Test

Well owner's information package delivered: Yes No

Date Package Delivered: 2014/05/18 Date Work Completed: 2014/05/08

Ministry Use Only

Audit No.: Z 176050

Received: JUN 19 2014



Measurements recorded in: Metric Imperial

Tag#: A193395

Page of

Well Owner's Information

First Name, Last Name / Organization, E-mail Address, Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number, Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Method of Construction and Well Use checkboxes: Cable Tool, Rotary (Conventional/Reverse), Boring, Air percussion, Diamond, Jetting, Driving, Digging, Public, Commercial, Not used, Domestic, Municipal, Dewatering, Livestock, Test Hole, Monitoring, Irrigation, Cooling & Air Conditioning, Industrial, Other, specify

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel), Wall Thickness (cm/in), Depth (m/ft) From, To, Status of Well

Construction Record - Screen table with columns: Outside Diameter (cm/in), Material (Plastic, Galvanized, Steel), Slot No., Depth (m/ft) From, To

Water Details and Hole Diameter tables

Well Contractor and Well Technician Information: Business Name of Well Contractor, Well Contractor's Licence No., Business Address, Municipality, Province, Postal Code, Business E-mail Address, Bus. Telephone No. (inc. area code), Name of Well Technician (Last Name, First Name), Well Technician's Licence No., Signature of Technician and/or Contractor, Date Submitted

Results of Well Yield Testing table with columns: Draw Down (Time, Water Level), Recovery (Time, Water Level), Pump intake set at (m/ft), Pumping rate (l/min / GPM), Duration of pumping, Final water level end of pumping (m/ft), If flowing give rate (l/min / GPM), Recommended pump depth (m/ft), Recommended pump rate (l/min / GPM), Well production (l/min / GPM), Disinfected?

Map of Well Location: Please provide a map below following instructions on the back. Includes a hand-drawn map of Lombardy Drive with well location marked #5566, dimensions 80' x 80', and a north arrow. Comments: 140 Chlorine after Drilling & Chlorine after Yield Test. Well owner's information package delivered: 2016/11/06, Date Work Completed: 2016/10/27. Ministry Use Only: Audit No. 2242999, NOV 18 2016 Received.



Measurements recorded in: Metric Imperial

Tag# A193411

Page ___ of ___

Well Owner's Information

First Name, Last Name / Organization, E-mail Address, Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space

Table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Results of Well Yield Testing

Table with columns: After test of well yield, water was, Draw Down (Time, Water Level), Recovery (Time, Water Level), Pumping rate, Duration of pumping, Final water level end of pumping, Recommended pump depth, Recommended pump rate, Well production, Disinfected?

Method of Construction

Well Use

Checkboxes for Method of Construction (Cable Tool, Rotary, Boring, etc.) and Well Use (Public, Commercial, Domestic, etc.)

Construction Record - Casing

Status of Well

Table with columns: Inside Diameter (cm/in), Open Hole OR Material, Wall Thickness (cm/in), Depth (m/ft) From, To, Status of Well (Water Supply, Replacement Well, etc.)

Construction Record - Screen

Table with columns: Outside Diameter (cm/in), Material, Slot No., Depth (m/ft) From, To

Water Details


Hole Diameter

Table with columns: Water found at Depth, Kind of Water, Hole Diameter (Depth, Diameter)

Well Contractor and Well Technician Information

Business Name of Well Contractor, Well Contractor's Licence No., Business Address, Municipality, Province, Postal Code, Business E-mail Address, Bus. Telephone No., Name of Well Technician, Well Technician's Licence No., Signature of Technician and/or Contractor, Date Submitted

Map of Well Location



Comments: 145 Chlorine after Drilling, 4 Chlorine after Yield Test. Well owner's information package delivered, Date Package Delivered, Date Work Completed, Ministry Use Only (Audit No. 2243019, Received)

Measurements recorded in: Metric Imperial

Tag# A193412

Page _____ of _____

Well Owner's Information

First Name <i>Beresite Construction</i>	Last Name / Organization <i>Beresite Construction</i>	E-mail Address	<input type="checkbox"/> Well Constructed by Well Owner
Mailing Address (Street Number/Name) <i>2354 Summerside Drive Manotick ON</i>		Municipality <i>Manotick</i>	Province <i>ON</i>
		Postal Code <i>K1M1B4</i>	Telephone No. (inc. area code) <i>61337151711</i>

Well Location

Address of Well Location (Street Number/Name) <i>5554 Lombardy Drive</i>		Township <i>Osacode</i>	Lot <i>pt lot 31 Plan 4m-830</i>	Concession
County/District/Municipality <i>Ottawa</i>		City/Town/Village <i>Osacode</i>	Province Ontario	Postal Code <i>K0A0W0</i>
UTM Coordinates <i>NAD 83</i>	Zone <i>18</i>	Easting <i>10452066</i>	Northing <i>4999583</i>	Municipal Plan and Sublot Number <i>Part 5116 RP43-14828</i>

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Clay		Packed	0	8'
Brown	Sand		Packed	8'	15'
Grey	Sand	Gravel	Packed	15'	51'6"
Grey	Limestone		Hard	51'6"	121'

Annular Space		
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
51'6" 46'6"	Cement Pressure Grouted	6.77
46'6" 0	Bentonite Pressure Grouted	13.54

Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input checked="" type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	
<input type="checkbox"/> Other, specify _____		<input type="checkbox"/> Other, specify _____	

Construction Record - Casing			Status of Well		
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		
			From	To	
97/8"	Mud (Open Hole)		0	56'6"	<input checked="" type="checkbox"/> Water Supply
6 1/4"	Steel	0.188	0	56'6"	<input type="checkbox"/> Replacement Well
6 1/8"	Open Hole		56'6"	121'	<input type="checkbox"/> Test Hole


Construction Record - Screen					
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)		
			From	To	
					<input type="checkbox"/> Recharge Well
					<input type="checkbox"/> Dewatering Well
					<input type="checkbox"/> Observation and/or Monitoring Hole
					<input type="checkbox"/> Alteration (Construction)
					<input type="checkbox"/> Abandoned, Insufficient Supply
					<input type="checkbox"/> Abandoned, Poor Water Quality
					<input type="checkbox"/> Abandoned, other, specify _____
					<input type="checkbox"/> Other, specify _____

Water Details		Hole Diameter	
Water found at Depth <i>115' (m/ft)</i>	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
		From	To
Water found at Depth <i>(m/ft)</i>	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	0	56'6" 97/8"
Water found at Depth <i>(m/ft)</i>	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	56'6"	121' 6 1/8"

Well Contractor and Well Technician Information		
Business Name of Well Contractor <i>14254860 Ontario Ltd Classical Well Drilling</i>	Well Contractor's Licence No. <i>4181717</i>	
Business Address (Street Number/Name) <i>PO BOX 1083</i>	Municipality <i>Prescott</i>	
Province <i>ON</i>	Postal Code <i>K0A0W0</i>	Business E-mail Address

Bus. Telephone No. (inc. area code) <i>613912541825</i>	Name of Well Technician (Last Name, First Name) <i>Ferawan, Johnathon</i>	
Well Technician's Licence No. <i>2181519</i>	Signature of Technician and/or Contractor	Date Submitted <i>2016/11/30</i>

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input checked="" type="checkbox"/> Clear and sand free		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input type="checkbox"/> Other, specify _____					
If pumping discontinued, give reason:		Static Level			
Pump intake set at (m/ft) <i>110'</i>		1	21.05	1	50.85
Pumping rate (l/min / GPM) <i>7 gpm</i>		2	23.15	2	45.7
Duration of pumping <i>1 hrs + 0 min</i>		3	25.2	3	42.4
Final water level end of pumping (m/ft) <i>56.4</i>		4	27	4	39.3
If flowing give rate (l/min / GPM)		5	28.65	5	36
		10	35	10	23.4
		15	39.5	15	18.3
		20	43	20	17.6
Recommended pump depth (m/ft) <i>110'</i>		25	45.8	25	17.05
Recommended pump rate (l/min / GPM) <i>7 gpm</i>		30	47.5	30	17.025
Well production (l/min / GPM)		40	52.8	40	17
Disinfected?		50	54.85	50	17
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>140</i>		60	56.4	60	16.975


 Comments:
*140 Chlorine after Drilling
 & Chlorine after Yield Test*

Well owner's information package delivered	Date Package Delivered	Ministry Use Only	
<input checked="" type="checkbox"/> Yes	<i>2016/11/30</i>	Audit No.	<i>2243020</i>
<input type="checkbox"/> No	Date Work Completed <i>2016/11/30</i>	Received	<i>DEC 1 2016</i>

31G/4h



GROUND WATER BRANCH
15 No 7116
MAY 21 1963
ONTARIO WATER RESOURCES COMMISSION

UTM 118Z 452110E

5R 491910810N

Elev. 4R 10310

The Ontario Water Resources Commission Act

WATER WELL RECORD

Basin 25 | |
County or District Carleton Place

Township, Village, Town or City Osgoode

Con. I P.1 Lot 28

Date completed 2 Feb 63
(day month year)

Owner Coady Constr Co
(print in block letters)

Address 220 Ellendale Cres
Ottawa

Casing and Screen Record

Inside diameter of casing 5"
Total length of casing 62'
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 5"

Pumping Test

Static level 31
Test-pumping rate 8 G.P.M.
Pumping level 60
Duration of test pumping 1 hr
Water clear or cloudy at end of test cloudy
Recommended pumping rate 8 G.P.M.
with pump setting of 75 feet below ground surface

Well Log

Overburden and Bedrock Record

sand
clay
hardpan
blue limestone

Water Record

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
0	20'	100	fresh
20	36'	120	fresh
36	59	131	"
59	133		

For what purpose(s) is the water to be used?

Post office

Is well on upland, in valley or on hillside? upland

Drilling or Boring Firm Capital Water Supply

Address 1243 Heron Rd

Licence Number 482 976

Name of Driller or Borer S Huff


Address

Date 4 Feb 1963

Walter Kavanagh
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



31G/4h



GROUND WATER BRANCH
15 No 7116
MAY 21 1963
ONTARIO WATER RESOURCES COMMISSION

UTM 118Z 452110E

5R 491910810N

Elev. 4R 10310

The Ontario Water Resources Commission Act

WATER WELL RECORD

Basin 25 | |
County or District Carleton Place

Township, Village, Town or City Osgoode

Con. I P.1 Lot 28

Date completed 2 Feb 63
(day month year)

Owner Coady Constr Co
(print in block letters)

Address 220 Ellendale Cres
Ottawa

Casing and Screen Record

Inside diameter of casing 5"
Total length of casing 62'
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 5"

Pumping Test

Static level 31
Test-pumping rate 8 G.P.M.
Pumping level 60
Duration of test pumping 1 hr
Water clear or cloudy at end of test cloudy
Recommended pumping rate 8 G.P.M.
with pump setting of 75 feet below ground surface

Well Log

Overburden and Bedrock Record

sand
clay
hardpan
blue limestone

Water Record

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
0	20'	100	fresh
20	36'	120	fresh
36	59	131	"
59	133		

For what purpose(s) is the water to be used?

Post office

Is well on upland, in valley or on hillside? upland

Drilling or Boring Firm Capital Water Supply

Address 1243 Heron Rd

Licence Number 482 976


Name of Driller or Borer S Huff

Date 4 Feb 1963

Walter Kavanagh
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1533843

Municipality 15009

Con. CON

OTTAWA-CARLETON

County or District: **Carleton**
 Township/Borough/City/Town/Village: **OSGOODE (Ottawa)**
 Con block tract survey, etc.: **1 Plan 393**
 Lot: **46 & 47**
 Address: **5503 OSGOODE Main St.**
 Date completed: **9 day of 03 month year**

21

Northings: 10, 12, 17, 18, 24, 25, 26, 30, 31, 47

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown Sand			Packed	0	14
Grey Clay			thick	14	30
Grey Clay & stones			HARD Pan	30	50
Grey Limestone			MED HARD	50	80
54' of 6 1/4" casing 1 DRIVE SHOE 1 WELL CAP 2 Bags of Bentonite Quick Grout					

31

32


41 WATER RECORD	
Water found at - feet	Kind of water
68 ¹³	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input checked="" type="checkbox"/> Sulphur <input checked="" type="checkbox"/> Minerals <input type="checkbox"/> Gas
15-18	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
20-23	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
25-28	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
30-33	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4"	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic	.188	0	53
6"	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic		53	80
17-18	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			20-23
24-25	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			27-30

Sizes of opening (Slot No.)	Diameter inches	Length feet
Material and type		Depth at top of screen feet

61 PLUGGING & SEALING RECORD		
<input checked="" type="checkbox"/> Annular space		<input type="checkbox"/> Abandonment
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)
From	To	
0	53	Bentonite Quick Grout
18-21	22-25	
26-29	30-33	

71 PUMPING TEST	
Pumping test method <input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailer	Pumping rate 12 GPM
Static level 26 feet	Water level end of pumping 60 feet
Water levels during <input checked="" type="checkbox"/> Pumping	2 Recovery
15 minutes 40 feet	30 minutes 60 feet
45 minutes 60 feet	60 minutes 60 feet
If flowing give rate	Pump intake set at
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Recommended pump setting 70 feet
	Water at end of test <input checked="" type="checkbox"/> Clear <input type="checkbox"/> Cloudy
	Recommended pump rate 10 GPM



54 FINAL STATUS OF WELL

Water supply
 Observation well
 Test hole
 Recharge well

Abandoned, insufficient supply
 Abandoned, poor quality
 Abandoned (Other)
 Dewatering

Unfinished
 Replacement well

55-56 WATER USE

Domestic
 Stock
 Irrigation
 Industrial

Commercial
 Municipal
 Public supply
 Cooling & air conditioning

Not use
 Other

57 METHOD OF CONSTRUCTION

Cable tool
 Rotary (conventional)
 Rotary (reverse)
 Rotary (air)

Air percussion
 Boring
 Diamond
 Jetting

Driving
 Digging
 Other

Name of Well Contractor: **B. MOORE WELL DRILLING 6455**
 Well Contractor's Licence No.: **6455**
 Address: **Box 436 OSGOODE ON. K0A 2W0**
 Name of Well Technician: **BOB MOORE**
 Well Technician's Licence No.: **7-0319**
 Signature of Technician/Contractor: **BOB MOORE**
 Submission date: **9 day 01 month 03 year**

MINISTRY USE ONLY

Data source: **6455**
 Contractor: **6455**
 Date received: **JUN 10 2003**

Date of inspection: _____
 Inspector: _____

Remarks: _____

CSS.ES3

Measurements recorded in: Metric Imperial

Well Owner's Information

5502 Osgoode Main
County/District/Municipality: Osgoode
City/Town/Village: Osgoode
23
Province: Ontario
Postal Code: K0A 2W0
Ottawa
UTM Coordinates: Zone Easting Northing
NAD 83 18 452037 499 1220
Municipal Plan and Sublot Number: Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Sand		Hard	0	2.5
Yellow	Coarse Sand		Soft	2.5	9.7
Grey	clay		Soft	9.7	13.5
Grey	gravel		packed	13.5	14.9
Grey	limestone		layered	14.9	24.3

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
0 to 6	ciment grout	4 Bag

Results of Well Yield Testing

After test of well yield, water was:	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify				
If pumping discontinued, give reason:	Static Level	2.80		8.51
Pump intake set at (m/ft): 19	1	8.08	1	8.08
Pumping rate (l/min / GPM): 56	2	8.07	2	7.94
Duration of pumping: 1 hrs + min	3	8.19	3	7.83
Final water level end of pumping (m/ft): 8.51	4	8.25	4	7.81
If flowing give rate (l/min / GPM): 80	5	8.30	5	7.80
Recommended pump depth (m/ft): 19	10	8.41	10	7
Recommended pump rate (l/min / GPM): 56	15	8.47	15	
Well production (l/min / GPM): 80	20	8.47	20	
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	25	8.47	25	
	30	8.48	30	
	40	8.48	40	
	50	8.50	50	
	60	8.51	60	

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
1555	Steel	.48	4.60	14.9	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify
1555	Open Hole		14.9	24.3	

Construction Record - Screen


Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
20	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	0 to 6	21.23
		6 to 24.3	15.55

Well Contractor and Well Technician Information

Business Name of Well Contractor: Bourgeois well Drilling
 Well Contractor's Licence No.:
 Business Address (Street Number/Name): 1178 Route 900 East
 Municipality: NATION
 Province: Ontario
 Postal Code: K0A 3C0
 Business E-mail Address: NA
 Bus. Telephone No. (inc. area code): 613 987 5291
 Name of Well Technician (Last Name, First Name): Michael Genier
 Well Technician's Licence No.: 3493
 Signature of Technician and/or Contractor: [Signature]
 Date Submitted: 2009 02 20



Well owner's information package delivered: Yes No

Date Package Delivered: Y|Y|Y|Y|M|M|D|D: 20090217


Date Work Completed: 20090217

Ministry Use Only

Audit No. Z 90541

Received: [Stamp]

316/46



7117 ^{6W}

UTM 118Z 45211610E

5R 49990710N

Elev. 4R 03110

Basin 25

Con I
lot 28

The Water-well Drillers Act, 1954
Department of Mines

Water-Well Record

County or Territorial District Carleton Township, Village, Town or City Osgoode township

Village, Town or City

Address Osgoode

Date completed (day) (month) (year)

Pipe and Casing Record

Pumping Test

Casing diameter(s) 5"
Length(s) 58'
Type of screen
Length of screen

Static level 18 ft
Pumping rate 360 gal per hour
Pumping level 7.5 ft
Duration of test 4 hours

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth (s) at which water (s) found	No. of feet water rises	Kind of water (fresh, salty, or sulphur)
<u>hardpan boulders</u>	<u>0</u>	<u>58</u>			
<u>limestone rock</u>	<u>58</u>	<u>154</u>	<u>154</u>	<u>136</u>	<u>fresh</u>

For what purpose(s) is the water to be used? house

Is water clear or cloudy? clear

Is well on upland, in valley, or on hillside? upland

Drilling firm J. Singer & Sons

Address Mountains

Name of Driller Gerald Singer

Address Mountains


Licence Number 312

I certify that the foregoing statements of fact are true.

Date Oct 10 Gerald Singer
Signature of Licensee

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



CSS.58

31G/4h



GROUND WATER BRANCH
15 No 7116
MAY 21 1963
ONTARIO WATER RESOURCES COMMISSION

UTM 118Z 452110E

5R 4999080N

Elev. 4R 10310

The Ontario Water Resources Commission Act

WATER WELL RECORD

Basin 25 | |
County or District Carleton Place

Township, Village, Town or City Osgoode

Con. I P.1 Lot 28

Date completed 2 Feb 63
(day month year)

Owner Coady Constr Co
(print in block letters)

Address 220 Ellendale Cres
Ottawa

Casing and Screen Record

Inside diameter of casing 5"
Total length of casing 62'
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 5"

Pumping Test

Static level 31
Test-pumping rate 8 G.P.M.
Pumping level 60
Duration of test pumping 1 hr
Water clear or cloudy at end of test cloudy
Recommended pumping rate 8 G.P.M.
with pump setting of 75 feet below ground surface

Well Log

Overburden and Bedrock Record

sand
clay
hardpan
blue limestone

Water Record

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
0	20'	100	fresh
20	36'	120	fresh
36	59	131	"
59	133		

For what purpose(s) is the water to be used?

Post office

Is well on upland, in valley or on hillside? upland

Drilling or Boring Firm Capital Water Supply

Address 1243 Heron Rd

Licence Number 482 976


Name of Driller or Borer S Huff

Date 4 Feb 1963

Walter Kavanagh
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



UTM 182 452050E



WATER RESOURCES
DIVISION No. 15 No. 132
MAY 17 1965
ONTARIO WATER
RESOURCES COMMISSION

Cons 4998920N

The Ontario Water Resources Commission Act

Elev 320

WATER WELL RECORD

Basin 25 | District Carleton

Township, Village, Town or City Osgoode

Con. 1 Lot 29

Date completed April 14th, 1965
(day month year)

Owner Canadian Legion
(print in block letters)

Address Osgoode Ont.

Casing and Screen Record

Inside diameter of casing 2"

Total length of casing 9'

Type of screen -

Length of screen -

Depth to top of screen -

Diameter of finished hole 2"

Pumping Test

Static level 20'

Test-pumping rate 360 G.P.H.

Pumping level 13' 31"

Duration of test pumping 1 hour

Water clear or cloudy at end of test clear

Recommended pumping rate 300 G.P.H.

with pump setting of 75 feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
Gravel	0	5		<u>FRESH</u>
Boulders	5	34		
Rocks	34	38'		
Limestone	38	80'	80'	

For what purpose(s) is the water to be used? Legion Hall

Is well on upland, in valley, or on hillside? ---

Drilling or Boring Firm J.B. Dufresne & Co. Ltd.

Address 1014 Maitland Ave.
Ottawa, Ontario.

Licence Number 1307

Name of Driller or Borer F. Laramee


Address 21A Garneau, Hull Que.

Date April 19th, 1965

[Signature]
for J.B. Dufresne & Co. Ltd.
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





3/6/42 41
1510042
3 9

184452200
4RT49990210
5R0315
25

The Ontario Water Resources Commission Act

WATER WELL RECORD

County or District Carleton Place
Con. Becken Farm I Lot 2828


WATER RESOURCES
JUN 2 1969
Date completed Jan 28, 1969
WATER COMMISSION
with pump setting of Osgoode

Casing and Screen Record
Inside diameter of casing 5"
Total length of casing 43'
Type of screen —
Length of screen —
Depth to top of screen —
Diameter of finished hole 5"

Pumping Test
Static level 20 ft
Test-pumping rate 10 G.P.M.
Pumping level 35 ft
Duration of test pumping 1 hr.
Water clear or cloudy at end of test Clear
Recommended pumping rate 5-10 G.P.M.
with pump setting of 56" feet below ground surface

Well Log	Water Record			
	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
Overburden and Bedrock Record				
<u>Overburden</u>	<u>0</u>	<u>39'</u>	<u>61</u>	<u>Fresh</u>
<u>Limestone</u>	<u>39'</u>	<u>65'</u>		

For what purpose(s) is the water to be used? House
Is well on upland, in valley, or on hillside? upland
Drilling or Boring Firm C.V. Morrison
Address Frankville
Licence Number 3104
Name of Driller or Borer P. QUINN
Address Frankville
Date Jan 28, 1969
C.V. Morrison
(Signature of Licensed Drilling or Boring Contractor)



OSGOODE STATION



ONTARIO

MINISTRY OF THE ENVIRONMENT
The Ontario Water Resources Act

WATER WELL RECORD

13
3.9/4h.

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1512448

MUNICIPALITY 15009

CON. CON

LOT 25-27 01

COUNTY OR DISTRICT *Ht* TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE *Orsgoode* CON., BLOCK, TRACT, SURVEY, ETC. *1* LOT 25-27 *01*

DATE COMPLETED 48-53 DAY *13* MO. *02* YR. *73*

RC. ELEVATION RC. BASIN CODE II III IV

1512448 18 452153 4998995 4 313 4 26 MAR 17, 1975 247

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
<i>Brown</i>	<i>Top soil</i>			0	2
<i>Brown</i>	<i>Sand</i>	<i>coffles</i>	<i>Loose</i>	2	32
<i>grey</i>	<i>sand</i>	<i>gravel boulders</i>	<i>Packed</i>	32	45

31 *0002602* *00032628* *0045228113*

32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-13	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-19	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
<i>06</i>	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	<i>1/8"</i>	0 47
<i>6</i>	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE		47 54
<i>06</i>	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE		47 0054

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH

MATERIAL AND TYPE DEPTH TO TOP OF SCREEN

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER, ETC.
10-13		
18-21		
26-29		

71 PUMPING TEST METHOD

1 PUMP 2 BAILER

PUMPING RATE *0010* GPM

DURATION OF PUMPING 15-16 HOURS *00* 7-18 MINS


STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING PUMPING
19-21 <i>006</i>	22-24 <i>026</i>	15 MINUTES <i>026</i> 30 MINUTES <i>026</i> 45 MINUTES <i>026</i> 60 MINUTES <i>026</i>

RECOMMENDED PUMP TYPE SHALLOW DEEP

RECOMMENDED PUMP SETTING *032* FEET

RECOMMENDED PUMPING RATE *0005* GPM

50-53 *000.5* GPM./FT. SPECIFIC CAPACITY



54 FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL

55-56 WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
 OTHER 9 NOT USED

57 METHOD OF DRILLING

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR *Maple Leaf Drilling* LICENCE NUMBER *3658*

ADDRESS *409-465 Richmond Rd Ottawa*

NAME OF DRILLER OR BORER *R. Harsen* LICENCE NUMBER

SIGNATURE OF CONTRACTOR *Robert Perrin* SUBMISSION DATE DAY *13* MO. *2* YR. *73*

OFFICE USE ONLY

DATA SOURCE *1* 58 CONTRACTOR *3658* 59-62 DATE RECEIVED *240473* 63-68 80

DATE OF INSPECTION INSPECTOR *K*

REMARKS:

P R
WI

099.58

WATER WELL RECORD

3/64h

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11 1517055 15009 29N 01

COUNTY OR DISTRICT Carleton	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE Osgoode	CON. BLOCK, TRACT, SURVEY ETC. Conc. 1	22-23 028 20
OWNER (SURNAME FIRST) Taldor Dev.	ADDRESS R. R. # 1, Osgoode, Ontario K0A 2W0	DATE COMPLETED DAY 21 MO 06 YR 79	

21 ZONE **18** EASTING **451999** NORTHING **4999199** ELEVATION **0310** BASIN CODE **26**

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand			0	3
Gray	Sand		Wet	3	10
Gray	Clay & Sand			10	24
Gray	Sand		Boulders	24	29
Gray	Limestone		Broken	29	31

31 0003628 0010228 002420528 002922813 003121571

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-13 0030	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
10-11 6 1/2	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	FROM 0 TO 0029
17-18 06	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		FROM 29 TO 0031
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE		FROM 27 TO 30

SCREEN


SIZE(S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET
	31-33	34-38
MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN 41-44 FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER, ETC.
FROM TO		
10-13	14-17	
18-21	22-25	
26-29	30-33	80

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	0030 GPM	11-14 01 HOUR 15-16 00 MINS 17-18
STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING
19-21 008 FEET	22-24 015 FEET	15 MINUTES 26-28 015 FEET 30 MINUTES 29-31 015 FEET 45 MINUTES 32-34 015 FEET 60 MINUTES 35-37 015 FEET
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
	GPM	1 <input checked="" type="checkbox"/> CLEAR 2 <input type="checkbox"/> CLOUDY
RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING	RECOMMENDED PUMPING RATE
1 <input checked="" type="checkbox"/> SHALLOW 2 <input type="checkbox"/> DEEP	43-45 020 FEET	46-49 0005 GPM



FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL

WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
9 OTHER 9 NOT USED

METHOD OF DRILLING

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR
Capital Water Supply Ltd. LICENCE NUMBER **1558**

ADDRESS
Box 490, Stittsville, Ontario K0A 3E0

NAME OF DRILLER OR BORER
S. Miller LICENCE NUMBER

SIGNATURE OF CONTRACTOR
[Signature] SUBMISSION DATE
DAY **26** MO **06** YR **79**

OFFICE USE ONLY

DATA SOURCE **1** CONTRACTOR **1558** DATE RECEIVED **130879**

DATE OF INSPECTION INSPECTOR *[Signature]*

REMARKS

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1517062

MUNICIP. 15009

CON. C/DN

01

COUNTY OR DISTRICT Carleton	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE Baggoode	CON. BLOCK, TRACT, SURVEY ETC. I Conc. 1	028 27
OWNER (SURNAME FIRST) Taldor Dev. / o/b T. Princiotta	ADDRESS R. R. # 1, Baggoode, Ontario K0A 2W0	DATE COMPLETED DAY 22 MO 06 YR 79	
ZONE 18	EASTING 451999	NORTHING 4999199	RC 4
		ELEVATION 0310	RC 4
		BASEIN CODE 26	

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand			0	5
Gray	Sand		Runny	5	14
Gray	Sand & Clay			14	29
Gray	Limestone			29	35

31 0005628 0014228 0029228as 003521S

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-13	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
10-11	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0	0029
17-18	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		29	0035
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH
	INCHES	FEET
MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN
		41-44
		FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	(CEMENT GROUT, LEAD PACKER, ETC.)
FROM TO		
10-13	14-17	
18-21	22-25	
26-29	30-33	80

71 PUMPING TEST

PUMPING TEST METHOD 1 <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	PUMPING RATE 0050 GPM	DURATION OF PUMPING 15-16 HOURS 00 MINS
STATIC LEVEL 19-21 006 FEET	WATER LEVEL END OF PUMPING 22-24 015 FEET	WATER LEVELS DURING 15 MINUTES 26-28 015 FEET 30 MINUTES 29-31 015 FEET 45 MINUTES 32-34 015 FEET 60 MINUTES 35-37 015 FEET
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
RECOMMENDED PUMP TYPE 1 <input checked="" type="checkbox"/> SHALLOW 2 <input type="checkbox"/> DEEP	RECOMMENDED PUMP SETTING 025 FEET	RECOMMENDED PUMPING RATE 0005 GPM

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.

DRILLERS REMARKS

FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED, POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL

WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
9 NOT USED

METHOD OF DRILLING

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR
Capital Water Supply Ltd.

LICENCE NUMBER
1558

ADDRESS
Box 490, Stittsville, Ontario K0A 3G0

NAME OF DRILLER OR BORER
S. Miller

LICENCE NUMBER

SIGNATURE OF CONTRACTOR
[Signature]

SUBMISSION DATE
DAY **26** MO **06** YR **79**

OFFICE USE ONLY

DATA SOURCE
1

CONTRACTOR
1558

DATE RECEIVED
130879

DATE OF INSPECTION

INSPECTOR
[Signature]

REMARKS

WATER WELL RECORD

3/64h

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11 1517063 MUNICIPAL 15009 CON. CAN 01

COUNTY OR DISTRICT: **Carleton** TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: **Osgoode** CON. BLOCK, TRACT, SURVEY, ETC: **Conc. 1 I** **028**
 OWNER (SURNAME FIRST): **Taldor Dev** ADDRESS: **R. R. # 1, Osgoode, Ontario K0A 2W0** DATE COMPLETED: DAY **21** MO **06** YR **79**
 UTM: **21** EASTING: **18** NORTHING: **451999** ELEVATION: **4999199** BASIN CODE: **4 0310 4 26**

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand			0	5
Gray	Sand & Clay			5	20
Gray	Clay			20	27
Gray	Limestone			27	40



31 0005628 0020218 05 0027205 0040215

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-13	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0	0029
06	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		29	0040
06	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			27-30

SCREEN


SIZE (S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET
	31-33	34-38
MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN 41-44

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC.)
FROM TO	
10-13	14-17
18-21	22-25
26-29	30-33

71 PUMPING TEST

PUMPING TEST METHOD: 1 PUMP 2 BAILER
 PUMPING RATE: **0030** GPM DURATION OF PUMPING: **01** HOURS **00** MINS
 WATER LEVELS DURING PUMPING: 15 MINUTES: **015** FEET, 30 MINUTES: **015** FEET, 45 MINUTES: **015** FEET, 60 MINUTES: **015** FEET
 RECOMMENDED PUMP TYPE: 1 SHALLOW 2 DEEP
 RECOMMENDED PUMP SETTING: **020** FEET RECOMMENDED PUMPING RATE: **0005** GPM



FINAL STATUS OF WELL 1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
 2 OBSERVATION WELL 6 ABANDONED, POOR QUALITY
 3 TEST HOLE 7 UNFINISHED
 4 RECHARGE WELL

WATER USE 1 DOMESTIC 5 COMMERCIAL
 2 STOCK 6 MUNICIPAL
 3 IRRIGATION 7 PUBLIC SUPPLY
 4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
 9 NOT USED

METHOD OF DRILLING 1 CABLE TOOL 6 BORING
 2 ROTARY (CONVENTIONAL) 7 DIAMOND
 3 ROTARY (REVERSE) 8 JETTING
 4 ROTARY (AIR) 9 DRIVING
 5 AIR PERCUSSION

CONTRACTOR NAME OF WELL CONTRACTOR: **Capital Water Supply Ltd.** LICENCE NUMBER: **1558**
 ADDRESS: **Box 490, Stittsville, Ontario K0A 3G0**
 NAME OF DRILLER OR BORER: **S. Miller** LICENCE NUMBER:
 SIGNATURE OF CONTRACTOR: *[Signature]* SUBMISSION DATE: DAY **26** MO **06** YR **79**

OFFICE USE ONLY DATA SOURCE: **1** CONTRACTOR: **1558** DATE RECEIVED: **130879**
 DATE OF INSPECTION: INSPECTOR: *[Signature]*
 REMARKS:



Ministry of the Environment Ontario

The Ontario Water Resources Act WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11 1517843 MUNICIPAL 15009 CON Cdn 01

COUNTY OF DISTRICT *West* TOWNSHIP, BOROUGH, CITY, TOWN/VILLAGE *Osgoode* CON. BLOCK, TRACT, SURVEY ETC. *James St.* 0/88

DATE COMPLETED DAY 19 MO 04 YR 82

RC 98899 ELEVATION 4 0310 RC 4 BASIN CODE 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	sand			0	26
grey	gravel			26	31
grey	sand hardpan			31	44
grey	limestone			44	63

31 00262228 0031211 004422814 0063215

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER			
10-13 0055	1 <input checked="" type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
15-18 0060	1 <input checked="" type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
20-23	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
25-28	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
30-33	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		

51 CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
96 64	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0	60
17-16	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			20-23
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			27-30

SCREEN

SIZE/SLOT NO.	DIAMETER INCHES	LENGTH FEET
MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN FEET
		41-44

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER ETC.
10-13	14-17	
18-21	22-25	
26-29	30-33	

71 PUMPING TEST

PUMPING TEST METHOD: 1 PUMP 2 BAILER

PUMPING RATE: 0030 GPM

DURATION OF PUMPING: 01 HOURS 00 MINS

PUMPING TEST	STATIC LEVEL FEET	WATER LEVEL END OF PUMPING FEET	WATER LEVELS DURING PUMPING			
			15 MINUTES	30 MINUTES	45 MINUTES	60 MINUTES
	015	030	030	030	030	030

IF FLOWING GIVE RATE: 38-41 GPM


PUMP INTAKE SET AT: FEET

WATER AT END OF TEST: 1 CLEAR 2 CLOUDY

RECOMMENDED PUMP TYPE: SHALLOW DEEP

RECOMMENDED PUMP SETTING: 030 FEET

RECOMMENDED PUMPING RATE: 0010 GPM



FINAL STATUS OF WELL 1 WATER SUPPLY

WATER USE 01 1 DOMESTIC

METHOD OF DRILLING 5 1 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR: Henry Mains Well Drilling LICENCE NUMBER: 3644

ADDRESS: Box 326, Richmond Ont.

NAME OF DRILLER OR BORER: Henry Mains LICENCE NUMBER:

SIGNATURE OF CONTRACTOR: [Signature] SUBMISSION DATE: 20 4 82

OFFICE USE ONLY

DATA SOURCE: 1 CONTRACTOR: 3644 DATE RECEIVED: 08 07 82

DATE OF INSPECTION: INSPECTOR:

REMARKS:

1. PRINT ONLY IN SPACES PROVIDED
 2. CHECK CORRECT BOX WHERE APPLICABLE

11

1518085

MUNICIPALITY 15009

CON. 06N

01

COUNTY OR DISTRICT: [REDACTED] TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: Osgoode CON. BLOCK, TRACT, SURVEY ETC: Conc. 1 I 027
 DATE COMPLETED: DAY 05 MO 11 YR 88
 501; Osgoode, Ontario. KOA 2W0
 79299 RC 4 ELEVATION 0300 RC 4 BASIN CODE 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
brown	Sand			0	4
gray	Sand			4	10
gray	Sand & Gravel			10	25
gray	Hardpan			25	30
gray	Limestone			38	75

31 0004628 0010228 0025228 11 0038214 0075215

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
0070'	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	1.00	0	0039
06	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		39	0075
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE			27-30

SCREEN

SIZES OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET


MATERIAL AND TYPE: _____ DEPTH TO TOP OF SCREEN: 41-44 FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER, ETC.)
10-13	14-17
18-21	22-25
26-29	30-33

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	0010 GPM	01 HOURS 00 MINS
STATIC LEVEL: 010 FEET	WATER LEVELS DURING:	1 <input checked="" type="checkbox"/> PUMPING 2 <input type="checkbox"/> RECOVERY
19-21: 025 FEET	22-24: 025 FEET	15 MINUTES: 025 FEET
26-28: 025 FEET	29-31: 025 FEET	30 MINUTES: 025 FEET
32-34: 025 FEET	35-37: 025 FEET	45 MINUTES: 025 FEET
38-41: 025 FEET	42: 025 FEET	60 MINUTES: 025 FEET
IF FLOWING, GIVE RATE: _____ GPM	PUMP INTAKE SET AT: 040 FEET	WATER AT END OF TEST: 1 <input checked="" type="checkbox"/> CLEAR 2 <input type="checkbox"/> CLOUDY
RECOMMENDED PUMP TYPE: <input checked="" type="checkbox"/> SHALLOW <input checked="" type="checkbox"/> DEEP	RECOMMENDED PUMP SETTING: 040 FEET	RECOMMENDED PUMPING RATE: 0005 GPM



FINAL STATUS OF WELL 1

WATER USE 01

METHOD OF DRILLING 5

CONTRACTOR

NAME OF WELL CONTRACTOR: Capital Water Supply Ltd. LICENCE NUMBER: 1558
 ADDRESS: Box 490; Stittsville, Ont. KOA 8G0
 NAME OF DRILLER OR BORER: S. Miller LICENCE NUMBER: _____
 SIGNATURE OF CONTRACTOR: [Signature] SUBMISSION DATE: DAY 05 MO 11 YR 88

OFFICE USE ONLY

DATA SOURCE: 1 CONTRACTOR: 1558 DATE: 26 01 88
 DATE OF INSPECTION: _____ INSPECTOR: _____
 REMARKS: _____

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1518482

MUNICIPALITY 15009 CON

01

COUNTY OR DISTRICT: Carleton TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: Osgoode CON. BLOCK, TRACT, SURVEY, ETC.: I Con 1, Plan M258 28

OWNER (SURNAME FIRST): Bison Construction ADDRESS: 41 Cleopatra Avenue K2G 0B6 DATE COMPLETED: DAY 16 MO 08 YR 83

ZONING: 18 EASTING: 451899 NORTHING: 4999199 PC: 4 ELEVATION: 0300 BASIN CODE: 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	clay			0	11
grey	hardpan	stone		11	27
grey	limestone			27	40

M.O.E. WF-18

31 0011205 32 002721412 33 0040215

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-15	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
9 1/2	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0 to 29
6	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		29 to 40
24-25	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE		27-30

SCREEN

SIZE OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

MATERIAL AND TYPE: _____ DEPTH TO TOP OF SCREEN: _____

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE
10-13	14-17
18-21	22-25
26-29	30-33

71 PUMPING TEST


PUMPING TEST METHOD: 1 PUMP 2 BAILER

PUMPING RATE: 0020 GPM DURATION OF PUMPING: 01 HOURS 00 MINS

STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING	RECOVERY
012	030	15 MINUTES: 030 30 MINUTES: 030 45 MINUTES: 030 60 MINUTES: 030	

RECOMMENDED PUMP TYPE: SHALLOW DEEP

RECOMMENDED PUMP SETTING: 030 FEET RECOMMENDED PUMPING RATE: 00/0 GPM



FINAL STATUS OF WELL

1 WATER SUPPLY 5 ABANDONED, INSUFFICIENT SUPPLY
2 OBSERVATION WELL 6 ABANDONED POOR QUALITY
3 TEST HOLE 7 UNFINISHED
4 RECHARGE WELL

WATER USE

1 DOMESTIC 5 COMMERCIAL
2 STOCK 6 MUNICIPAL
3 IRRIGATION 7 PUBLIC SUPPLY
4 INDUSTRIAL 8 COOLING OR AIR CONDITIONING
9 OTHER 9 NOT USED

METHOD OF DRILLING

1 CABLE TOOL 6 BORING
2 ROTARY (CONVENTIONAL) 7 DIAMOND
3 ROTARY (REVERSE) 8 JETTING
4 ROTARY (AIR) 9 DRIVING
5 AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR: Henry Mains Well Drilling LICENCE NUMBER: 3644

ADDRESS: Box 326, Richmond Ont.

NAME OF DRILLER OR BOREY: Henry Mains LICENCE NUMBER: _____

SIGNATURE OF CONTRACTOR: _____ SUBMISSION DATE: DAY 27 MO 8 YR 83

OFFICE USE ONLY

DATA SOURCE: 1 CONTRACTOR: 3644 DATE RECEIVED: 12 09 83

DATE OF INSPECTION: _____ INSPECTOR: _____

REMARKS: _____



Ministry of the Environment

Ontario

The Ontario Water Resources Act

31644

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

1518483

MUNICIPALITY 15009

CONTRACTOR C&N

01

COUNTY OR DISTRICT: Carleton TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: Osgood CON. BLOCK, TRACT, SURVEY, ETC.: I Con 1 Plan M258027

OWNER (SURNAME FIRST): Bison Construction ADDRESS: 41 Cleopatra Nepean K2G 0B6 DATE COMPLETED: DAY 16 MO 08 YR 83

ZONE: U 18 EASTING: 45189.9 NORTHING: 49991.99 ELEVATION: 0.300 BASIN CODE: 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	sand			0	9
grey	hardpan	stones		9	29
grey	limestone			29	40

MOE VF-18

31 0009228 002921412 0040215

41 WATER RECORD

WATER FOUND AT - FEET: 037

KIND OF WATER:

10-13	1 <input checked="" type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	14
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL	
15-18	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	19
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL	
20-23	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	24
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL	
25-28	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	29
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL	
30-33	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR	34
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL	40

51 CASING & OPEN HOLE RECORD

DEPTH - FEET	MATERIAL	WELL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
10-11	1 <input checked="" type="checkbox"/> STEEL	12		13-16
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			
17-18	1 <input type="checkbox"/> STEEL	19		20-23
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			
24-25	1 <input type="checkbox"/> STEEL	26		27-30
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			

SCREEN: 188 0/031 3/0040

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER, ETC.
FROM TO		
10-13	14-17	
18-21	22-25	
26-29	30-33	40

71 PUMPING TEST

PUMPING TEST METHOD: 1 PUMP 2 BAILER

PUMPING RATE: 0030 GPM

DURATION OF PUMPING: 01:00 HOURS

WATER LEVELS DURING PUMPING:

19-21	22-24	25-27	28-30	31-33	34-36
010	030	030	030	030	030
FEET	FEET	FEET	FEET	FEET	FEET

RECOMMENDED PUMP TYPE: SHALLOW

RECOMMENDED PUMP SETTING: 030 FEET

RECOMMENDED PUMPING RATE: 0010 GPM

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE INDICATE NORTH BY ARROW.

DRILLERS REMARKS:

FINAL STATUS OF WELL 1

WATER USE 01

METHOD OF DRILLING 5

CONTRACTOR

NAME OF WELL CONTRACTOR: Henry Mairs Well Drilling LICENCE NUMBER: 3644

ADDRESS: Box 326, Richmond Ont

NAME OF DRILLER OR BORE: Henry Mairs LICENCE NUMBER:

SIGNATURE OF CONTRACTOR: Henry Mairs SUBMISSION DATE: DAY 27 MO 8 YR 83

OFFICE USE ONLY

DATA SOURCE: 1 CONTRACTOR: 3644 DATE RECEIVED: 12 09 83

DATE OF INSPECTION: INSPECTOR:

REMARKS:

WATER WELL RECORD

3164h

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1519019

MUNICIPALITY 15009

CON. CON

01

COUNTY OR DISTRICT: **Carleton** TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: **Osgoode** CON. BLOCK, TRACT, SURVEY, ETC: **I Con 1, 0287**

OWNER (SURNAME FIRST): **Bicen Construction** ADDRESS: **4 Cleopatra Nepean K2G 0B6** DATE COMPLETED: **09 05 84**

U ZONE: **18** EASTING: **452099** NORTHING: **4999299** RC: **4** ELEVATION: **0310** RC: **4** BASIN CODE: **26**

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	sand			0	5
grey	hardpan	stone		5	41
grey	limestone			41	50

MOE VF-18

31 0005228 004121412 0050215

32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER			
10-13	<input checked="" type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
15-18	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
20-23	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
25-28	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
30-33	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06	STEEL	1/88	0	43
06	STEEL		43	50

SCREEN

SIZE (S) OF OPENING (S) SLOT NO 1	DIAMETER INCHES	LENGTH FEET
	34-38	39-40

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC.)
10-13	14-17
18-21	22-25
26-29	30-33

71 PUMPING TEST

PUMPING TEST METHOD: PUMP BAILEY

PUMPING RATE: **0020** GPM DURATION OF PUMPING: **01 00** HOURS MINS

STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING PUMPING			
010	030	15 MINUTES: 030	30 MINUTES: 030	45 MINUTES: 030	60 MINUTES: 030

RECOMMENDED PUMP TYPE: SHALLOW DEEP

RECOMMENDED PUMP SETTING: **030** FEET

RECOMMENDED PUMPING RATE: **0010** GPM

1488 LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.

DRILLERS REMARKS:

FINAL STATUS OF WELL: **1**

WATER USE: **01**

METHOD OF DRILLING: **5**

CONTRACTOR: **Henry Mains Well Drilling** LICENCE NUMBER: **3644**

ADDRESS: **Box 326, Richmond Ont.**

NAME OF DRILLER OR BORER: **Henry Mains** LICENCE NUMBER:

SIGNATURE OF CONTRACTOR: **Henry Mains** SUBMISSION DATE: **12 5 84**

OFFICE USE ONLY

DATA SOURCE: **1** CONTRACTOR: **3644** DATE RECEIVED: **03 07 84**

DATE OF INSPECTION: _____ INSPECTOR: _____

REMARKS:



Ministry
of the
Environment

Ontario

The Ontario Water Resources Act

3164h

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1519660

MUNICIPALITY 15009

CON. C/N

01

COUNTY OR DISTRICT Carleton	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE Osgoode	CON. BLOCK, TRACT, SURVEY ETC Conc. 1	DATE COMPLETED 27 1 79
OWNER (SURNAME FIRST) Taldor Enterprises	ADDRESS R. R. # 1, Osgoode, Ontario	DATE COMPLETED DAY 31 MO 10 YR 79	

ZONING 18	EASTING 451699	NORTHING 4999199	RC 4	ELEVATION 0300	RC 4	BASEIN CODE 26
---------------------	--------------------------	----------------------------	----------------	--------------------------	----------------	--------------------------

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand			0	13
Gray	Sand		Wet	13	30
Gray	Sand & Gravel			30	32
Gray	Limestone			32	40

MOE
VF-18

31	0013628	0030228	0032228/11	0040215
32				


WATER FOUND AT - FEET	KIND OF WATER
10-13 0038'	1 <input checked="" type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERAL

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
10-11 06 6 1/2	1 <input checked="" type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE	188	0 0032
17-18 06 5 1/2	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input checked="" type="checkbox"/> OPEN HOLE		32 0040
24-25 18	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE		27-30

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH
	INCHES	FEET
MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN	
	41-44	30
	FEET	

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER, ETC.)
10-13	14-17
18-21	22-25
26-29	30-33

PUMPING TEST METHOD <input checked="" type="checkbox"/> PUMP 2 <input type="checkbox"/> BAILER	PUMPING RATE 0060 GPM	DURATION OF PUMPING 15-16 00 HOURS 17-18 00 MINS
STATIC LEVEL 007 FEET	WATER LEVEL END OF PUMPING 010 FEET	WATER LEVELS DURING
19-21	22-24	15 MINUTES 26-28
010 FEET	010 FEET	30 MINUTES 29-31
		45 MINUTES 32-34
		60 MINUTES 35-37
		010 FEET
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT 30 FEET	WATER AT END OF TEST <input checked="" type="checkbox"/> CLEAR 2 <input type="checkbox"/> CLOUDY
RECOMMENDED PUMP TYPE <input checked="" type="checkbox"/> SHALLOW <input type="checkbox"/> DEEP	RECOMMENDED PUMP SETTING 025 FEET	RECOMMENDED PUMPING RATE 0005 GPM



FINAL STATUS OF WELL	1 <input checked="" type="checkbox"/> WATER SUPPLY 2 <input type="checkbox"/> OBSERVATION WELL 3 <input type="checkbox"/> TEST HOLE 4 <input type="checkbox"/> RECHARGE WELL	5 <input type="checkbox"/> ABANDONED, INSUFFICIENT SUPPLY 6 <input type="checkbox"/> ABANDONED, POOR QUALITY 7 <input type="checkbox"/> UNFINISHED
WATER USE	1 <input checked="" type="checkbox"/> DOMESTIC 2 <input type="checkbox"/> STOCK 3 <input type="checkbox"/> IRRIGATION 4 <input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> OTHER	5 <input type="checkbox"/> COMMERCIAL 6 <input type="checkbox"/> MUNICIPAL 7 <input type="checkbox"/> PUBLIC SUPPLY 8 <input type="checkbox"/> COOLING OR AIR CONDITIONING 9 <input type="checkbox"/> NOT USED
METHOD OF DRILLING	1 <input type="checkbox"/> CABLE TOOL 2 <input type="checkbox"/> ROTARY (CONVENTIONAL) 3 <input type="checkbox"/> ROTARY (REVERSE) 4 <input type="checkbox"/> ROTARY (AIR) <input checked="" type="checkbox"/> AIR PERCUSSION	5 <input type="checkbox"/> BORING 6 <input type="checkbox"/> DIAMOND 7 <input type="checkbox"/> JETTING 8 <input type="checkbox"/> DRIVING

NAME OF WELL CONTRACTOR Capital Water Supply Ltd.	LICENCE NUMBER 1558
ADDRESS Box 490, Stittsville, Ontario K0 3E0	
NAME OF DRILLER OR BORER S. Miller	LICENCE NUMBER
SIGNATURE OF CONTRACTOR <i>W. H. ...</i>	SUBMISSION DATE DAY 31 MO 10 YR 79

DATA SOURCE 1	CONTRACTOR 1558	DATE RECORDED 210380
DATE OF INSPECTION	INSPECTOR K	
REMARKS changed from 1517260		

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11 1521685

MUNICIPALITY: [] LOT: 25-27

COUNTY OR DISTRICT: Carleton TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: Osborne CON. BLOCK, TRACT, SURVEY, ETC.: Main St. Cont LOT: 5479

Box 123, Melville Ont. DATE COMPLETED: DAY 30 MO 4 YR. 82

ING: [] RC: [] ELEVATION: [] RC: [] BASIN: []

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	fill			0	5
grey	sand			5	15
grey	hardpan	stones	stone hard	15	46
grey	limestone			46	85

4 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
60	<input checked="" type="checkbox"/> FRESH <input type="checkbox"/> SULPHUR <input type="checkbox"/> SALTY <input type="checkbox"/> MINERAL
80	<input checked="" type="checkbox"/> FRESH <input type="checkbox"/> SULPHUR <input type="checkbox"/> SALTY <input type="checkbox"/> MINERAL
20-23	<input type="checkbox"/> FRESH <input type="checkbox"/> SULPHUR <input type="checkbox"/> SALTY <input type="checkbox"/> MINERAL
25-25	<input type="checkbox"/> FRESH <input type="checkbox"/> SULPHUR <input type="checkbox"/> SALTY <input type="checkbox"/> MINERAL
30-33	<input type="checkbox"/> FRESH <input type="checkbox"/> SULPHUR <input type="checkbox"/> SALTY <input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
6 1/4	STEEL	1/88	0	48
6	STEEL		48	85

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

MATERIAL AND TYPE: [] DEPTH TO TOP OF SCREEN: []

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
10-13	
18-21	pressure cement grout
26-29	

71 PUMPING TEST

PUMPING TEST METHOD: PUMP BAILER


PUMPING RATE: 9 GPM DURATION OF PUMPING: 1 HOURS 0 MINS

STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING			
15	80	80	80	80	80

RECOMMENDED PUMP TYPE: SHALLOW DEEP

RECOMMENDED PUMP SETTING: 80 FEET

RECOMMENDED PUMPING RATE: 9 GPM



FINAL STATUS OF WELL

WATER SUPPLY ABANDONED, INSUFFICIENT SUPPLY

OBSERVATION WELL ABANDONED, POOR QUALITY

TEST HOLE UNFINISHED

RECHARGE WELL

WATER USE

DOMESTIC COMMERCIAL

STOCK MUNICIPAL

IRRIGATION PUBLIC SUPPLY

INDUSTRIAL COOLING OR AIR CONDITIONING

OTHER: fire dept. NOT USED

METHOD OF DRILLING

CABLE TOOL BORING

ROTARY (CONVENTIONAL) DIAMOND

ROTARY (REVERSE) JETTING

ROTARY (AIR) DRIVING

AIR PERCUSSION

CONTRACTOR

NAME OF WELL CONTRACTOR: W. Mains Well Drilling LICENCE NUMBER: 3644

ADDRESS: Box 326, Richmond Ont.

NAME OF DRILLER OR BORER: [] LICENCE NUMBER: []

SIGNATURE OF CONTRACTOR: [] SUBMISSION DATE: DAY 30 MO 4 YR. 82

OFFICE USE ONLY

DATE RECEIVED: AUG 14 1987

DATE OF INSPECTION: [] INSPECTOR: []

REMARKS: []

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

1529556

Municipality 15009 Con. CON 01

County or District [Redacted] Township/Borough/City/Town/Village OSGOODE
 Con block tract survey, etc. 1 Part 67 28
 Address 5515 Lion St. OSGOODE ON Date completed 23 day 7 month 97 year

21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown Sand			Packed	0	15
GREY Sand			Packed	15	18
GREY Clay			Runny	18	26
GREY Clay & Stones			HARD PAN	26	52
GREY Limestone			MED HARD	52	88
55' of 6 1/4" casing 1 HEAVY DRIVE shoe 1 WELL cap 5 Bags of Cement B.M.					

31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----


41 WATER RECORD	
Water found at - feet	Kind of water
85	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input checked="" type="checkbox"/> Minerals <input type="checkbox"/> Gas
15-18	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
20-23	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
25-28	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
30-33	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic	1.88	0	53
6"	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic		53	88
17-18	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			20-23
24-25	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			27-30

SCREEN	Sizes of opening (Slot No.)	Diameter inches	Length feet	
				Material and type

61 PLUGGING & SEALING RECORD			
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)	
From	To		
0	21	Cement Grout	
18-21	22-25		
26-29	30-33		

71 PUMPING TEST	
Pumping test method <input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailer	Pumping rate 12 GPM
Static level 21 feet	Water levels during pumping 15 minutes 30 feet 30 minutes 40 feet 45 minutes 40 feet 60 minutes 40 feet
Recommended pump type <input checked="" type="checkbox"/> Shallow <input type="checkbox"/> Deep	Recommended pump setting 35 feet



FINAL STATUS OF WELL		
<input checked="" type="checkbox"/> Water supply	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Unfinished
<input type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well
<input type="checkbox"/> Test hole	<input type="checkbox"/> Abandoned (Other)	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Recharge well		

WATER USE		
<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Stock	<input type="checkbox"/> Municipal	<input type="checkbox"/> Other
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Public supply	
<input type="checkbox"/> Industrial	<input type="checkbox"/> Cooling & air conditioning	

METHOD OF CONSTRUCTION		
<input checked="" type="checkbox"/> Cable tool	<input type="checkbox"/> Air percussion	<input type="checkbox"/> Driving
<input type="checkbox"/> Rotary (conventional)	<input type="checkbox"/> Boring	<input type="checkbox"/> Digging
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Other
<input type="checkbox"/> Rotary (air)	<input type="checkbox"/> Jetting	

Name of Well Contractor B. MOORE WELL DRILLING	Well Contractor's Licence No. 6455
Address Main St. Box 436 OSGOODE ON	
Name of Well Technician Bob MOORE	Well Technician's Licence No. T-0319
Signature of Technician/Contractor Bob Moore	Submission date 24 mo 7 yr 97

MINISTRY USE ONLY	Data source	Contractor	Date received
		6455	AUG 11 1997
	Date of inspection	Inspector	Remarks

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1533843

Municipality 15009

Con. CON

OTTAWA-CARLETON

County or District: **Carleton**
 Township/Borough/City/Town/Village: **OSGOODE (Ottawa)**
 Con block tract survey, etc.: **1 Plan 393**
 Lot: **46 & 47**
 Address: **5503 OSGOODE Main St.**
 Date completed: **9 day of 03**

21

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown Sand			Packed	0	14
Grey Clay			thick	14	30
Grey Clay & stones			HARD Pan	30	50
Grey Limestone			MED HARD	50	80
54' of 6 1/4" casing 1 DRIVE SHOE 1 WELL CAP 2 Bags of Bentonite Quick Grout					

31

32


41 WATER RECORD	
Water found at - feet	Kind of water
68	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input checked="" type="checkbox"/> Sulphur <input checked="" type="checkbox"/> Minerals <input type="checkbox"/> Gas
15-18	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
20-23	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
25-28	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
30-33	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic	.188	0	53
6"	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic		53	80
17-18	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			20-23
24-25	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			27-30

Sizes of opening (Slot No.)	Diameter inches	Length feet
Material and type		Depth at top of screen feet

61 PLUGGING & SEALING RECORD		
<input checked="" type="checkbox"/> Annular space		<input type="checkbox"/> Abandonment
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)
From	To	
0	53	Bentonite Quick Grout
18-21	22-25	
26-29	30-33	

71 PUMPING TEST											
Pumping test method	Pumping rate										
<input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailer	12 GPM										
Static level: 26 feet Water level end of pumping: 60 feet	Duration of pumping: 1 Hours Water levels during pumping: <table border="1"> <tr> <th>Time</th> <th>Level (feet)</th> </tr> <tr> <td>15 minutes</td> <td>40</td> </tr> <tr> <td>30 minutes</td> <td>60</td> </tr> <tr> <td>45 minutes</td> <td>60</td> </tr> <tr> <td>60 minutes</td> <td>60</td> </tr> </table>	Time	Level (feet)	15 minutes	40	30 minutes	60	45 minutes	60	60 minutes	60
Time	Level (feet)										
15 minutes	40										
30 minutes	60										
45 minutes	60										
60 minutes	60										
If flowing give rate: _____ GPM Recommended pump type: <input checked="" type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Pump intake set at: 70 feet Water at end of test: <input checked="" type="checkbox"/> Clear <input type="checkbox"/> Cloudy Recommended pump setting: _____ GPM Recommended pump rate: 10 GPM										



54 FINAL STATUS OF WELL

Water supply
 Observation well
 Test hole
 Recharge well
 Abandoned, insufficient supply
 Abandoned, poor quality
 Abandoned (Other)
 Dewatering
 Unfinished
 Replacement well

55-56 WATER USE

Domestic
 Stock
 Irrigation
 Industrial
 Commercial
 Municipal
 Public supply
 Cooling & air conditioning
 Not use
 Other

57 METHOD OF CONSTRUCTION

Cable tool
 Rotary (conventional)
 Rotary (reverse)
 Rotary (air)
 Air percussion
 Boring
 Diamond
 Jetting
 Driving
 Digging
 Other

Name of Well Contractor: **B. MOORE WELL DRILLING 6455**
 Well Contractor's Licence No.: **6455**
 Address: **Box 436 OSGOODE ON. K0A 2W0**
 Name of Well Technician: **BOB MOORE**
 Well Technician's Licence No.: **7-0319**
 Signature of Technician/Contractor: **BOB MOORE**
 Submission date: **9 day of 03**

MINISTRY USE ONLY

Data source: _____ Contractor: **6455** Date received: **JUN 10 2003**

Date of inspection: _____ Inspector: _____

Remarks: _____

CSS.ES3

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

MUN		CON		LOT	
First Name Osgoode Youth Centre	Last Name City of Ottawa	Mailing Address (Street Number/Name, RR, Lot, Concession) 5479 Osgoode Main Street			
County/District/Municipality City of Ottawa	Township/City/Town/Village Osgoode	Province Ontario	Postal Code K0A2W0	Telephone Number (include area code) 613 580 2424 Ext 2229	
Address of Well Location (County/District/Municipality) City of Ottawa		Township Osgoode	Lot Plan 303 E Pt Lot 14	Concession	
RR#/Street Number/Name 5479 Osgoode Main Street		City/Town/Village Osgoode	Site/Compartment/Block/Tract etc.		
GPS Reading	NAD Zone Easting 8 3 18 451931	Northing 4999099	Unit Make/Model Garmin	Mode of Operation: <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify	

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	Depth From	Metres To
Black	Asphalt				
Black	Asphalt		Hard	0	0.15
Brown	Sand		Soft	0.15	2.13
Grey	Sand	Gravel Stone	Soft Packed	2.13	14.93
Grey	limestone	Dolostone	Hard	14.93	64.31
Grey	Sandstone	Dolostone	Hard	64.31	73.46

Hole Diameter		
Depth From	Metres To	Diameter Centimetres
0	16.46	25.08
16.46	73.46	15.23
Water Record		
Water found at Metres	Kind of Water	
65 m	<input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals	
71 m	<input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals	
After test of well yield, water was <input checked="" type="checkbox"/> Clear and sediment free <input type="checkbox"/> Other, specify		
Chlorinated	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	

Construction Record					
Inside diam centimetres	Material	Wall thickness centimetres	Depth		Metres
			From	To	
15.88	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass		0.48	0	16.46
	<input type="checkbox"/> Plastic <input type="checkbox"/> Concrete				
	<input type="checkbox"/> Galvanized				
Screen		Slot No.			
Outside diam	<input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized				
No Casing or Screen					
<input checked="" type="checkbox"/> Open hole			16.46 73.46		

Test of Well Yield					
Pumping test method	Draw Down		Recovery		Metres
	Time min	Water Level Metres	Time min	Water Level Metres	
Submersible					
Pump intake set at - (metres) 45.7	Static Level	7.48		8.03	
Pumping rate - 91 (litres/min)	1	7.78	1	7.74	
Duration of pumping 1 hrs + 0 min	2	7.84	2	7.65	
Final water level end of pumping 8.03 metres	3	7.88	3	7.70	
Recommended pump type. <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	4	7.9	4	7.59	
Recommended pump depth. 45 metres	5	7.92	5	7.57	
Recommended pump rate. 91 (litres/min)	10	7.96	10	7.53	
If flowing give rate - (litres/min)	15	7.98	15	7.50	
	20	7.98	20	7.48	
	25	8.00	25		
	30	8.01	30		
	40	8.01	40		
	50	8.02	50		
	60	8.03	60		

Plugging and Sealing Record			
Depth set at - Metres	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)	<input checked="" type="checkbox"/> Annular space <input type="checkbox"/> Abandonment
From To			
16.46 0	Bentonite Pressure Grouted	1.30	

Method of Construction			
<input type="checkbox"/> Cable Tool	<input checked="" type="checkbox"/> Rotary (air)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Digging
<input type="checkbox"/> Rotary (conventional)	<input checked="" type="checkbox"/> Air percussion	<input type="checkbox"/> Jetting	<input type="checkbox"/> Other
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Boring	<input type="checkbox"/> Driving	
Water Use			
<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Industrial	<input type="checkbox"/> Public Supply	<input type="checkbox"/> Other
<input type="checkbox"/> Stock	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used	
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Municipal	<input type="checkbox"/> Cooling & air conditioning	
Final Status of Well			
<input checked="" type="checkbox"/> Water Supply	<input type="checkbox"/> Recharge well	<input type="checkbox"/> Unfinished	<input type="checkbox"/> Abandoned, (Other)
<input type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Dewatering	
<input type="checkbox"/> Test Hole	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well	

Well Contractor/Technician Information	
Name of Well Contractor Splash Well Drilling	Well Contractor's Licence No. 4877
Business Address (street name, number, city etc.) P.O. BOX 1083, Prescott	
Name of Well Technician (last name, first name) Ferguson, Todd	Well Technician's Licence No. 1478
Signature of Technician/Contractor <i>Todd Ferguson</i>	Date Submitted 2005 12 20

Location of Well	
In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.	
Audit No. Z 33210	Date Well Completed 2005 11 29
Was the well owner's information package delivered? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Date Delivered 2005 12 15

Ministry Use Only	
Data Source	Contractor 4877
Date Received MAR 15 2006	Date of Inspection
Remarks	Well Record Number

Measurements recorded in: Metric Imperial

Well Owner's Information

5502 Osgoode Main
County/District/Municipality: Osgoode
City/Town/Village: Osgoode
23
Province: Ontario
Postal Code: K0A 2W0
Ottawa
UTM Coordinates: Zone Easting Northing
NAD 83 18 452037 499 1220
Municipal Plan and Sublot Number: Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Sand		Hard	0	2.5
Yellow	Coarse Sand		Soft	2.5	9.7
Grey	clay		Soft	9.7	13.5
Grey	gravel		packed	13.5	14.9
Grey	limestone		layered	14.9	24.3

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
0 to 6	ciment grout	4 Bag

Results of Well Yield Testing

After test of well yield, water was:	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify				
If pumping discontinued, give reason:	Static Level	2.80		8.51
Pump intake set at (m/ft): 19	1	8.00	1	8.08
Pumping rate (l/min / GPM): 56	2	8.07	2	7.94
Duration of pumping: 1 hrs + min	3	8.19	3	7.83
Final water level end of pumping (m/ft): 8.51	4	8.25	4	7.81
If flowing give rate (l/min / GPM): 80	5	8.30	5	7.80
Recommended pump depth (m/ft): 19	10	8.41	10	7
Recommended pump rate (l/min / GPM): 56	15	8.47	15	
Well production (l/min / GPM): 80	20	8.47	20	
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	25	8.47	25	
	30	8.48	30	
	40	8.48	40	
	50	8.50	50	
	60	8.51	60	

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
1555	Steel	.48	4.60	14.9	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify
1555	Open Hole		14.9	24.3	

Construction Record - Screen


Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water:	Hole Diameter
20 (m/ft)	<input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested	Depth (m/ft) From To Diameter (cm/in)
	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	0 6 21.23
		6 24.3 15.55

Well Contractor and Well Technician Information

Business Name of Well Contractor: Bourgeois well Drilling
 Well Contractor's Licence No.:
 Business Address (Street Number/Name): 1178 Route 900 East
 Municipality: NATION
 Province: Ontario Postal Code: K0A 3C0 Business E-mail Address: NA
 Bus. Telephone No. (inc. area code): 613 987 5291 Name of Well Technician (Last Name, First Name): Michael Genier
 Well Technician's Licence No.: 3493 Signature of Technician and/or Contractor: [Signature] Date Submitted: 2009 02 20



Well owner's information package delivered: Yes No

Date Package Delivered: Y|Y|Y|Y M|M D|D
Date Work Completed: 2009 02 17

Ministry Use Only
 Audit No. Z 90541
 Received: [Stamp] 2008

Address of Well Location (Street Number/Name, RR) 5473 main st Township _____ Lot _____ Concession _____
 County/District/Municipality _____ City/Town/Village Osgoode Province Ontario Postal Code _____

 UTM Coordinates Zone Easting Northing GPS Unit Make Model Mode of Operation: Undifferentiated Averaged
 NAD 83 18451891 4999099 Garmin Etrex Differentiated, specify _____

Overburden and Bedrock Materials (see instructions on the back of this form)					
General Colour	Most Common Material	Other Materials	General Description	Depth (Metres)	
				From	To
Blk	Top soil		soft, dry	0	.31
Brn	medium sand		soft, dry	.31	1.5
Brn	medium sand		soft, saturated	1.5	2.9

Hole Details		
Depth (Metres)	Diameter (Centimetres)	
	From	To
0	2.9	8.25

Water Use

Public Industrial Not used Other, specify _____
 Domestic Commercial Dewatering
 Livestock Municipal Monitoring
 Irrigation Test Hole Cooling & Air Conditioning

Method of Construction

Cable Tool Air Percussion Digging
 Rotary (Conventional) Diamond Boring
 Rotary (Reverse) Jetting Other, specify _____
 Rotary (Air) Driving Direct push

Status of Well

Test Hole Abandoned, Insufficient Supply
 Replacement Well Abandoned, Poor Water Quality
 Dewatering Well Other, specify monitoring
 Alteration (Construction) Abandoned, other, specify _____

No Casing and Screen Used Yes No

Static Water Level Test _____ Metres

Screen

Galvanized Steel Fibreglass Concrete Plastic
 Outside Diameter (Centimetres) 4.82 Slot No. 10

Water Details

Water found at Depth _____ Metres Gas Fresh Salty Sulphur Minerals
 Water found at Depth _____ Metres Gas Fresh Salty Sulphur Minerals
 Water found at Depth _____ Metres Gas Fresh Salty Sulphur Minerals

Disinfected Yes No If no, provide reason: _____ Date Master Well Completed (yyy/mm/dd) 2009/12/18

Cluster Information (Please also fill out the additional Cluster Well Information for Well Construction for each parcel of land and cluster.)

Total Wells in Cluster 4 Please indicate Number of Cluster Well Information Log Sheets Submitted _____
 Total Wells on this Property 4 1

Location of Well Cluster

Detailed Map must be provided as an attachment no larger than legal size (8.5" x 14"). Sketches are not allowed.
 Check box to confirm detailed map is provided as per Section 11.1 (3)

Consent to release additional information concerning the cluster to the Director upon request _____

Construction Details				
Inside Diameter (Centimetres)	Material (steel, plastic, fibreglass, concrete, galvanized)	Wall Thickness	Depth (Metres)	
			From	To
4.03	PVC Riser	.368	0	1.35
	Pvc screen		1.35	2.9

Annular Space/Abandonment Sealing Record			
Depth Set at (Metres)		Type of Sealant Used (Material and Type)	Volume Used (Cubic Metres)
From	To		
0	1.22	Benseal	
1.22	2.9	Sand	

Well Contractor and Well Technician Information

Business Name of Well Contractor Strata Soil Sampling Well Contractor's Licence No. 72411
 Business Address (Street No./Name, number, RR) #2-147 West Beaver Creek Municipality Richmond Hill
 Province ON Postal Code L4B 1C6 Business E-mail Address wrecords@stratasoil.com
 Bus Telephone No. (inc. area code) (905) 704-9304 Name of Well Technician (Last Name, First Name) Muir, Mike
 Well Technician's Licence No. 3448 Signature of Technician Mike Muir Date Submitted (yyy/mm/dd) 2009/12/31

Ministry Use Only

Audit No. M 05276 Well Contractor No. _____
 Date Received (yyy/mm/dd) JAN 24 2010 Date of Inspection (yyy/mm/dd) _____
 Remarks _____

Property Owner's Information

Consent

Address of Well Location (Street Number/Name, RR)		Lot	Concession	Township	County/District/Municipality	Signature of Technician/Contractor	Date (yyyy/mm/dd)
5473 main st							
City/Town/Village	Province	Postal Code	GPS Unit Make	Model	Unit Mode of Operation		
Osgoode	Ontario		Garmin	Etrex	<input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged		
					<input type="checkbox"/> Differentiated, specify:		

Well # on Sketch	UTM Coordinates		Full Depth of Hole (metres)	Hole Diameter (cm)	Method of Construction	Casing Material	Casing Length (metres)	Screen Interval (metres)		Annular Space Sealant Used	Static Water Level (metres)	Abandonment Sealant Used	Comments	Date of Completion (yyyy/mm/dd)
	Zone	Easting						Northing	From					
2	18451	891	4999094	2.9	8.25	Direct Push	PVC	1.35	1.35	2.9	Benseal			2009/12/18
3	18451	888	49991090	2.9	8.25	"	"	1.35	1.35	2.9	"			"
4	18451	890	4999083	2.9	8.25	"	"	1.35	1.35	2.9	"			"

Well Contractor and Well Technician Information



Business Name of Well Contractor		Business Address (Street Number/Name, RR)		Municipality	Province
Strata Soil Sampling		#2147 West Beaver Creek		Richmond Hill	ON
Postal Code	Business Telephone No. (inc. area code)	Well Contractor's Licence No.	Business E-mail Address		
H4B1C6	(905) 764-9304	7 2 4 1	wrecords@strata-soil.com		
Name of Well Technician (First Name, Last Name)		Well Technician's Licence No.	Date Submitted (yyyy/mm/dd)	Signature of Technician	
Mait, Mike		3 4 4 8	2009/12/31	<i>Mike Mait</i>	

Date 1st Well in Cluster Constructed (yyyy/mm/dd)	Date Last Well in Cluster Constructed (yyyy/mm/dd)
2009/12/18	2009/12/18

Ministry Use Only

Date Received (yyyy/mm/dd)	Date Inspected (yyyy/mm/dd)
JAN 21 2010	
Audit No.	Remarks
c06498	M05276

7102
Stantec Consulting Ltd. © 2009



① BORE AND INSTALL A WELL AT MW09-15 REGARDLESS OF CLEAN OR DIRTY CONDITIONS

② IF ANY OF MW09-11 TO MW09-14 SEEM "IMPACTED", STEP OUT 3 METRES AND RE-BORE.

ONLY INSTALL WELL IN "CLEAN" BOREHOLE

LEGEND:

- PROPERTY BOUNDARY
- MONITORING WELL
- ⊕ BOREHOLE
- △ BM BENCHMARK (TOP OF RESIDENTIAL WELL) ASSUMED EL. = 100m
- AST ABOVEGROUND STORAGE TANK

JAN 2 | 2010

864907 9250W 1H2L2

NOTE: THIS DRAWING ILLUSTRATES SUPPORTING INFORMATION SPECIFIC TO A STANTEC CONSULTING LTD. REPORT AND MUST NOT BE USED FOR OTHER PURPOSES.

ESTIMATED EXTENT OF SOIL IMPACTS (NOV. 19, 2009)
 PHASE II ENVIRONMENTAL SITE ASSESSMENT
 5473 MAIN STREET, OSGOODE, ONTARIO

Client: CHERRIE GRIFFITH

Job No.: 1056585
 Scale: AS SHOWN
 Date: 09/12/02
 Dwn. By: MT/GBB
 App'd By: SKR

Dwg. No.: 5

Stantec

Measurements recorded in: Metric Imperial

Abandonment
A004308

Page 1 of 1

Well Location

Address of Well Location (Street Number/Name): 5502 Main Street
 County/District/Municipality: Ottawa Carleton
 Township: National Capital Region
 City/Town/Village: Osgoode
 Province: Ontario
 UTM Coordinates: NAD 83 18 45 20 34 49 99 149
 Depth (m/ft) From: 0 To: 3.4

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	To
brown			Sand	0	3.4
well tag is enclosed					
A total of 7 wells were decommissioned					

Annular Space		
Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)
0	0.05	topsoil
0.05	0.15	hole plug
0.15	3.40	bentonite, cement, grout

Results of Well Yield Testing				
After test of well yield, water was: <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: Pump intake set at (m/ft) Pumping rate (l/min / GPM) Duration of pumping _____ hrs + _____ min Final water level end of pumping (m/ft) If flowing give rate (l/min / GPM) Recommended pump depth (m/ft) Recommended pump rate (l/min / GPM) Well production (l/min / GPM) Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No	Static Level			
	1		1	
	2		2	
	3		3	
	4		4	
	5		5	
10		10		
15		15		
20		20		
25		25		
30		30		
40		40		
50		50		
60		60		

Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input checked="" type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	
<input type="checkbox"/> Other, specify _____		<input type="checkbox"/> Other, specify _____	

Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From	To

Construction Record - Screen				Status of Well
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From	
				<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input checked="" type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input checked="" type="checkbox"/> Abandoned, other, specify decommissioned <input type="checkbox"/> Other, specify _____

Water Details		Hole Diameter	
Water found at Depth (m/ft): 1.98	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	Depth (m/ft) From: 0	To: 3.4
Water found at Depth (m/ft):	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	Diameter (cm/in):	5.7

Well Contractor and Well Technician Information

Business Name of Well Contractor: OGS INC
 Well Contractor's Licence No.: 6191614
 Business Address (Street Number/Name): 5518 Appleton Side Road
 Municipality: Almonte
 Province: Ontario
 Postal Code: K0A1A0
 Business E-mail Address: oosinc@bellnet.ca
 Bus. Telephone No. (inc. area code): 613-256-7666
 Name of Well Technician (Last Name, First Name): Echlin, Chad
 Well Technician's Licence No.: 3299
 Signature of Technician and/or Contractor: [Signature]
 Date Submitted: 20101210

Map of Well Location

Please provide a map below following instructions on the back.

Site plan and area map are enclosed.

Comments:

Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input type="checkbox"/> Yes <input type="checkbox"/> No	Y Y Y Y M M D D 20101210	Audit No.: Z107037 JAN 05 2011

Measurements recorded in: Metric Imperial

Address of Well Location (Street Number/Name) **5531 LUMBARDY DRIVE** Township **OSSEONDE** Lot **27** Concession **1**
 County/District/Municipality **OTTAWA** City/Town/Village **OSSEONDE** Province **Ontario** Postal Code **K0A2N0**
 UTM Coordinates Zone Easting Northing **18 451 980 499 9463** Municipal Plan and Sublot Number **PLAN 4M-830 Sublot RP 4R-1A828** Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)					
General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
GREY	SAND/SILT	FILL		0.00	1.83
GREY	CLAY			1.83	6.41
GREY	TILL	SAND/GRAVEL/BOUNDERS		6.41	11.95
GREY	LIMESTONE	SHALE		11.95	21.96 (72')

Annular Space		
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
0.00 11.97	Bentonite/grout	0.44

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool <input checked="" type="checkbox"/> Rotary (Conventional) <input type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify	<input type="checkbox"/> Public <input type="checkbox"/> Commercial <input type="checkbox"/> Not used <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Municipal <input type="checkbox"/> Dewatering <input type="checkbox"/> Livestock <input type="checkbox"/> Test Hole <input type="checkbox"/> Monitoring <input type="checkbox"/> Irrigation <input type="checkbox"/> Cooling & Air Conditioning <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify


Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From To	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify	
15.88	Steel A589	0.48	11.61 11.67		

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From To
			N/A

Water Details			Hole Diameter	
Water found at Depth (m/ft) 11.95	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested		Depth (m/ft) From To	Diameter (cm/in)
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested		11.67 21.96	15.24
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested			

Well Contractor and Well Technician Information			
Business Name of Well Contractor STANTON SKILLING INC	Well Contractor's License No. 4875		
Business Address (Street Number/Name) BOX 219, 157 FIVE ARCHES DR	Municipality PAREE/AM		
Province ON Postal Code K0A 2N0 Business E-mail Address stanton.drilling@bell.net			
Bus. Telephone No. (inc. area code) (413) 647-5072 Name of Well Technician (Last Name, First Name) STANTON JEFF			
Well Technician's Licence No. 00806 Signature of Technician and/or Contractor [Signature] Date Submitted 20110928			

Results of Well Yield Testing				
After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: N/A.	Static Level	4.18		
	1	4.90	1	4.77
	2	5.03	2	4.71
	3	5.07	3	4.68
	4	5.11	4	4.64
	5	5.13	5	4.62
Pump intake set at (m/ft) 12.2m (40')				
Pumping rate (l/min / GPM) 45lpm (10gpm)				
Duration of pumping 1 hrs + 0 min				
Final water level end of pumping (m/ft) 5.77m (18.9')				
If flowing give rate (l/min / GPM) N/A.				
Recommended pump depth (m/ft) 12.2m (40')				
Recommended pump rate (l/min / GPM) 45lpm (10gpm)				
Well production (l/min / GPM) > 130lpm (>50gpm)				
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
	10	5.27	10	4.54
	15	5.35	15	4.47
	20	5.43	20	4.39
	25	5.51	25	4.31
	30	5.57	30	4.30
	40	5.65	40	4.28
	50	5.74	50	4.27
	60	5.77	60	4.26



Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	20110921	Audit No. Z133002
	Date Work Completed 20110921	Received OCT 04 2011

Well Location

Address of Well Location (Street Number/Name)
3243 Robert Dowd Road

Township
Osgoode

Lot
29

Concession
1

County/District/Municipality
Ottawa Carleton

City/Town/Village
Osgoode

Province
Ontario

Postal Code

UTM Coordinates Zone Easting Northing
NAD 83 18 452190 4999169

Municipal Plan and Sublot Number

Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	To
Brown	Sand			0	1.21
Red	Sand			1.21	3.65
Grey	Sand			3.65	7.61
Grey	Clay	Stones		7.61	16.15
Grey	Limestone			16.15	57.90
Grey & White	Sandstone			57.90	83.20

Annular Space

Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
17.67	0	Grouted Bentonite Slurry	.46m³

Results of Well Yield Testing

After test of well yield, water was:
 Clear and sand free
 Other, specify _____

If pumping discontinued, give reason:

Pump intake set at (m/ft)
60.95

Pumping rate (l/min / GPM)
22.75

Duration of pumping
1 hrs + min

Final water level end of pumping (m/ft)
37.06

If flowing give rate (l/min / GPM)

Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
Static Level	8.45		
1	8.86	1	35.31
2	9.95	2	34.54
3	11.15	3	33.70
4	11.96	4	32.95
5	12.82	5	32.10
10	16.17	10	28.67
15	19.40	15	
20	22.15	20	
25	24.70	25	
30	26.95	30	
40	31.50	40	
50	35.05	50	
60	37.06	60	

Recommended pump depth (m/ft)
45.71

Recommended pump rate (l/min / GPM)
22.75

Well production (l/min / GPM)

Disinfected?
 Yes No

Method of Construction

Cable Tool Diamond
 Rotary (Conventional) Jetting
 Rotary (Reverse) Driving
 Boring Digging
 Air percussion
 Other, specify _____

Well Use

Public Commercial Not used
 Domestic Municipal Dewatering
 Livestock Test Hole Monitoring
 Irrigation Cooling & Air Conditioning
 Industrial
 Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
15.86	Steel	.48	+ .45	17.67	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)		Status of Well
			From	To	
					<input type="checkbox"/> Other, specify _____

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
81.98	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0	17.67
		17.67	83.20

Well Contractor and Well Technician Information

Business Name of Well Contractor
Capital Water Supply Ltd.

Well Contractor's Licence No.
1 5 5 8

Business Address (Street Number/Name)
Box 490

Municipality
Stittsville

Province
Ontario

Postal Code
K2S1A6

Business E-mail Address
office@capitalwater.ca

Bus. Telephone No. (inc. area code)
6138361766

Name of Well Technician (Last Name, First Name)
Miller, Stephen

Well Technician's Licence No.
0 0 9 7

Signature of Technician and/or Contractor
[Signature]

Date Submitted
2011/10/28

Map of Well Location

Please provide a map below following instructions on the back.

Comments:

Well owner's information package delivered
 Yes No

Date Package Delivered
2011/10/27

Date Work Completed
2011/10/26

Ministry Use Only

Audit No.
Z139714

Rev. FEB 09 2007

Address of Well Location (Street Number/Name) 5537 Lombardy Street		Township Osgoode	Lot	Concession
County/District/Municipality Ottawa Carleton		City/Town/Village Osgoode	Province Ontario	Postal Code
UTM Coordinates	Zone	Easting	Northing	Municipal Plan and Sublot Number
NAD	83	18451992	4999614	

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Soil	Stones		0	3.35
Grey	Sandy Soil	Boulders	Loose	3.35	7.61
Grey	Till	Large Boulders	Packed	7.61	14.32
Grey	Limestone		Medium	14.32	54.86
Grey & White	Sandstone		Hard	54.86	75.58

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
From: 15.84 To: 0	Grouted Bentonite Slurry	.504m³

Results of Well Yield Testing

After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: Pump intake set at (m/ft) 30.47 Pumping rate (l/min / GPM) 54.5 Duration of pumping 1 hrs + _____ min Final water level end of pumping (m/ft) 8.19 If flowing give rate (l/min / GPM) Recommended pump depth (m/ft) 22.85 Recommended pump rate (l/min / GPM) 45.5 Well production (l/min / GPM) Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Static Level	5.46		
	1	6.52	1	6.49
	2	7.05	2	5.95
	3	7.26	3	5.80
	4	7.42	4	5.72
	5	7.53	5	5.68
10	7.86	10	5.58	
15	7.99	15	5.51	
20	8.05	20	5.51	
25	8.10	25	5.48	
30	8.12	30	5.47	
40	8.14	40	5.46	
50	8.17	50	5.46	
60	8.19	60	5.46	

Method of Construction

Cable Tool Diamond Public Commercial Not used

Rotary (Conventional) Jetting Domestic Municipal Dewatering

Rotary (Reverse) Driving Livestock Test Hole Monitoring

Boring Digging Irrigation Cooling & Air Conditioning

Air percussion Industrial Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
27.13	Open		0	15.84	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
15.86	Steel	.48	+ .45	15.84	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Hole Diameter	
		Depth (m/ft)	Diameter (cm/in)
71.62(m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		From: 0 To: 15.84	15.86
(m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____		15.84	75.58
(m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____			14.91

Well Contractor and Well Technician Information

Business Name of Well Contractor: Capital Water Supply Ltd. Well Contractor's Licence No.: 1 5 5 8

Business Address (Street Number/Name): Box 490 Municipality: Stittsville

Province: Ontario Postal Code: K2S1A6 Business E-mail Address: office@capitalwater.ca

Bus. Telephone No. (inc. area code): 6138361766 Name of Well Technician (Last Name, First Name): Miller, Stephen

Well Technician's Licence No.: 0097 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20160322

Map of Well Location

Please provide a map below following instructions on the back.

Comments:

Ministry Use Only

Well owner's information package delivered: Yes No

Date Package Delivered: 20160310

Date Work Completed: 20160309

Audit No: Z188416

Received: AUG 29 2016



Measurements recorded in: Metric Imperial

Page _____ of _____

Well Owner's Information

First Name, Last Name / Organization, E-mail Address, Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number, Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Method of Construction and Well Use checkboxes

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel), Wall Thickness (cm/in), Depth (m/ft) From, To, Status of Well

Construction Record - Screen table with columns: Outside Diameter (cm/in), Material (Plastic, Galvanized, Steel), Slot No., Depth (m/ft) From, To

Water Details and Hole Diameter tables

Well Contractor and Well Technician Information form

Results of Well Yield Testing table with columns: Draw Down, Recovery, Time (min), Water Level (m/ft)

Map of Well Location form

Comments, Well owner's information package delivered, Date Package Delivered, Date Work Completed, Ministry Use Only (Audit No., Received)



Measurements recorded in: Metric Imperial

A182515 Tag #: A182515

S-21166 Page of

Well Owner's Information

First Name, Last Name / Organization (CITY OF OTTAWA), E-mail Address, Well Constructed by Well Owner

Mailing Address (Street Number/Name), Municipality (Ottawa), Province (ON), Postal Code (K1P1J1), Telephone No.

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession

County/District/Municipality, City/Town/Village (Osgoode), Province (Ontario), Postal Code

UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number, Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used, Volume Placed (m³/ft³)


Results of Well Yield Testing table with columns: Draw Down, Recovery, Time (min), Water Level (m/ft)

Method of Construction, Well Use (Cable Tool, Rotary, Boring, etc.)

Construction Record - Casing table with columns: Inside Diameter, Open Hole OR Material, Wall Thickness, Depth (m/ft) From, To, Status of Well

Construction Record - Screen table with columns: Outside Diameter, Material, Slot No., Depth (m/ft) From, To

Water Details and Hole Diameter tables



Well Contractor and Well Technician Information (Strata Drilling Group, 7219, 165 Shields Court, Markham)

Ministry Use Only (Audit No. 2212340, Date Work Completed, Received)



Measurements recorded in: Metric Imperial

A182517

Tag#: A182517

S-2166

Page of

Well Owner's Information

First Name Last Name / Organization E-mail Address Well Constructed by Well Owner

Mailing Address (Street Number/Name) Municipality Province Postal Code Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name) Township Lot Concession

County/District/Municipality City/Town/Village Province Ontario Postal Code

UTM Coordinates Zone Easting Northing Municipal Plan and Sublot Number Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with 5 columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From To

Annular Space table with 3 columns: Depth Set at (m/ft) From To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Results of Well Yield Testing table with columns for Draw Down and Recovery, and rows for various pumping parameters

Method of Construction and Well Use table with checkboxes for various construction methods and well uses

Construction Record - Casing table with columns for Inside Diameter, Open Hole OR Material, Wall Thickness, Depth (m/ft) From To, and Status of Well

Construction Record - Screen table with columns for Outside Diameter, Material, Slot No., Depth (m/ft) From To, and Status of Well

Water Details and Hole Diameter table with columns for Water found at Depth, Kind of Water, and Hole Diameter

Well Contractor and Well Technician Information table with fields for Business Name, Address, Licence No., and Technician details

Map of Well Location section with a hand-drawn map showing well location relative to 'OSGOODE MAN' and 'REGINA ROAD'.



Measurements recorded in: Metric Imperial

A182518 Tag#: A182518

S-2116 Page of

Well Owner's Information

First Name, Last Name / Organization (City of Ottawa), E-mail Address, Mailing Address (110 Laurier Avenue West, 5th Floor), Municipality (Ottawa), Province (ON), Postal Code (K1P1S1), Telephone No.

Well Location

Address of Well Location (320 Reid's Lane), Township, Lot, Concession, County/District/Municipality, City/Town/Village (Osgoode), Province (Ontario), Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number.

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To. Includes entries for top soil, sand, silt, and clay.

Annular Space table with columns: Depth Set at (m/ft) From, To; Type of Sealant Used; Volume Placed (m³/ft³). Includes entries for concrete/mortar, bentonite, and filter sand.

Method of Construction and Well Use checkboxes. Includes options like Cable Tool, Rotary, Boring, Air percussion, and Well Use categories like Public, Commercial, Test Hole, etc.


Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material, Wall Thickness (cm/in), Depth (m/ft) From, To. Includes entry for 4.03 PVC casing.

Construction Record - Screen table with columns: Outside Diameter (cm/in), Material, Slot No., Depth (m/ft) From, To. Includes entry for 4.82 PVC screen.

Water Details and Hole Diameter tables. Water Details include kind of water (Fresh, Untested, Gas, Other) and depth. Hole Diameter includes depth and diameter.

Well Contractor and Well Technician information. Includes Business Name (Arden Drilling Group), Licence No., Business Address (165 Shields Court, Markham), Province (ON), Postal Code (L3R9V2), Business E-mail Address, Bus. Telephone No., Name of Well Technician (McLay, James), Well Technician's Licence No., Signature, and Date Submitted.

Results of Well Yield Testing table. Includes sections for After test of well yield, water was; Draw Down (Time, Water Level); Recovery (Time, Water Level); Pumping rate; Duration of pumping; Final water level end of pumping; If flowing give rate; Recommended pump depth; Recommended pump rate; Well production; Disinfected?.



Comments section and Ministry Use Only section. Includes Well owner's information package delivered status, Date Package Delivered, Date Work Completed, Audit No. (212338), and Received date (DEC 22 2017).



Measurements recorded in: Metric Imperial

Tag#: A193395

Page of

Well Owner's Information

First Name, Last Name / Organization, E-mail Address, Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number, Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Method of Construction and Well Use checkboxes: Cable Tool, Rotary (Conventional/Reverse), Boring, Air percussion, Diamond, Jetting, Driving, Digging, Public, Commercial, Not used, Domestic, Municipal, Dewatering, Livestock, Test Hole, Monitoring, Irrigation, Cooling & Air Conditioning, Industrial, Other, specify

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel), Wall Thickness (cm/in), Depth (m/ft) From, To, Status of Well

Construction Record - Screen table with columns: Outside Diameter (cm/in), Material (Plastic, Galvanized, Steel), Slot No., Depth (m/ft) From, To

Water Details and Hole Diameter tables

Well Contractor and Well Technician Information: Business Name of Well Contractor, Well Contractor's Licence No., Business Address, Municipality, Province, Postal Code, Business E-mail Address, Bus. Telephone No. (inc. area code), Name of Well Technician (Last Name, First Name), Well Technician's Licence No., Signature of Technician and/or Contractor, Date Submitted

Results of Well Yield Testing table with columns: Draw Down (Time, Water Level), Recovery (Time, Water Level), Pump intake set at (m/ft), Pumping rate (l/min / GPM), Duration of pumping, Final water level end of pumping (m/ft), If flowing give rate (l/min / GPM), Recommended pump depth (m/ft), Recommended pump rate (l/min / GPM), Well production (l/min / GPM), Disinfected?

Map of Well Location: Please provide a map below following instructions on the back. Includes a hand-drawn map showing Lombardy Drive, well location #5566, and dimensions (80' x 80').



Measurements recorded in: Metric Imperial

Tag# A193411

Page _____ of _____

Well Owner's Information

First Name, Last Name / Organization, E-mail Address, Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location

Address of Well Location (Street Number/Name), Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code, UTM Coordinates, Zone, Easting, Northing, Municipal Plan and Sublot Number

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (m/ft) From, To

Annular Space table with columns: Depth Set at (m/ft) From, To, Type of Sealant Used (Material and Type), Volume Placed (m³/ft³)

Method of Construction and Well Use checkboxes: Cable Tool, Rotary, Boring, Air percussion, Diamond, Jetting, Driving, Digging, Public, Commercial, Not used, Domestic, Municipal, Dewatering, Livestock, Test Hole, Monitoring, Irrigation, Cooling & Air Conditioning, Industrial, Other

Construction Record - Casing table with columns: Inside Diameter (cm/in), Open Hole OR Material, Wall Thickness (cm/in), Depth (m/ft) From, To, Status of Well


Construction Record - Screen table with columns: Outside Diameter (cm/in), Material, Slot No., Depth (m/ft) From, To

Water Details and Hole Diameter tables

Well Contractor and Well Technician Information: Business Name, Licence No., Business Address, Municipality, Province, Postal Code, Business E-mail Address

Well Contractor and Well Technician Information: Bus. Telephone No., Name of Well Technician, Well Technician's Licence No., Signature of Technician and/or Contractor, Date Submitted

Results of Well Yield Testing table with columns: Draw Down (Time, Water Level), Recovery (Time, Water Level), Pumping rate, Duration of pumping, Final water level end of pumping, Recommended pump depth, Recommended pump rate, Well production, Disinfected?



Comments: 145 Chlorine after Drilling, 4 Chlorine after Yield Test. Well owner's information package delivered, Date Package Delivered, Date Work Completed, Ministry Use Only: Audit No. 2243019

Measurements recorded in: Metric Imperial

Tag# A193412

Page _____ of _____

Well Owner's Information

 First Name: _____ Last Name / Organization: Beresite Construction E-mail Address: _____ Well Constructed by Well Owner

 Mailing Address (Street Number/Name): 2354 Summerside Drive Municipality: Manotick ON Province: ON Postal Code: K4M1B4 Telephone No. (inc. area code): 61337151711
Well Location

 Address of Well Location (Street Number/Name): 5554 Lombardy Drive Township: Osacode Lot: pt lot 31 Plan 4m-830 Concession: _____

 County/District/Municipality: Ottawa City/Town/Village: Osacode Province: Ontario Postal Code: K0A0W0

 UTM Coordinates: Zone 18 Easting 452066 Northing 4999583 Municipal Plan and Sublot Number: Part 5116 RP43-14828 Other: _____

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Clay		Packed	0	8'
Brown	Sand		Packed	8'	15'
Grey	Sand	Gravel	Packed	15'	51'6"
Grey	Limestone		Hard	51'6"	121'

Annular Space		
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
51'6" 46'6"	Cement Pressure Grouted	6.77
46'6" 0	Bentonite Pressure Grouted	13.54

Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input checked="" type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	
<input type="checkbox"/> Other, specify _____		<input type="checkbox"/> Other, specify _____	

Construction Record - Casing			Status of Well		
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		
			From	To	
97/8"	(mud) (Open Hole)		0	56'6"	<input checked="" type="checkbox"/> Water Supply
6 1/4"	Steel	0.188	0	56'6"	<input type="checkbox"/> Replacement Well
6 1/8"	Open Hole		56'6"	121'	<input type="checkbox"/> Test Hole


Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)
			From
			To

Water Details		Hole Diameter	
Water found at Depth: <u>115' (m/ft)</u> <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft) From: _____ To: _____	Diameter (cm/in): _____
Water found at Depth: _____ (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	0 56'6"	97/8"
Water found at Depth: _____ (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	56'6"	121' 6 1/8"

Well Contractor and Well Technician Information			
Business Name of Well Contractor: <u>14254860 Ontario Ltd</u>		Well Contractor's Licence No.: <u>4181717</u>	
Business Address (Street Number/Name): <u>PO BOX 1083</u>		Municipality: <u>Prescott</u>	
Province: <u>ON</u>	Postal Code: <u>K0A0W0</u>	Business E-mail Address: _____	

Bus. Telephone No. (inc. area code): <u>613912541825</u>	Name of Well Technician (Last Name, First Name): <u>Ferawson, Johnathon</u>
Well Technician's Licence No.: <u>2181519</u>	Signature of Technician and/or Contractor: _____ Date Submitted: <u>2016/11/30</u>

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: _____		Static Level	<u>16.9</u>		<u>56.4</u>
Pump intake set at (m/ft): <u>110'</u>		1	<u>21.05</u>	1	<u>50.85</u>
Pumping rate (l/min / GPM): <u>7 gpm</u>		2	<u>23.15</u>	2	<u>45.7</u>
Duration of pumping: <u>1 hrs + 0 min</u>		3	<u>25.2</u>	3	<u>42.4</u>
Final water level end of pumping (m/ft): <u>56.4</u>		4	<u>27</u>	4	<u>39.3</u>
If flowing give rate (l/min / GPM): _____		5	<u>28.65</u>	5	<u>36</u>
		10	<u>35</u>	10	<u>23.4</u>
		15	<u>39.5</u>	15	<u>18.3</u>
		20	<u>43</u>	20	<u>17.6</u>
Recommended pump depth (m/ft): <u>110'</u>		25	<u>45.8</u>	25	<u>17.05</u>
Recommended pump rate (l/min / GPM): <u>7 gpm</u>		30	<u>47.5</u>	30	<u>17.025</u>
Well production (l/min / GPM): _____		40	<u>52.8</u>	40	<u>17</u>
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <u>140</u>		50	<u>54.85</u>	50	<u>17</u>
		60	<u>56.4</u>	60	<u>16.975</u>


 Comments: 140 Chlorine after Drilling & Chlorine after Yield Test

Well owner's information package delivered: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: <u>2016/11/30</u>	Ministry Use Only Audit No.: <u>2243020</u> Received: <u>DEC 1 6 2016</u>
Date Work Completed: <u>2016/11/30</u>		



Measurements recorded in: Metric Imperial

A207699

Page of

Address of Well Location (Street Number/Name) **5549 Lombardy Drive** Township **Osgoode** Lot **27** Concession **1**

County/District/Municipality **Ottawa Carleton** City/Town/Village **Osgoode** Province **Ontario** Postal Code **K0A 2**

UTM Coordinates Zone Easting Northing Municipal Plan and Sublot Number Other

NAD 83 18 452000 4999637 4M830 S/L 29

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
	Sand + Gravel + boulders + Clay			0'	43'
Grey	Limestone			43'	138'
Grey	Limestone			138'	233'
Grey	Limestone			233'	240'

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
49' - 39'	Neat cement	10.8
39' - 0'	Bentonite slurry	50.4

Results of Well Yield Testing

After test of well yield, water was:
 Clear and sand free
 Other, specify **Not tested**

If pumping discontinued, give reason: **X**

Pump intake set at (m/ft) **220**

Pumping rate (l/min / GPM) **20**

Duration of pumping **1 hrs + 0 min**

Final water level end of pumping (m/ft) **21.7'**

If flowing give rate (l/min / GPM) **X**

Recommended pump depth (m/ft) **140'**

Recommended pump rate (l/min / GPM) **20**

Well production (l/min / GPM) **20**

Disinfect? Yes No

Time (min)	Draw Down (m/ft)		Recovery (m/ft)	
	Water Level	Time	Water Level	Time
Static Level	16.6"		21.7"	
1	19.9	1	19.7	
2	20.1	2	18.2	
3	20.4	3	17.9	
4	20.7	4	17.7	
5	20.9	5	17.5	
10	21.2	10	17.1	
15	21.5	15	16.7	
20	21.7	20	16.6	
25	21.7	25	16.6	
30	21.7	30	16.6	
40	21.7	40	16.6	
50	21.7	50	16.6	
60	21.7	60	16.6	

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify _____
 Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	
			From	To
6 1/4"	Steel	.188"	+2'	49'
6"	Open Hole		49'	240'

Status of Well

Water Supply
 Replacement Well
 Test Hole
 Recharge Well
 Dewatering Well
 Observation and/or Monitoring Hole
 Alteration (Construction)
 Abandoned, Insufficient Supply
 Abandoned, Poor Water Quality
 Abandoned, other, specify _____
 Other, specify _____

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested
138'	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____
233'	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____
	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____

Hole Diameter

Depth (m/ft)	Diameter (cm/in)
0' - 49'	9 3/4"
49' - 240'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: **Air Rock Drilling Co. Ltd.** Well Contractor's Licence No.: **1119**

Business Address (Street Number/Name): **6659 Franktown Rd. #1** Municipality: **Richmond**

Province: **ON** Postal Code: **K0A 2Z0** Business E-mail Address: **air-rock@sympatico.ca**

Bus. Telephone No. (inc. area code): **8188852170** Name of Well Technician (Last Name, First Name): **Hogan, Dan**

Well Technician's Licence No.: **13058** Signature of Technician and/or Contractor: *[Signature]* Date Submitted: **10 31 2016**

Map of Well Location

Please provide a map below following instructions on the back.

Comments: **10HP 10GPM - Set at 140 Feet**

Well owner's information package delivered: Yes No

Date Package Delivered: **2016 09 30**

Date Work Completed: **2016 09 28**

Ministry Use Only

Audit No.: **2237037**

Received: **NOV 28 2016**



Measurements recorded in: Metric Imperial

Address of Well Location (Street Number/Name) **5495 Osgoode Main** Township **Osgoode** Lot **X** Concession **X**

County/District/Municipality **Ottawa Carleton** City/Town/Village **Osgoode** Province **Ontario** Postal Code

UTM Coordinates Zone **18** Easting **451988** Northing **4999137** Municipal Plan and Sublot Number **Plan 393** Other **S/L 44**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)	
				From	To
	Sand			0	27
	Gravel	Soulders		27	44
Grey	Limestone			44	207
Grey	Sandstone			207	234
Grey	Sandstone			234	240

Annular Space

Depth Set at (m)	Type of Sealant Used (Material and Type)	Volume Placed (m³)
From	To	
0	Neat cement	10.93
44	Bentonite slurry	18.5

Results of Well Yield Testing

After test of well yield, water was:		Draw Down		Recovery	
<input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason:		Static Level	27'4"		28.11"
Pump intake set at (m)		1	28.2	1	27.9
Pumping rate (l/min / GPM)		2	28.3	2	27.8
Duration of pumping		3	28.4	3	27.7
1 hrs + 0 min		4	28.5	4	27.6
Final water level end of pumping (m/ft)		5	28.6	5	27.4
28.1"		10	28.8	10	27.4
If flowing give rate (l/min / GPM)		15	28.8	15	27.4
X		20	28.8	20	27.4
Recommended pump depth (m)		25	28.8	25	27.4
140'		30	28.1	30	27.4
Recommended pump rate (l/min / GPM)		40	28.1	40	27.4
20 GPM		50	28.1	50	27.4
Well production (l/min / GPM)		60	28.1	60	27.4
20					
Disinfected?					
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No					

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Municipal Dewatering
 Rotary (Reverse) Driving Domestic Test Hole Monitoring
 Boring Digging Livestock Irrigation Cooling & Air Conditioning
 Air percussion Industrial Other, specify
 Other, specify

Construction Record - Casing

Inside Diameter (cm)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm)	Depth (m)		Status of Well
			From	To	
6 1/4"	Steel	.188"	+2'	54'	<input checked="" type="checkbox"/> Water Supply
6 1/4"	Open Hole		54'	240'	<input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details


Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Hole Diameter	
		Depth (m/ft)	Diameter (cm/in)
From	To	From	To
234	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	0' 54'	9 3/4"
		54' 240'	6 1/4"

Well Contractor and Well Technician Information

Business Name of Well Contractor: **Air Rock Drilling Co. Ltd.** Well Contractor's Licence No.: **1118**

Business Address (Street Number/Name): **555 Forest Street, Ottawa** Municipality: **Ottawa**

Province: **ON** Postal Code: **K1A 2Z0** Business E-mail Address: **air-rock@sympatico.ca**



Business Telephone No. (inc. area code): **613-838-2170** Name of Well Technician (Last Name, First Name): **Hanna, Jeremy**

Well Technician's Licence No.: **13002** Signature of Technician and/or Contractor: *[Signature]* Date Submitted: **2018 07 31**

Well owner's information package delivered: Yes No

Date Package Delivered: **2018 07 13**

Date Work Completed: **2018 07 10**

Ministry Use Only

Audit No.: **276999**

Received: **SEP 10 2018**

Measurements recorded in: Metric Imperial

Tag #: A 236933

Page of

Address of Well Location (Street Number/Name) 5533 Lombardy Drive		Township Osgoode	Lot pt lot #27	Concession Con #1
County/District/Municipality Ottawa-Carleton		City/Town/Village Ottawa	Province Ontario	Postal Code K0A2W0
UTM Coordinates Zone NAD 83	Easting 18451978	Northing 4999488	Municipal Plan and Sublot Number Plan 4m-830 P+81k 46+52	Other

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
Brown	Sand	Stones	Packed	0	15'
Grey	Sand	Stones	Packed	15'	42'
Grey	Clay (Till)	Stones + Boulders	Packed	42'	51'6"
Grey	Limestone		Layered	51'6"	121'

Annular Space		
Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)
56'6"	46'6"	Cement Pressure Grouted
46'6"	0	Bentonite Pressure Grouted
		Volume Placed (m³/ft³)
		6.77
		13.54

Method of Construction	Well Use
<input type="checkbox"/> Cable Tool <input checked="" type="checkbox"/> Rotary (Conventional) <input type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify _____	<input type="checkbox"/> Diamond <input type="checkbox"/> Jetting <input type="checkbox"/> Driving <input type="checkbox"/> Digging <input type="checkbox"/> Public <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Livestock <input type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify _____

Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	
			From	To
6 1/4"	Steel	188	+2'	56'6"
6 1/6"	Open Hole		56'5"	121'

Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft) From	Diameter (cm/in) To
65'	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0	56'6" 9 7/8"
108'	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	56'6"	121' 6 1/6"

Well Contractor and Well Technician Information			
Business Name of Well Contractor 1425486 Ontario Ltd Plas Splash Well Drilling		Well Contractor's Licence No. 418177	
Business Address (Street Number/Name) PO BOX 1083		Municipality Prescott	
Province ON	Postal Code K0E1T0	Business E-mail Address	
Bus. Telephone No. (inc. area code) 613 925 4885	Name of Well Technician (Last Name, First Name) Ferauwon, Johnathon		
Well Technician's Licence No. 4101412	Signature of Technician and/or Contractor		Date Submitted 2019/03/28

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____		Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason:		Static Level	14		15.85
Pump intake set at (m/ft) 110'		1	15.2	1	14.65
Pumping rate (l/min / GPM) 20 gpm		2	15.3	2	14.6
Duration of pumping 1 hrs + 0 min		3	15.4	3	14.55
Final water level end of pumping (m/ft) 15.85		4	15.4	4	14.5
If flowing give rate (l/min / GPM)		5	15.45	5	14.5
Recommended pump depth (m/ft) 100'		10	15.5	10	14.4
Recommended pump rate (l/min / GPM) 10 gpm		15	15.65	15	14.35
Well production (l/min / GPM)		20	15.7	20	14.3
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No 140		25	15.75	25	14.3
		30	15.8	30	14.25
		40	15.8	40	14.2
		50	15.8	50	14.2
		60	15.85	60	14.2

Map of Well Location	
Please provide a map below following instructions on the back.	

Comments: 140 Chlorine after Drilling 0 Chlorine after Yield Test	
Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered 2019/03/28
Date Work Completed 2019/03/28	Ministry Use Only Audit No. Z292468 MAY 01 2019 Received

Measurements recorded in: Metric Imperial

A304984

Page of

Well Owner's Information

First Name, Last Name/Organization (Vibration Studios Inc.), E-mail Address, Well Constructed by Well Owner

Mailing Address (Street Number/Name), Municipality, Province, Postal Code, Telephone No. (inc. area code)

Well Location: Address of Well Location, Township, Lot, Concession, County/District/Municipality, City/Town/Village, Province, Postal Code

Overburden and Bedrock Materials/Abandonment Sealing Record

Table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth From, Depth To

Annular Space: Depth Set at, Type of Sealant Used, Volume Placed

Method of Construction, Well Use


Construction Record - Casing: Inside Diameter, Open Hole OR Material, Wall Thickness, Depth, Status of Well

Construction Record - Screen: Outside Diameter, Material, Slot No., Depth, Status of Well

Water Details: Water found at Depth, Kind of Water, Hole Diameter: Depth, Diameter

Well Contractor and Well Technician Information: Business Name, Licence No., Address, E-mail, Technician Name, Signature

Results of Well Yield Testing: Draw Down, Recovery, Time, Water Level



Comments, Well owner's information package delivered, Date Package Delivered, Date Work Completed, Ministry Use Only



Measurements recorded in: Metric Imperial

Address of Well Location (Street Number/Name) **5550 Osgoode main st** Township **Osgoode** Lot _____ Concession _____
 County/District/Municipality **Ottawa** City/Town/Village **Osgoode** Province **Ontario** Postal Code **K0A2W0**
 UTM Coordinates Zone, Easting Northing Municipal Plan and Sublot Number Other
 NAD **83** **1804522424999306**

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From To
			Raised well casing above grade in accordance with regulation 903 Well was sanitized	

Annular Space		
Depth Set at (m/ft) From To	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)
	N/A	


Results of Well Yield Testing				
After test of well yield, water was: <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: Pump intake set at (m/ft) Pumping rate (l/min / GPM) Duration of pumping _____ hrs + _____ min Final water level end of pumping (m/ft) If flowing give rate (l/min / GPM) Recommended pump depth (m/ft) Recommended pump rate (l/min / GPM) Well production (l/min / GPM) Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No	Static Level			
	1		1	
	2		2	
	3		3	
	4		4	
	5		5	
10		10		
15		15		
20		20		
25		25		
30		30		
40		40		
50		50		
60		60		

Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Stilling	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Zooling & Air Conditioning
<input type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Other, specify _____		<input type="checkbox"/> Other, specify _____	

Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From To	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
	N/A			

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From To
	N/A		

Water Details		Hole Diameter	
Water found at Depth (m/ft) 6 feet	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft) From To	Diameter (cm/in)
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	5" 5"	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested		



Well Contractor and Well Technician Information

Business Name of Well Contractor **CSN electrical & Plumbing** Well Contractor's Licence No. **6364**
 Business Address (Street Number/Name) **5640 manotick main st** Municipality **Ottawa**
 Province **Ont** Postal Code **K4A1G3** Business E-mail Address **Plumbing@csn-electric.ca**
 Bus. Telephone No. (inc. area code) **6136923284** Name of Well Technician (Last Name, First Name) **Sadler Johnston**
 Well Technician's Licence No. **5689** Signature of Technician and/or Contractor *[Signature]* Date Submitted **20210806**

Comments: **Osgoode main st**

Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered 20210806	Ministry Use Only Audit No. Z319370 AUG 26 2021 Received _____
Date Work Completed 20210806		



Well Tag No. (Place Sticker and/or Print Below)

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: Metric Imperial

NO TAG FOUND

Page of

CITY OF OTTAWA

Address of Well Location (Street Number/Name): 3200 Reids Lane
 Township: Oracode Ottawa
 Lot: [blank]
 Concession: [blank]
 County/District/Municipality: [blank]
 City/Town/Village: Oracode Ottawa
 Province: Ontario
 Postal Code: [blank]
 UTM Coordinates Zone: NAD 83
 Easting: 18 45 19 52
 Northing: 49 99 25 4
 Municipal Plan and Sublot Number: [blank]
 Other: [blank]

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To

Annular Space

Depth Set at (m/ft) From	Depth Set at (m/ft) To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
0	2	Hole Plug	
2	13	Bentonite Slurry	

Results of Well Yield Testing

After test of well yield, water was: <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason: 	Static Level			
	1		1	
	Pump intake set at (m/ft)	2	2	
	Pumping rate (l/min / GPM)	3	3	
	Duration of pumping _____ hrs + _____ min	4	4	
	Final water level end of pumping (m/ft)	5	5	
If flowing give rate (l/min / GPM)	10		10	
	15		15	
	20		20	
	25		25	
	30		30	
	40		40	
Recommended pump depth (m/ft)	50		50	
	60		60	
Recommended pump rate (l/min / GPM)				
Well production (l/min / GPM)				
Disinfected? <input type="checkbox"/> Yes <input type="checkbox"/> No				

Method of Construction

Cable Tool Diamond Public Commercial Not used
 Rotary (Conventional) Jetting Domestic Municipal Dewatering
 Rotary (Reverse) Driving Livestock Test Hole Monitoring
 Boring Digging Irrigation Cooling & Air Conditioning
 Air percussion Industrial
 Other, specify hand pull Other, specify _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
2.047	PVC	1.54	2	3	<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input checked="" type="checkbox"/> Abandoned, other, specify <u>not needed</u> <input type="checkbox"/> Other, specify _____

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To
2.375	PVC	60	3	13

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	Hole Diameter	
		Depth (m/ft) From	Depth (m/ft) To

Well Contractor and Well Technician Information

Business Name of Well Contractor: Strata Drilling Group
 Well Contractor's Licence No.: 222411
 Business Address (Street Number/Name): 165 Shields Court
 Municipality: Markham
 Province: ON Postal Code: L3R 8B2 Business E-mail Address: wrecords@strataoil.com
 Bus. Telephone No. (inc. area code): 905 940 7919 Name of Well Technician (Last Name, First Name): Beatty, Brian
 Well Technician's Licence No.: 3516 Signature of Technician and/or Contractor: _____ Date Submitted: _____

Map of Well Location

Please provide a map below following instructions on the back.

MW03-01
ON MAP

Comments: Dillon General Contractors

Well owner's information package delivered: Yes No

Date Package Delivered: 20190108
 Date Work Completed: 20190108

Ministry Use Only
 Audit No.: 2302833
 Received: MAR 08 2019



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

FILE LOCATION: \\ellon.ca\DILLON_DP\Ottawa\Ottawa CAD\CAD\2018\163971 Reids Lane Csgcode\MKD\Fig2_MW\andSelf\runplot.mxd

MAR 08 2019

C-7241 Z302833



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

MAR 08 2019

2302886 1241

MAP D
DATA I
MAP C
MAP P

0 7

MC
FIG1



ATTACHMENT C


GRAIN SIZE ANALYSES OF REPRESENTATIVE SOIL SAMPLES

Grain Size Distribution Analysis



Kollaard Associates
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075
SAMPLE PASSING								100.0	99.8	99.3	89.2	21.4	5.8	3.7

CLIENT: Crestview Innovations Inc.	
PROJECT: 3200 Reids Lane, Ossgoode	OUR REF.: 210064
TYPE OF MATERIAL: Sand	INTENDED USE: Residential
DATE SAMPLED: February 3, 2021	DATE TESTED: February 11, 2021
SOURCE: BH1 - 0.76-1.37	SAMPLE NO: SS2
REMARKS:	



Kollaard Associates
Engineers

Box 189, 210 Prescott Street
Kemptville, Ontario K0G 1J0
(613) 860-0923, FAX: (613) 258-0475

Dean Tataryn

Issued by:

Dean Tataryn, B.E.S., EP

Date:


February 12, 2021

Grain Size Distribution Analysis



Kollaard Associates
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075
SAMPLE PASSING									100.0	99.0	83.7	19.0	7.1	5.2

CLIENT: Crestview Innovations Inc.	
PROJECT: 3200 Reids Lane, Ossgoode	OUR REF.: 210064
TYPE OF MATERIAL: Sand	INTENDED USE: Residential
DATE SAMPLED: February 3, 2021	DATE TESTED: February 11, 2021
SOURCE: BH3 - 0.76 - 1.37	SAMPLE NO: SS2
REMARKS:	



Kollaard Associates
Engineers

Box 189, 210 Prescott Street
Kemptville, Ontario K0G 1J0
(613) 860-0923, FAX: (613) 258-0475

Issued by:

Date:


Dean Tartaryn, B.E.S. EP
February 12, 2021

Grain Size Distribution Analysis



Kollaard Associates
Engineers

SAND



SIEVE SIZE (mm)	76.2	53	26.5	19.0	16	13.2	9.5	4.75	2.36	1.180	0.600	0.300	0.15	0.075
SAMPLE PASSING									100.0	99.9	93.8	17.5	4.7	3.4

CLIENT: Crestview Innovations Inc.

PROJECT: 3200 Reids Lane, Ossgoode

OUR REF.: 210064

TYPE OF MATERIAL: Sand

INTENDED USE: Residential

DATE SAMPLED: February 3, 2021

DATE TESTED: February 11, 2021

SOURCE: BH5 - 0.76 - 1.37

SAMPLE NO: SS2

REMARKS:



Kollaard Associates
Engineers

Box 189, 210 Prescott Street
Kemptville, Ontario K0G 1J0
(613) 860-0923, FAX: (613) 258-0475


Issued by:

Date:

Dean Tataryn

Dean Tataryn, B.E.S. EP
February 12, 2021

Unified Soil Classification System



Sample ID	Depth	% Gravel	% Sand	% Silt	% Clay
BH2 SS9	7.62-8.22 m	17.7	32.1	45.2	5.0
BH4 SS7	4.52-5.18 m	0.0	85.9	10.1	4.0

GRAIN SIZE DISTRIBUTION

Figure No.

Kollaard Associates Inc. File # 210064

3200 Reid Lane, Osgoode

Project No. 122410003



PROJECT DETAILS

Client:	Kollaard Associates Inc. File # 210064	Project No.:	122410003
Project:	3200 Reid Lane, Osgoode	Test Method:	LS702
Material Type:	Soil	Sampled By:	Kollaard Associates Inc.
Source:	BH2	Date Sampled:	February 4, 2021
Sample No.:	SS9	Tested By:	Denis Rodriguez
Sample Depth:	7.62-8.22 m	Date Tested:	February 15, 2021

SOIL INFORMATION

Liquid Limit (LL)	
Plasticity Index (PI)	
Soil Classification	
Specific Gravity (G _s)	2.750
Sq. Correction Factor (α)	0.978
Mass of Dispersing Agent/Litre	40
	g

CALCULATION OF DRY SOIL MASS

Oven Dried Mass (W _d), (g)	101.04
Air Dried Mass (W _a), (g)	101.21
Hygroscopic Corr. Factor (F=W _a /W _d)	0.9983
Air Dried Mass in Analysis (M _a), (g)	56.58
Oven Dried Mass in Analysis (M _d), (g)	56.48
Percent Passing 2.0 mm Sieve (P ₂₀), (%)	75.62
Sample Represented (W _v), (g)	74.69

WASH TEST DATA

Oven Dry Mass in Hydrometer Analysis (g)	56.48
Sample Weight after Hydrometer and Wash (g)	20.26
Percent Passing No. 200 Sieve (%)	64.1
Percent Passing Corrected (%)	48.50

PERCENT LOSS IN SIEVE

Sample Weight Before Sieve (g)	1062.00
Sample Weight After Sieve (g)	1059.20
Percent Loss in Sieve (%)	0.26

SIEVE ANALYSIS

Sieve Size mm	Cum. Wt. Retained	Percent Passing
75.0		100.0
63.0		100.0
53.0		100.0
37.5		100.0
26.5	0.0	100.0
19.0	25.1	97.6
13.2	76.8	92.8
9.5	122.9	88.4
4.75	187.6	82.3
2.00	258.9	75.6
Total (C + F) ¹	1059.20	
0.850	4.50	69.60
0.425	7.77	65.22
0.250	10.43	61.66
0.106	16.24	53.88
0.075	18.98	50.21
PAN	20.26	

Note 1: (C + F) = Coarse + Fine

HYDROMETER DETAILS

Volume of Bulb (V _b), (cm ³)	63.0
Length of Bulb (L ₂), (cm)	14.47
Length from '0' Reading to Top of Bulb (L ₁), (cm)	10.29
Scale Dimension (h _s), (cm/Div)	0.155
Cross-Sectional Area of Cylinder (A), (cm ²)	27.25
Meniscus Correction (H _m), (g/L)	1.0

START TIME 9:33 AM

HYDROMETER ANALYSIS

Date	Time	Elapsed Time T Mins	H _s Divisions g/L	H _e Divisions g/L	Temperature T _e °C	Corrected Reading R = H _s - H _e g/L	Percent Passing P %	L cm	η Poise	K	Diameter D mm
15-Feb-21	9:34 AM	1	36.0	7.0	21.0	29.0	37.99	10.63404	9.84835	0.013126	0.04280
15-Feb-21	9:35 AM	2	32.0	7.0	21.0	25.0	32.75	11.25404	9.84835	0.013126	0.03114
15-Feb-21	9:38 AM	5	28.0	7.0	21.0	21.0	27.51	11.87404	9.84835	0.013126	0.02023
15-Feb-21	9:48 AM	15	22.0	7.0	21.0	15.0	19.65	12.80404	9.84835	0.013126	0.01213
15-Feb-21	10:03 AM	30	19.0	7.0	21.0	12.0	15.72	13.26904	9.84835	0.013126	0.00873
15-Feb-21	10:33 AM	60	16.0	7.0	21.0	9.0	11.79	13.73404	9.84835	0.013126	0.00628
15-Feb-21	1:43 PM	250	12.0	7.0	22.0	5.0	6.5492	14.35404	9.61570	0.012970	0.00311
16-Feb-21	9:33 AM	1440	10.0	7.0	22.0	3.0	3.9295	14.86404	9.61570	0.012970	0.00131

Remarks:

Reviewed By: Brian Proulx

Date: February 23, 2021

PROJECT DETAILS

Client:	Kollaard Associates Inc. File # 210064	Project No.:	122410003
Project:	3200 Reid Lane, Osgoode	Test Method:	LST702
Material Type:	Soil	Sampled By:	Kollaard Associates Inc.
Source:	BH4	Date Sampled:	February 3, 2021
Sample No.:	SS7	Tested By:	Denis Rodriguez
Sample Depth	4.52-5.18 m	Date Tested:	February 15, 2021

SOIL INFORMATION

Liquid Limit (LL)	
Plasticity Index (PI)	
Soil Classification	
Specific Gravity (G _s)	2.750
Sg. Correction Factor (α)	0.978
Mass of Dispersing Agent/Litre	24 g

HYDROMETER DETAILS

Volume of Bulb (V _b), (cm ³)	63.0
Length of Bulb (L ₂), (cm)	14.47
Length from '0' Reading to Top of Bulb (L ₁), (cm)	10.29
Scale Dimension (H _s), (cm/Div)	0.155
Cross-Sectional Area of Cylinder (A), (cm ²)	27.25
Meniscus Correction (H _m), (g/L)	1.0

START TIME 9:40 AM

CALCULATION OF DRY SOIL MASS

Oven Dried Mass (W _d), (g)	80.13
Air Dried Mass (W _a), (g)	80.22
Hygroscopic Corr. Factor (F=W _a /W _d)	0.9989
Air Dried Mass in Analysis (M _a), (g)	99.30
Oven Dried Mass in Analysis (M _d), (g)	99.19
Percent Passing 2.0 mm Sieve (P _{2.0}), (%)	99.89
Sample Represented (W _v), (g)	99.30

HYDROMETER ANALYSIS

Date	Time	Elapsed Time T Mins	H _s Divisions g/L	H _c Divisions g/L	Temperature T _c °C	Corrected Reading R = H _s - H _c g/L	Percent Passing P %	L cm	η Poise	K	Diameter D mm
15-Feb-21	9:41 AM	1	12.0	3.5	22.0	8.5	8.37	14.35404	9.61570	0.012970	0.04914
15-Feb-21	9:42 AM	2	11.0	3.5	22.0	7.5	7.39	14.50904	9.61570	0.012970	0.03493
15-Feb-21	9:45 AM	5	11.0	3.5	22.0	7.5	7.39	14.50904	9.61570	0.012970	0.02209
15-Feb-21	9:55 AM	15	10.0	3.5	21.5	6.5	6.40	14.66404	9.73081	0.013047	0.01290
15-Feb-21	10:10 AM	30	9.0	3.5	21.5	5.5	5.42	14.81904	9.73081	0.013047	0.00917
15-Feb-21	10:40 AM	60	9.0	3.5	21.5	5.5	5.42	14.81904	9.73081	0.013047	0.00648
15-Feb-21	1:50 PM	250	8.0	3.5	22	4.5	4.43	14.97404	9.61570	0.012970	0.00317
16-Feb-21	9:40 AM	1440	7.0	3.5	22	3.5	3.45	15.12904	9.61570	0.012970	0.00133

Reviewed By: *Brian Pezard*

Date: *February 23/2021*

Remarks:

WASH TEST DATA

Oven Dry Mass In Hydrometer Analysis (g)	99.19
Sample Weight after Hydrometer and Wash (g)	87.02
Percent Passing No. 200 Sieve (%)	12.3
Percent Passing Corrected (%)	12.25

PERCENT LOSS IN SIEVE

Sample Weight Before Sieve (g)	623.50
Sample Weight After Sieve (g)	623.40
Percent Loss in Sieve (%)	0.02

SIEVE ANALYSIS

Sieve Size mm	Cum. Wt. Retained	Percent Passing
75.0		100.0
63.0		100.0
53.0		100.0
37.5		100.0
26.5		100.0
19.0		100.0
13.2		100.0
9.5		100.0
4.75	0.0	100.0
2.00	0.7	99.9
Total (C + F)¹	623.40	
0.850	0.44	99.44
0.425	1.99	97.88
0.250	28.60	71.09
0.106	80.00	19.32
0.075	85.18	14.11
PAN	86.94	

Note 1: (C + F) = Coarse + Fine



ATTACHMENT D

RESULTS OF LABORATORY NITROGEN TESTING OF RECEIVING AQUIFER SAMPLES



Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1947810
Date Submitted: 2021-02-12
Date Reported: 2021-02-18
Project: 210064
COC #: 211512

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____
Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1947810
 Date Submitted: 2021-02-12
 Date Reported: 2021-02-18
 Project: 210064
 COC #: 211512

Group	Analyte	MRL	Units	Guideline	1542143 GW 2021-02-12 MW2	1542144 GW 2021-02-12 MW4	1542145 GW 2021-02-12 MW6
Nutrients	N-NH3	0.010	mg/L		<0.010	<0.010	0.031
	Total Kjeldahl Nitrogen	0.100	mg/L		0.393	0.331	0.245
Others	N-NO2	0.10	mg/L		0.17	<0.10	<0.10
	N-NO3	0.10	mg/L		5.80	<0.10	<0.10

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1947810
 Date Submitted: 2021-02-12
 Date Reported: 2021-02-18
 Project: 210064
 COC #: 211512

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 396258 Analysis/Extraction Date 2021-02-16 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	96	
N-NO3	<0.10 mg/L	103	
Run No 396301 Analysis/Extraction Date 2021-02-17 Analyst SKH Method EPA 350.1			
N-NH3	<0.010 mg/L	100	80-120
Run No 396312 Analysis/Extraction Date 2021-02-17 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	112	70-130

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

OFFICIAL CERTIFICATE OF ANALYSIS - EXCEEDENCE SUMMARY

Client : Kollaard Associates Inc.
 Project : 210064

Reception Date : 2023-11-20

Eurofins Sample No	Client Sample Identification	Analyte	Result	Units	Exceeded Criteria		
					A	B	C
Nitrate (Water, Colorimetry)							
7379224	BH1	Nitrate (as Nitrogen)	18.8	mg/L	10		

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Kollaard Associates Inc.
Project : 210064

Reception Date: 2023-11-20

			Eurofins Sample No :						
			7379224	7379225	7379226	7379227	7379228		
			Matrix :						
			Ground Water	Ground Water	Ground Water	Ground Water	Ground Water		
			Sampling Date :						
			2023-11-20	2023-11-20	2023-11-20	2023-11-20	2023-11-20		
			Client Sample Identification :						
			BH1	BH3	BH5	BH7	BH8		
Nutrients	RL	Unit	Criteria						
			A	B	C				
Ammonia, Total (Water, Colorimetry)									
Ammonia (Total, as Nitrogen)	0.02	mg/L			<0.020	<0.020	0.047	0.023	1.11
Nitrate (Water, Colorimetry)									
Nitrate (as Nitrogen)	0.1	mg/L	10		18.8	0.28	<0.10	<0.10	<0.10
Nitrite (Water, Colorimetry)									
Nitrite (as Nitrogen)	0.1	mg/L	1		0.19	<0.10	<0.10	<0.10	<0.10
Total Kjeldahl Nitrogen (Water, Colorimetry)									
Total Kjeldahl Nitrogen	0.1	mg/L			0.674	0.374	0.494	0.703	1.46

			Eurofins Sample No :					
			7379229	7379230	7379231			
			Matrix :					
			Ground Water	Ground Water	Ground Water			
			Sampling Date :					
			2023-11-20	2023-11-20	2023-11-20			
			Client Sample Identification :					
			BH9	BH10	BH11			
Nutrients	RL	Unit	Criteria					
			A	B	C			
Ammonia, Total (Water, Colorimetry)								
Ammonia (Total, as Nitrogen)	0.02	mg/L			0.065	0.032	0.208	
Nitrate (Water, Colorimetry)								
Nitrate (as Nitrogen)	0.1	mg/L	10		<0.10	<0.10	<0.10	
Nitrite (Water, Colorimetry)								
Nitrite (as Nitrogen)	0.1	mg/L	1		<0.10	<0.10	<0.10	
Total Kjeldahl Nitrogen (Water, Colorimetry)								
Total Kjeldahl Nitrogen	0.1	mg/L			0.503	0.415	0.569	

Approved by : R. Zafari
Raheleh Zafari,
Ottawa, Environmental Chemist, PhD

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Kollaard Associates Inc.
Project : 210064

Reception Date: 2023-11-20

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
Ammonia, Total (Water, Colorimetry)									
<i>Method : Ammonia (Water, Colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Ammonia (Total, as Nitrogen)	mg/L	0.02	<0.020	101	80-120	115	80-120	-	0-20
Associated Samples : 7379224, 7379225, 7379226, 7379227, 7379228, 7379229, 7379230, 7379231								Prep Date: 2023-11-24 Analysis Date: 2023-11-24	
Nitrate (Water, Colorimetry)									
<i>Method : Nitrates/Nitrates (Water, Colorimetry). Internal method: OTT-I-NUT-WI46199.</i>									
Nitrate (as Nitrogen)	mg/L	0.1	<0.10	106	80-120				
Associated Samples : 7379224, 7379225, 7379226, 7379227, 7379228, 7379229, 7379230, 7379231								Prep Date: 2023-11-22 Analysis Date: 2023-11-22	
Nitrite (Water, Colorimetry)									
<i>Method : Nitrates/Nitrates (Water, Colorimetry). Internal method: OTT-I-NUT-WI46199.</i>									
Nitrite (as Nitrogen)	mg/L	0.1	<0.10	93	80-120				
Associated Samples : 7379224, 7379225, 7379226, 7379227, 7379228, 7379229, 7379230, 7379231								Prep Date: 2023-11-22 Analysis Date: 2023-11-22	
Total Kjeldahl Nitrogen (Water, Colorimetry)									
<i>Method : TKN (Water, colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Total Kjeldahl Nitrogen	mg/L	0.1	<0.100	104	70-130	102	70-130	11	0-20
Associated Samples : 7379224, 7379225, 7379226, 7379227, 7379228, 7379229, 7379230, 7379231								Prep Date: 2023-11-24 Analysis Date: 2023-11-27	

Where RPD % is reported as "-" the calculation is not available because one or both of the duplicates is within 5 times the RL.

OFFICIAL CERTIFICATE OF ANALYSIS - EXCEEDENCE SUMMARY

Client : Kollaard Associates Inc.
 Project : 210064

Reception Date : 2024-02-28

Eurofins Sample No	Client Sample Identification	Analyte	Result	Units	Exceeded Criteria		
					A	B	C
Nitrate (Water, Colorimetry)							
7543456	BH1	Nitrate (as Nitrogen)	15.6	mg/L	10		

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Kollaard Associates Inc.
Project : 210064

Reception Date: 2024-02-28

				Eurofins Sample No :						
				7543456	7543457	7543458	7543459	7543460		
				Matrix :						
				Ground Water	Ground Water	Ground Water	Ground Water	Ground Water		
				Sampling Date :						
				2024-02-27	2024-02-28	2024-02-27	2024-02-28	2024-02-28		
				Client Sample Identification :						
				BH1	BH5	BH7	BH8	BH9		
Nutrients	RL	Unit	Criteria							
			A	B	C					
Ammonia, Total (Water, Colorimetry)										
Ammonia (Total, as Nitrogen)	0.02	mg/L				<0.020	<0.020	<0.020	0.037	0.087
Nitrate (Water, Colorimetry)										
Nitrate (as Nitrogen)	0.1	mg/L	10			15.6	0.34	<0.10	<0.10	0.22
Nitrite (Water, Colorimetry)										
Nitrite (as Nitrogen)	0.1	mg/L	1			0.12	<0.10	<0.10	<0.10	<0.10
Total Kjeldahl Nitrogen (Water, Colorimetry)										
Total Kjeldahl Nitrogen	0.1	mg/L				0.500	0.310	0.676	0.229	0.524

				Eurofins Sample No :						
				7543461	7543462					
				Matrix :						
				Ground Water	Ground Water					
				Sampling Date :						
				2024-02-28	2024-02-28					
				Client Sample Identification :						
				BH10	BH11					
Nutrients	RL	Unit	Criteria							
			A	B	C					
Ammonia, Total (Water, Colorimetry)										
Ammonia (Total, as Nitrogen)	0.02	mg/L				0.224	0.155			
Nitrate (Water, Colorimetry)										
Nitrate (as Nitrogen)	0.1	mg/L	10			<0.10	<0.10			
Nitrite (Water, Colorimetry)										
Nitrite (as Nitrogen)	0.1	mg/L	1			<0.10	<0.10			
Total Kjeldahl Nitrogen (Water, Colorimetry)										
Total Kjeldahl Nitrogen	0.1	mg/L				0.806	0.442			

Approved by : 
Emma-Dawn Ferguson,
Environmental Chemist

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Kollaard Associates Inc.
Project : 210064

Reception Date: 2024-02-28

Parameter	Unit	RL	Blank	QC		Matrix Spike		Duplicate	
				Recovery %	Range %	Recovery %	Range %	RPD %	Range %
Ammonia, Total (Water, Colorimetry)									
<i>Method : Ammonia (Water, Colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Ammonia (Total, as Nitrogen)	mg/L	0.02	<0.020	103	80-120	99	80-120	1	0-20
Associated Samples : 7543456, 7543457, 7543458, 7543459, 7543460, 7543461, 7543462								Prep Date: 2024-02-29 Analysis Date: 2024-02-29	
Nitrate (Water, Colorimetry)									
<i>Method : Nitrates/Nitrates (Water, Colorimetry). Internal method: OTT-I-NUT-WI46199.</i>									
Nitrate (as Nitrogen)	mg/L	0.1	<0.10	100	80-120			1	0-20
Associated Samples : 7543456, 7543457, 7543458, 7543459, 7543460, 7543461, 7543462								Prep Date: 2024-03-01 Analysis Date: 2024-03-01	
Nitrite (Water, Colorimetry)									
<i>Method : Nitrates/Nitrates (Water, Colorimetry). Internal method: OTT-I-NUT-WI46199.</i>									
Nitrite (as Nitrogen)	mg/L	0.1	<0.10	101	80-120	104	80-120	-	0-20
Associated Samples : 7543456, 7543457, 7543458, 7543459, 7543460, 7543461, 7543462								Prep Date: 2024-03-01 Analysis Date: 2024-03-01	
Total Kjeldahl Nitrogen (Water, Colorimetry)									
<i>Method : TKN (Water, colorimetry). Internal method: OTT-I-NUT-WI46201.</i>									
Total Kjeldahl Nitrogen	mg/L	0.1	<0.100	124	70-130	109	70-130	-	0-20
Associated Samples : 7543456, 7543457, 7543458, 7543459, 7543460, 7543461, 7543462								Prep Date: 2024-02-29 Analysis Date: 2024-03-01	

Where RPD % is reported as "-" the calculation is not available because one or both of the duplicates is within 5 times the RL.

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1993661
Date Submitted: 2023-02-10
Date Reported: 2023-02-14
Project: 210064
COC #: 905438

Page 1 of 3

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Raheleh Zafari, Environmental Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <https://directory.cala.ca/>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1993661
 Date Submitted: 2023-02-10
 Date Reported: 2023-02-14
 Project: 210064
 COC #: 905438

Group	Analyte	MRL	Units	Guideline	Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.
Nutrients	N-NH3	0.020	mg/L		1674214 Water
	Total Kjeldahl Nitrogen	0.100	mg/L		2023-02-09 BH1
Others	N-NO2	0.10	mg/L		<0.020
	N-NO3	0.10	mg/L		0.572

Guideline =

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1993661
 Date Submitted: 2023-02-10
 Date Reported: 2023-02-14
 Project: 210064
 COC #: 905438

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 437473 Analysis/Extraction Date 2023-02-13 Analyst SKH Method EPA 350.1			
N-NH3	<0.020 mg/L	92	80-120
Run No 437476 Analysis/Extraction Date 2023-02-13 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	101	80-120
Run No 437487 Analysis/Extraction Date 2023-02-13 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	116	70-130

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1947810
Date Submitted: 2021-02-12
Date Reported: 2021-02-18
Project: 210064
COC #: 211512

Page 1 of 3

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:



Addrine Thomas
2021.02.18
14:41:20 -05'00'

APPROVAL:

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1947810
 Date Submitted: 2021-02-12
 Date Reported: 2021-02-18
 Project: 210064
 COC #: 211512

Group	Analyte	MRL	Units	Guideline	1542143 GW 2021-02-12 MW2 MW1	1542144 GW 2021-02-12 MW4 MW3	1542145 GW 2021-02-12 MW6 MW5
Nutrients	N-NH3	0.010	mg/L		<0.010	<0.010	0.031
	Total Kjeldahl Nitrogen	0.100	mg/L		0.393	0.331	0.245
Others	N-NO2	0.10	mg/L		0.17	<0.10	<0.10
	N-NO3	0.10	mg/L		5.80	<0.10	<0.10

Guideline =

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1947810
 Date Submitted: 2021-02-12
 Date Reported: 2021-02-18
 Project: 210064
 COC #: 211512

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 396258 Analysis/Extraction Date 2021-02-16 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	96	
N-NO3	<0.10 mg/L	103	
Run No 396301 Analysis/Extraction Date 2021-02-17 Analyst SKH Method EPA 350.1			
N-NH3	<0.010 mg/L	100	80-120
Run No 396312 Analysis/Extraction Date 2021-02-17 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	112	70-130

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1979883
Date Submitted: 2022-06-22
Date Reported: 2022-06-28
Project: 210064
COC #: 892186

Page 1 of 3

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Emma-Dawn Ferguson, Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <https://directory.cala.ca/>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1979883
 Date Submitted: 2022-06-22
 Date Reported: 2022-06-28
 Project: 210064
 COC #: 892186

Group	Analyte	MRL	Units	Guideline	Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.
Nutrients	N-NH3	0.010	mg/L		1632864 Water
	Total Kjeldahl Nitrogen	0.100	mg/L		2022-06-17 MW1
Others	N-NO2	0.10	mg/L		0.020
	N-NO3	0.10	mg/L		0.292
					<0.10
					8.11

Guideline =

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1979883
 Date Submitted: 2022-06-22
 Date Reported: 2022-06-28
 Project: 210064
 COC #: 892186

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 424404 Analysis/Extraction Date 2022-06-23 Analyst ML Method EPA 350.1			
N-NH3	<0.010 mg/L	99	80-120
Run No 424476 Analysis/Extraction Date 2022-06-24 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	102	80-120
N-NO3	<0.10 mg/L	103	80-120
Run No 424502 Analysis/Extraction Date 2022-06-24 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	105	70-130

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1973212
Date Submitted: 2022-03-11
Date Reported: 2022-03-18
Project: 210064
COC #: 887286

Page 1 of 4

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1973212
 Date Submitted: 2022-03-11
 Date Reported: 2022-03-18
 Project: 210064
 COC #: 887286

Group	Analyte	MRL	Units	Guideline	Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.
Nutrients	N-NH3	0.010	mg/L		1614181 Water
	Total Kjeldahl Nitrogen	0.100	mg/L		2022-03-10 BH3
Others	N-NO2	0.10	mg/L		0.028
	N-NO3	0.10	mg/L		0.397
					<0.10
					<0.10

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1973212
 Date Submitted: 2022-03-11
 Date Reported: 2022-03-18
 Project: 210064
 COC #: 887286

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 418445 Analysis/Extraction Date 2022-03-14 Analyst SKH Method EPA 350.1			
N-NH3	<0.010 mg/L	101	80-120
Run No 418494 Analysis/Extraction Date 2022-03-14 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	99	70-130
Run No 418535 Analysis/Extraction Date 2022-03-15 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	98	80-120
N-NO3	<0.10 mg/L	98	80-120

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1973212
Date Submitted: 2022-03-11
Date Reported: 2022-03-18
Project: 210064
COC #: 887286

Sample Comment Summary

Sample ID: 1614181 BH3 Sediment not included in TKN analysis.

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1972761
Date Submitted: 2022-03-04
Date Reported: 2022-03-09
Project: 210064
COC #: 886841

Page 1 of 4

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1972761
 Date Submitted: 2022-03-04
 Date Reported: 2022-03-09
 Project: 210064
 COC #: 886841

Group	Analyte	MRL	Units	Guideline	Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.	1613058 Water 2022-03-03 BH1	1613059 Water 2022-03-04 BH5
Nutrients	N-NH3	0.010	mg/L			<0.010	<0.010
	Total Kjeldahl Nitrogen	0.100	mg/L			0.737	0.309
Others	N-NO2	0.10	mg/L			0.16	<0.10
	N-NO3	0.10	mg/L			19.7	0.72

Guideline =

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1972761
 Date Submitted: 2022-03-04
 Date Reported: 2022-03-09
 Project: 210064
 COC #: 886841

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 418148 Analysis/Extraction Date 2022-03-07 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	101	70-130
Run No 418208 Analysis/Extraction Date 2022-03-08 Analyst SKH Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	88	80-120
N-NO3	<0.10 mg/L	99	80-120
Run No 418237 Analysis/Extraction Date 2022-03-09 Analyst SKH Method EPA 350.1			
N-NH3	0.013 mg/L	118	80-120

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1972761
Date Submitted: 2022-03-04
Date Reported: 2022-03-09
Project: 210064
COC #: 886841

Sample Comment Summary

Sample ID: 1613058 BH1 Sediment not included in TKN analysis for this report.

Guideline = * = **Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1977214
Date Submitted: 2022-05-12
Date Reported: 2022-05-19
Project: 210064
COC #: 890555

Page 1 of 4

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Emma-Dawn Ferguson, Chemist

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1977214
 Date Submitted: 2022-05-12
 Date Reported: 2022-05-19
 Project: 210064
 COC #: 890555

Group	Analyte	MRL	Units	Guideline	1625779 Water 2022-05-06 5503 Osgoode Main	1625780 Water 2022-05-06 3216 Reids Lane	1625781 Water 2022-05-06 5535 Osgoode Main	1625782 Water 2022-05-06 5519 Osgoode Main
Anions	N-NO2	0.10	mg/L	MAC 1.0	<0.10	0.72	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10	30.8*	12.3*	22.3*
Nutrients	N-NH3	0.010	mg/L		0.249	0.182	0.060	0.095
	Total Kjeldahl Nitrogen	0.100	mg/L		0.145	0.740	0.298	0.533

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1977214
 Date Submitted: 2022-05-12
 Date Reported: 2022-05-19
 Project: 210064
 COC #: 890555

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 421994 Analysis/Extraction Date 2022-05-17 Analyst AaN			
Method SM 4110			
N-NO2	<0.10 mg/L	97	90-110
N-NO3	<0.10 mg/L	102	90-110
Run No 422119 Analysis/Extraction Date 2022-05-18 Analyst SKH			
Method SM 4110			
N-NO3	<1.0 mg/L	111	90-110
Run No 422273 Analysis/Extraction Date 2022-05-18 Analyst SKH			
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	114	70-130
Run No 422331 Analysis/Extraction Date 2022-05-19 Analyst SKH			
Method EPA 350.1			
N-NH3	<0.010 mg/L	89	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1977214
Date Submitted: 2022-05-12
Date Reported: 2022-05-19
Project: 210064
COC #: 890555

Sample Comment Summary

Sample ID: 1625779	5503 Osgoode Main	For workorder: Holding time for N-NO2 & N-NO3 analysis was exceeded.
Sample ID: 1625780	3216 Reids Lane	NO3 MRL elevated due to matrix interference (dilution was done).
Sample ID: 1625781	5535 Osgoode Main	NO3 MRL elevated due to matrix interference (dilution was done).
Sample ID: 1625782	5519 Osgoode Main	NO3 MRL elevated due to matrix interference (dilution was done).

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



ATTACHMENT E

SEPTIC EFFLUENT DILUTION CALCULATIONS

SEPTIC EFFLUENT DILUTION CALCULATIONS

Number of Lots	7
Gross Site Area	35035 m ²
Env. Can. Water Surplus (NPI)	379 mm

Hard Surface Area (Post-Development)

Roadway	1965	Lot Based
Dwellings (320 m ² /house)	2240	
Other impervious surfaces (pools, etc.)	700	
Driveways	<u>996</u>	
Total	5901 m ²	

Net Infiltration Area = Gross Site Area - Hard Surface Area (Post-Development)
 29134 m²

Infiltration Reduction Factor:

Topography (rolling)	0.20
Soil (open sandy loam)	0.40
<u>Cover (cultivated/orchard)</u>	<u>0.10</u>
Total IRF	0.70

Septic Dilution For 7 Septic Systems:

$$\frac{\text{Number of Lots} \times 365 \text{ m}^3 \text{ Effluent Per Year} \times 40 \text{ mg/L NO}_3}{\text{Number of Lots} \times 365 \text{ m}^3 \text{ Effluent Per Year} + (\text{Net Infiltration Area} \times \text{NPI} \times \text{IRF})} = 9.9 \text{ mg/L NO}_3\text{-N}$$

Ottawa Intl A WATER BUDGET MEANS FOR THE PERIOD 1939-2021 DC20492

LAT.... 45.32 WATER HOLDING CAPACITY... 75 MM HEAT INDEX... 36.75
 LONG... 75.67 LOWER ZONE..... 45 MM A..... 1.080

DATE	TEMP (C)	PCPN	RAIN	MELT	PE	AE	DEF	SURP	SNOW	SOIL	ACC P
31- 1	-10.6	62	12	14	0	0	0	25	83	74	294
28- 2	-9.0	56	10	16	1	1	0	26	111	74	350
31- 3	-2.8	65	31	77	6	6	0	103	68	75	416
30- 4	5.7	73	68	73	31	31	0	110	0	75	489
31- 5	13.1	75	75	0	80	80	0	14	0	56	565
30- 6	18.3	85	85	0	116	107	-9	5	0	29	650
31- 7	20.9	88	88	0	136	103	-33	3	0	11	737
31- 8	19.7	84	84	0	118	83	-35	1	0	11	822
30- 9	14.8	82	82	0	75	65	-10	4	0	24	904
31-10	8.3	78	78	0	37	36	-1	14	0	52	78
30-11	1.2	76	59	8	10	10	0	38	9	71	154
31-12	-6.9	79	27	14	1	1	0	36	47	74	233
AVE	6.0 TTL	903	699	202	611	523	-88	379			

Ottawa Intl A STANDARD DEVIATIONS FOR THE PERIOD 1939-2021 DC20492

DATE	TEMP (C)	PCPN	RAIN	MELT	PE	AE	DEF	SURP	SNOW	SOIL	ACC P
31- 1	2.9	26	15	17	1	1	0	28	44	3	59
28- 2	2.6	26	14	25	1	1	0	34	59	3	63
31- 3	2.6	28	22	49	5	5	0	55	87	0	71
30- 4	1.8	32	33	88	9	9	0	89	2	2	80
31- 5	1.8	34	34	2	12	12	0	24	0	22	94
30- 6	1.2	38	38	0	8	17	18	16	0	29	105
31- 7	1.2	45	45	0	8	31	33	16	0	22	117
31- 8	1.3	37	37	0	9	29	31	4	0	21	126
30- 9	1.5	39	39	0	8	16	16	15	0	28	132
31-10	1.5	37	37	1	7	7	2	21	0	27	37
30-11	1.8	27	27	8	4	4	0	32	13	12	45
31-12	3.0	30	22	13	1	1	0	30	34	4	55



ATTACHMENT F

RESULTS OF LABORATORY TESTING OF TEST WELL WATER SAMPLES

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.


Report Number: 1953233
Date Submitted: 2021-05-13
Date Reported: 2021-05-20
Project: 210064
COC #: 873626

Page 1 of 7

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:


Addrine
Thomas
2021.05.20
16:03:15 -04'00'

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

Group	Analyte	MRL	Units	Guideline	1556912 Water 2021-05-12 TW#1-3 hr	1556913 Water 2021-05-12 TW#1-6 hr
Anions	Cl	1	mg/L	AO 250	178	180
	F	0.10	mg/L	MAC 1.5	0.83	0.85
	N-NO2	0.10	mg/L	MAC 1.0	<0.50	<0.50
	N-NO3	0.10	mg/L	MAC 10.0	<0.50	<0.50
	SO4	1	mg/L	AO 500	44	44
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	143	142
	Colour	2	TCU		<2	<2
	Conductivity	5	uS/cm		951	945
	DOC	0.5	mg/L	AO 5	1.8	2.0
	pH	1.00		6.5-8.5	8.19	8.20
	S2-	0.01	mg/L	AO 0.05	1.10*	1.10*
	TDS (COND - CALC)	1	mg/L	AO 500	618*	614*
	Turbidity	0.1	NTU	AO 5.0	2.2	1.1
Hardness	Hardness as CaCO3	1	mg/L	OG 100	229*	229*
Indices/Calc	Ion Balance	0.01			1.03	1.03
Metals	Al	0.01	mg/L	OG 0.1	<0.01	<0.01
	As	0.001	mg/L	IMAC 0.01	<0.001	<0.001
	B	0.01	mg/L	IMAC 5.0	0.53	0.54
	Ba	0.01	mg/L	MAC 1.0	0.08	0.07
	Ca	1	mg/L		44	44
	Cd	0.0001	mg/L	MAC 0.005	<0.0001	<0.0001
	Co	0.0002	mg/L		<0.0002	<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001	<0.001
	Fe	0.03	mg/L	AO 0.3	0.16	0.11

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

Group	Analyte	MRL	Units	Guideline	1556912 Water 2021-05-12 TW#1-3 hr	1556913 Water 2021-05-12 TW#1-6 hr
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001	<0.0001
	K	1	mg/L		11	11
	Mg	1	mg/L		29	29
	Mn	0.01	mg/L	AO 0.05	0.01	0.01
	Na	2	mg/L	AO 200	98	98
	Pb	0.001	mg/L	MAC 0.010	<0.001	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Sr	0.001	mg/L		3.92	3.87
	U	0.001	mg/L	MAC 0.02	<0.001	<0.001
	V	0.001	mg/L		<0.001	<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01	<0.01
Nutrients	N-NH3	0.010	mg/L		0.307	0.303
	Total Kjeldahl Nitrogen	0.100	mg/L		0.391	0.504
Subcontract	Phenols	0.001	mg/L		<0.0010	<0.0010
	Tannin & Lignin	0.1	mg/L		0.1	0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400541 Analysis/Extraction Date 2021-05-13 Analyst K B Method C SM2130B			
Turbidity	0.6 NTU	101	70-130
Run No 400603 Analysis/Extraction Date 2021-05-14 Analyst SKH Method C SM2120C			
Colour	<2 TCU	102	90-110
Run No 400654 Analysis/Extraction Date 2021-05-14 Analyst SKH Method EPA 200.8			
Aluminum	<0.01 mg/L	106	80-120
Arsenic	<0.001 mg/L	100	80-120
Boron (total)	<0.01 mg/L	106	80-120
Barium	<0.01 mg/L	95	80-120
Cadmium	<0.0001 mg/L	100	80-120
Cobalt	<0.0002 mg/L	104	80-120
Chromium Total	<0.001 mg/L	105	80-120
Copper	<0.001 mg/L	105	80-120
Iron	<0.03 mg/L	99	80-120
Mercury	<0.0001 mg/L	90	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Manganese	<0.01 mg/L	100	80-120
Lead	<0.001 mg/L	106	80-120
Antimony	<0.0005 mg/L	96	80-120
Selenium	<0.001 mg/L	94	80-120
Strontium	<0.001 mg/L	94	80-120
Uranium	<0.001 mg/L	107	80-120
Vanadium	<0.001 mg/L	104	80-120
Zinc	<0.01 mg/L	104	80-120
Run No 400665 Analysis/Extraction Date 2021-05-15 Analyst SWS			
Method SM2320,2510,4500H/F			
F	<0.10 mg/L	100	90-110
pH		100	90-110
Run No 400666 Analysis/Extraction Date 2021-05-14 Analyst SWS			
Method SM 5310B			
DOC	<0.5 mg/L	89	80-120
Run No 400717 Analysis/Extraction Date 2021-05-17 Analyst SKH			
Method EPA 350.1			
N-NH3	<0.010 mg/L	99	80-120

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400719 Analysis/Extraction Date 2021-05-17 Analyst SKH			
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	102	70-130
Run No 400737 Analysis/Extraction Date 2021-05-18 Analyst Z S			
Method M SM3120B-3500C			
Calcium	<1 mg/L	100	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	98	76-124
Sodium	<2 mg/L	105	82-118
Run No 400792 Analysis/Extraction Date 2021-05-17 Analyst SWS			
Method SM2320,2510,4500H/F			
Alkalinity (CaCO3)	<5 mg/L	97	90-110
Conductivity	<5 uS/cm	97	90-110
Run No 400797 Analysis/Extraction Date 2021-05-19 Analyst AET			
Method SM 4110			
Chloride	<5 mg/L		90-110
N-NO2	<0.50 mg/L	98	90-110
N-NO3	<0.50 mg/L	105	90-110
SO4	<5 mg/L	100	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953233
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-20
 Project: 210064
 COC #: 873626

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400811 Analysis/Extraction Date 2021-05-19 Analyst AET Method C SM2340B			
Hardness as CaCO3			
Ion Balance			
TDS (COND - CALC)			
Run No 400865 Analysis/Extraction Date 2021-05-14 Analyst AET Method SUBCONTRACT-A			
Phenols	<0.0010 mg/L	98	
Tannin & Lignin	<0.10 mg/L	103	
Run No 400982 Analysis/Extraction Date 2021-05-20 Analyst AET Method C SM4500-S2-D			
S2-	<0.01 mg/L	104	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1953218
Date Submitted: 2021-05-13
Date Reported: 2021-05-16
Project: 210064
COC #: 873626

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana
Dzeletovic
2021.05.16
08:33:26 -04'00'

APPROVAL: _____
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1953218
 Date Submitted: 2021-05-13
 Date Reported: 2021-05-16
 Project: 210064
 COC #: 873626

Group	Analyte	MRL	Units	Guideline	Lab I.D.	Sample Matrix	Sample Type	Sampling Date	Sample I.D.		
					1556873	Water		2021-05-12	TW#1-3 hr	1556874	Water
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0						0	0
	Faecal Coliforms	0	ct/100mL							0	0
	Heterotrophic Plate Count	0	ct/1mL							0	0
	Total Coliforms	0	ct/100mL	MAC 0						0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.


Report Number: 1952974
Date Submitted: 2021-05-11
Date Reported: 2021-05-19
Project: 210064
COC #: 873496

Page 1 of 7

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL:  Addrine
Thomas
2021.05.19
16:06:04
~~04:00~~
Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

Group	Analyte	MRL	Units	Guideline	1556262 Water 2021-05-10 TW2-3 hrs	1556263 Water 2021-05-10 TW2-6 hrs
Anions	Cl	1	mg/L	AO 250	155	165
	F	0.10	mg/L	MAC 1.5	0.94	0.89
	N-NO2	0.10	mg/L	MAC 1.0	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10	<0.10
	SO4	1	mg/L	AO 500	47	41
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	139	140
	Colour	2	TCU		<2	<2
	Conductivity	5	uS/cm		829	879
	DOC	0.5	mg/L	AO 5	1.8	2.1
	pH	1.00		6.5-8.5	8.05	8.01
	S2-	0.01	mg/L	AO 0.05	0.27*	0.24*
	TDS (COND - CALC)	1	mg/L	AO 500	539*	571*
	Turbidity	0.1	NTU	AO 5.0	5.7*	1.2
Hardness	Hardness as CaCO3	1	mg/L	OG 100	211*	233*
Indices/Calc	Ion Balance	0.01			0.97	1.01
Metals	Al	0.01	mg/L	OG 0.1	<0.01	<0.01
	As	0.001	mg/L	IMAC 0.01	<0.001	<0.001
	B	0.01	mg/L	IMAC 5.0	0.57	0.58
	Ba	0.01	mg/L	MAC 1.0	0.26	0.20
	Ca	1	mg/L		40	44
	Cd	0.0001	mg/L	MAC 0.005	<0.0001	<0.0001
	Co	0.0002	mg/L		<0.0002	<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001	<0.001
	Fe	0.03	mg/L	AO 0.3	0.46*	0.14

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

Group	Analyte	MRL	Units	Guideline	1556262 Water 2021-05-10 TW2-3 hrs	1556263 Water 2021-05-10 TW2-6 hrs
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001	<0.0001
	K	1	mg/L		11	11
	Mg	1	mg/L		27	30
	Mn	0.01	mg/L	AO 0.05	0.02	0.01
	Na	2	mg/L	AO 200	78	80
	Pb	0.001	mg/L	MAC 0.010	<0.001	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Sr	0.001	mg/L		3.28	3.64
	U	0.001	mg/L	MAC 0.02	<0.001	<0.001
	V	0.001	mg/L		<0.001	<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01	<0.01
Nutrients	N-NH3	0.010	mg/L		0.290	0.307
	Total Kjeldahl Nitrogen	0.100	mg/L		0.272	0.323
Subcontract	Phenols	0.001	mg/L		<0.0010	<0.0010
	Tannin & Lignin	0.1	mg/L		0.1	0.2

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400409 Analysis/Extraction Date 2021-05-12 Analyst K B Method C SM2130B			
Turbidity	<0.1 NTU	101	70-130
Run No 400492 Analysis/Extraction Date 2021-05-13 Analyst K B Method C SM2120C			
Colour	<2 TCU	87	90-110
Run No 400510 Analysis/Extraction Date 2021-05-13 Analyst SKH Method EPA 200.8			
Aluminum	<0.01 mg/L	100	80-120
Arsenic	<0.001 mg/L	102	80-120
Boron (total)	<0.01 mg/L	108	80-120
Barium	<0.01 mg/L	89	80-120
Cadmium	<0.0001 mg/L	97	80-120
Cobalt	<0.0002 mg/L	114	80-120
Chromium Total	<0.001 mg/L	109	80-120
Copper	<0.001 mg/L	116	80-120
Iron	<0.03 mg/L	103	80-120
Mercury	<0.0001 mg/L	96	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Manganese	<0.01 mg/L	99	80-120
Lead	<0.001 mg/L	111	80-120
Antimony	<0.0005 mg/L	90	80-120
Selenium	<0.001 mg/L	87	80-120
Strontium	<0.001 mg/L	86	80-120
Uranium	<0.001 mg/L	110	80-120
Vanadium	<0.001 mg/L	108	80-120
Zinc	<0.01 mg/L	108	80-120
Run No 400520 Analysis/Extraction Date 2021-05-12 Analyst SWS Method SM 5310B			
DOC	<0.5 mg/L	92	80-120
Run No 400525 Analysis/Extraction Date 2021-05-14 Analyst AET Method SM 4110			
N-NO2	<0.10 mg/L	101	90-110
N-NO3	<0.10 mg/L	105	90-110
SO4	<1 mg/L	100	90-110
Run No 400564 Analysis/Extraction Date 2021-05-13 Analyst SKH Method EPA 350.1			
N-NH3	<0.010 mg/L	106	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400568 Analysis/Extraction Date 2021-05-13 Analyst SKH			
Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	95	70-130
Run No 400570 Analysis/Extraction Date 2021-05-13 Analyst SWS			
Method SM2320,2510,4500H/F			
Alkalinity (CaCO3)	<5 mg/L	98	90-110
Conductivity	<5 uS/cm	100	90-110
F	<0.10 mg/L	101	90-110
pH		100	90-110
Run No 400624 Analysis/Extraction Date 2021-05-14 Analyst Z S			
Method M SM3120B-3500C			
Calcium	<1 mg/L	99	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	98	76-124
Sodium	<2 mg/L	102	82-118
Run No 400722 Analysis/Extraction Date 2021-05-18 Analyst AET			
Method SM 4110			
Chloride	<5 mg/L		90-110

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952974
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-19
 Project: 210064
 COC #: 873496

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400734 Analysis/Extraction Date 2021-05-18 Analyst AET Method C SM2340B			
Hardness as CaCO3			
Ion Balance			
TDS (COND - CALC)			
Run No 400761 Analysis/Extraction Date 2021-05-18 Analyst AET Method C SM4500-S2-D			
S2-	<0.01 mg/L	92	80-120
Run No 400865 Analysis/Extraction Date 2021-05-18 Analyst AET Method SUBCONTRACT-A			
Phenols	<0.0010 mg/L	103	
Tannin & Lignin	<0.10 mg/L	100	

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1952957
Date Submitted: 2021-05-11
Date Reported: 2021-05-13
Project: 210064
COC #: 873496

Page 1 of 2

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Steven
Tosh
2021.05.13
11:33:30
-04'00'



APPROVAL:

Steven Tosh, Operations Manager

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952957
 Date Submitted: 2021-05-11
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873496

Group	Analyte	MRL	Units	Guideline	Lab I.D.	Sample Matrix	Sample Type	Sampling Date	Sample I.D.
					1556225	1556226	Water	Water	2021-05-10
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0					
	Faecal Coliforms	0	ct/100mL						
	Heterotrophic Plate Count	0	ct/1mL						
	Total Coliforms	0	ct/100mL	MAC 0					

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1952723
Date Submitted: 2021-05-06
Date Reported: 2021-05-13
Project: 210064
COC #: 873355

Page 1 of 8

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:



Addrine Thomas
2021.05.13
15:56:08 -04'00'

APPROVAL:

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

Group	Analyte	MRL	Units	Guideline	1555611 Water 2021-05-05 TW#3-3 hr	1555612 Water 2021-05-05 TW#3-6 hr
Anions	Cl	1	mg/L	AO 250	167	173
	F	0.10	mg/L	MAC 1.5	0.17	0.16
	N-NO2	0.10	mg/L	MAC 1.0	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10	<0.10
	SO4	1	mg/L	AO 500	49	50
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	154	157
	Colour	2	TCU		<2	2
	Conductivity	5	uS/cm		879	916
	DOC	0.5	mg/L	AO 5	1.9	1.9
	pH	1.00		6.5-8.5	8.01	8.08
	S2-	0.01	mg/L	AO 0.05	<0.01	<0.01
	TDS (COND - CALC)	1	mg/L	AO 500	571*	595*
	Turbidity	0.1	NTU	AO 5.0	3.2	1.5
Hardness	Hardness as CaCO3	1	mg/L	OG 100	298*	310*
Indices/Calc	Ion Balance	0.01			1.00	1.02
Metals	Al	0.01	mg/L	OG 0.1	<0.01	<0.01
	As	0.001	mg/L	IMAC 0.01	<0.001	<0.001
	B	0.01	mg/L	IMAC 5.0	0.06	0.06
	Ba	0.01	mg/L	MAC 1.0	0.32	0.33
	Ca	1	mg/L		65	68
	Cd	0.0001	mg/L	MAC 0.005	<0.0001	<0.0001
	Co	0.0002	mg/L		<0.0002	<0.0002
	Cr	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Cu	0.001	mg/L	AO 1.0	<0.001	<0.001
	Fe	0.03	mg/L	AO 0.3	0.54*	0.21

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

Group	Analyte	MRL	Units	Guideline	1555611 Water 2021-05-05 TW#3-3 hr	1555612 Water 2021-05-05 TW#3-6 hr
Metals	Hg	0.0001	mg/L	MAC 0.001	<0.0001	<0.0001
	K	1	mg/L		4	4
	Mg	1	mg/L		33	34
	Mn	0.01	mg/L	AO 0.05	0.01	0.01
	Na	2	mg/L	AO 200	64	67
	Pb	0.001	mg/L	MAC 0.010	<0.001	<0.001
	Sb	0.0005	mg/L	IMAC 0.006	<0.0005	<0.0005
	Se	0.001	mg/L	MAC 0.05	<0.001	<0.001
	Sr	0.001	mg/L		0.662	0.677
	U	0.001	mg/L	MAC 0.02	<0.001	<0.001
	V	0.001	mg/L		<0.001	<0.001
	Zn	0.01	mg/L	AO 5.0	<0.01	<0.01
Nutrients	N-NH3	0.010	mg/L		0.171	0.168
	Total Kjeldahl Nitrogen	0.100	mg/L		0.184	0.337
Subcontract	Phenols	0.001	mg/L		<0.0010	<0.0010
	Tannin & Lignin	0.1	mg/L		0.7	0.6

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400186 Analysis/Extraction Date 2021-05-07 Analyst K B Method C SM2130B			
Turbidity	<0.1 NTU	101	70-130
Run No 400216 Analysis/Extraction Date 2021-05-07 Analyst AET Method C SM4500-S2-D			
S2-	<0.01 mg/L	82	80-120
Run No 400254 Analysis/Extraction Date 2021-05-07 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	101	70-130
Run No 400261 Analysis/Extraction Date 2021-05-07 Analyst SWS Method SM 5310B			
DOC	<0.5 mg/L	89	80-120
Run No 400292 Analysis/Extraction Date 2021-05-10 Analyst Z S Method M SM3120B-3500C			
Calcium	<1 mg/L	105	90-110
Potassium	<1 mg/L	106	87-113
Magnesium	<1 mg/L	103	76-124
Sodium	<2 mg/L	106	82-118

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400294 Analysis/Extraction Date 2021-05-10 Analyst SKH			
Method EPA 200.8			
Aluminum	<0.01 mg/L	100	80-120
Arsenic	<0.001 mg/L	97	80-120
Boron (total)	<0.01 mg/L	103	80-120
Cobalt	<0.0002 mg/L	100	80-120
Chromium Total	<0.001 mg/L	99	80-120
Copper	<0.001 mg/L	100	80-120
Iron	<0.03 mg/L	96	80-120
Manganese	<0.01 mg/L	98	80-120
Selenium	<0.001 mg/L	92	80-120
Vanadium	<0.001 mg/L	100	80-120
Zinc	<0.01 mg/L	99	80-120
Run No 400341 Analysis/Extraction Date 2021-05-10 Analyst SKH			
Method EPA 350.1			
N-NH3	<0.010 mg/L	108	80-120
Run No 400382 Analysis/Extraction Date 2021-05-11 Analyst K B			
Method C SM2120C			
Colour	<2 TCU	82	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 400384 Analysis/Extraction Date 2021-05-11 Analyst SKH Method EPA 200.8			
Barium	<0.01 mg/L	94	80-120
Cadmium	<0.0001 mg/L	99	80-120
Mercury	<0.0001 mg/L	91	80-120
Lead	<0.001 mg/L	105	80-120
Antimony	<0.0005 mg/L	100	80-120
Strontium	<0.001 mg/L	93	80-120
Uranium	<0.001 mg/L	105	80-120
Run No 400405 Analysis/Extraction Date 2021-05-11 Analyst SKH Method EPA 351.2			
Total Kjeldahl Nitrogen	<0.100 mg/L	130	70-130
Run No 400415 Analysis/Extraction Date 2021-05-12 Analyst AET Method SM 4110			
N-NO2	<0.10 mg/L	99	90-110
N-NO3	<0.10 mg/L	101	90-110
SO4	<1 mg/L	95	90-110
Run No 400418 Analysis/Extraction Date 2021-05-11 Analyst SWS Method C SM4500-FC			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

QC Summary

Analyte	Blank	QC % Rec	QC Limits
F	<0.10 mg/L	94	90-110
Run No 400423 Analysis/Extraction Date 2021-05-10 Analyst AET Method SUBCONTRACT-A			
Phenols	<0.0010 mg/L	101	
Tannin & Lignin	<0.10 mg/L	100	
Run No 400441 Analysis/Extraction Date 2021-05-11 Analyst SWS Method C SM2510B			
Conductivity	<5 uS/cm	99	95-105
Run No 400442 Analysis/Extraction Date 2021-05-11 Analyst SWS Method SM2320,2510,4500H/F			
pH	5.85	100	90-110
Run No 400451 Analysis/Extraction Date 2021-05-11 Analyst SWS Method SM 2320B			
Alkalinity (CaCO ₃)	<5 mg/L	100	95-105
Run No 400525 Analysis/Extraction Date 2021-05-13 Analyst AET Method SM 4110			
Chloride	<1 mg/L	100	90-110
Run No 400544 Analysis/Extraction Date 2021-05-13 Analyst AET Method C SM2340B			

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952723
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-13
 Project: 210064
 COC #: 873355

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Hardness as CaCO3			
Ion Balance			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1952724
Date Submitted: 2021-05-06
Date Reported: 2021-05-09
Project: 210064
COC #: 873355

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana Dzeletovic
Dragana
Dzeletovic
2021.05.09
10:54:46 -04'00'

APPROVAL: _____
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#:
 Invoice to: Kollaard Associates Inc.

Report Number: 1952724
 Date Submitted: 2021-05-06
 Date Reported: 2021-05-09
 Project: 210064
 COC #: 873355

Group	Analyte	MRL	Units	Guideline	Lab I.D.	Sample Matrix
					Sample Type	Sampling Date
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	1555613	Water
	Faecal Coliforms	0	ct/100mL		2021-05-05	Water
	Heterotrophic Plate Count	0	ct/1mL		TW#3-3 hr	2021-05-05
	Total Coliforms	0	ct/100mL	MAC 0	TW#3-6 hr	

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



ATTACHMENT G


RESULTS OF LABORATORY TESTING OF EXISTING NEIGHBOURING WELL WATER
SAMPLES



ATTACHMENT H

PUMPING TEST DATA FOR TW1

TW1-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



DRAWDOWN DATA TW1


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	388.094	8.382	-6.86	0.00
1	387.814	8.282	-6.889	0.03
2	383.442	8.282	-7.334	0.47
3	379.072	8.282	-7.78	0.92
4	376.956	8.282	-7.996	1.14
5	376.305	8.282	-8.062	1.20
6	376.115	8.282	-8.082	1.22
7	375.925	8.282	-8.101	1.24
8	375.789	8.282	-8.115	1.26
9	375.754	8.182	-8.118	1.26
10	375.672	8.182	-8.127	1.27
11	375.618	8.182	-8.132	1.27
12	375.564	8.182	-8.138	1.28
13	375.374	8.182	-8.157	1.30
14	375.483	8.182	-8.146	1.29
15	375.564	8.182	-8.138	1.28
16	375.564	8.182	-8.138	1.28
17	375.555	8.082	-8.139	1.28
18	375.528	8.082	-8.141	1.28
19	375.528	8.082	-8.141	1.28
20	375.393	8.082	-8.155	1.30
21	375.447	8.082	-8.15	1.29
22	375.447	8.082	-8.15	1.29
23	375.393	8.082	-8.155	1.30
24	375.366	8.082	-8.158	1.30
25	375.366	8.082	-8.158	1.30
26	375.393	8.082	-8.155	1.30
27	375.393	8.082	-8.155	1.30
28	375.366	8.082	-8.158	1.30
29	375.366	8.082	-8.158	1.30
30	375.366	8.082	-8.158	1.30
31	375.393	8.082	-8.155	1.30
32	375.366	8.082	-8.158	1.30
33	375.284	8.082	-8.166	1.31
34	375.338	8.082	-8.161	1.30
35	375.338	8.082	-8.161	1.30
36	375.338	8.082	-8.161	1.30
37	375.284	8.082	-8.166	1.31
38	375.393	8.082	-8.155	1.30
39	375.338	8.082	-8.161	1.30
40	375.23	8.082	-8.172	1.31
41	375.23	8.082	-8.172	1.31
42	375.284	8.082	-8.166	1.31
43	375.311	8.082	-8.164	1.30
44	375.284	8.082	-8.166	1.31
45	375.311	8.082	-8.164	1.30
46	375.257	8.082	-8.169	1.31
47	375.393	8.082	-8.155	1.30
48	375.284	8.082	-8.166	1.31
49	375.257	8.082	-8.169	1.31
50	375.311	8.082	-8.164	1.30
51	375.284	8.082	-8.166	1.31
52	375.311	8.082	-8.164	1.30
53	375.311	8.082	-8.164	1.30
54	375.338	8.082	-8.161	1.30
55	375.311	8.082	-8.164	1.30
56	375.284	8.082	-8.166	1.31
57	375.284	8.082	-8.166	1.31
58	375.284	8.082	-8.166	1.31
59	375.311	8.082	-8.164	1.30
60	375.284	8.082	-8.166	1.31
61	375.284	8.082	-8.166	1.31
62	375.23	8.082	-8.172	1.31
63	375.23	8.082	-8.172	1.31
64	375.203	8.082	-8.175	1.32
65	375.23	8.082	-8.172	1.31
66	375.203	8.082	-8.175	1.32
67	375.067	8.082	-8.188	1.33
68	375.176	8.082	-8.177	1.32
69	375.203	8.082	-8.175	1.32
70	375.121	8.082	-8.183	1.32
71	375.067	8.082	-8.188	1.33
72	375.04	8.082	-8.191	1.33
73	375.094	8.082	-8.186	1.33
74	375.094	8.082	-8.186	1.33
75	375.04	8.082	-8.191	1.33
76	375.067	8.082	-8.188	1.33
77	375.149	8.082	-8.18	1.32
78	375.121	8.082	-8.183	1.32
79	375.176	8.082	-8.177	1.32
80	375.121	8.082	-8.183	1.32
81	375.067	8.082	-8.188	1.33
82	375.121	8.082	-8.183	1.32
83	375.067	8.082	-8.188	1.33
84	375.067	8.082	-8.188	1.33
85	375.067	8.082	-8.188	1.33
86	375.067	8.082	-8.188	1.33

87	375.067	8.082	-8.188	1.33
88	375.04	8.082	-8.191	1.33
89	375.067	8.082	-8.188	1.33
90	375.094	8.082	-8.186	1.33
91	375.094	8.082	-8.186	1.33
92	375.04	8.082	-8.191	1.33
93	375.013	8.082	-8.194	1.33
94	375.094	8.082	-8.186	1.33
95	374.986	8.082	-8.197	1.34
96	375.013	8.082	-8.194	1.33
97	374.959	8.082	-8.199	1.34
98	374.904	8.082	-8.205	1.35
99	374.823	8.082	-8.213	1.35
100	374.85	8.082	-8.211	1.35
101	374.823	8.082	-8.213	1.35
102	374.85	8.082	-8.211	1.35
103	374.904	8.082	-8.205	1.35
104	374.85	8.082	-8.211	1.35
105	374.796	8.082	-8.216	1.36
106	374.769	8.082	-8.219	1.36
107	374.688	8.082	-8.227	1.37
108	374.742	8.082	-8.222	1.36
109	374.715	8.082	-8.224	1.36
110	374.715	8.082	-8.224	1.36
111	374.715	8.082	-8.224	1.36
112	374.715	8.082	-8.224	1.36
113	374.742	8.082	-8.222	1.36
114	374.769	8.082	-8.219	1.36
115	374.688	8.082	-8.227	1.37
116	374.715	8.082	-8.224	1.36
117	374.742	8.082	-8.222	1.36
118	374.769	8.082	-8.219	1.36
119	374.769	8.082	-8.219	1.36
120	374.796	8.082	-8.216	1.36
121	374.85	8.082	-8.211	1.35
122	374.85	8.082	-8.211	1.35
123	374.715	8.082	-8.224	1.36
124	374.769	8.082	-8.219	1.36
125	374.796	8.082	-8.216	1.36
126	374.769	8.082	-8.219	1.36
127	374.85	8.082	-8.211	1.35
128	374.904	8.082	-8.205	1.35
129	374.932	8.082	-8.202	1.34
130	374.904	8.082	-8.205	1.35
131	374.904	8.082	-8.205	1.35
132	374.877	8.082	-8.208	1.35
133	374.932	8.082	-8.202	1.34
134	374.986	8.082	-8.197	1.34
135	374.959	8.082	-8.199	1.34
136	374.932	8.082	-8.202	1.34
137	374.932	8.082	-8.202	1.34
138	374.932	8.082	-8.202	1.34
139	374.932	8.082	-8.202	1.34
140	374.986	8.082	-8.197	1.34
141	374.904	8.082	-8.205	1.35
142	374.986	8.082	-8.197	1.34
143	374.959	8.082	-8.199	1.34
144	374.959	8.082	-8.199	1.34
145	374.986	8.082	-8.197	1.34
146	374.986	8.082	-8.197	1.34
147	375.013	8.082	-8.194	1.33
148	375.067	8.082	-8.188	1.33
149	374.986	8.082	-8.197	1.34
150	375.04	8.082	-8.191	1.33
151	375.094	8.082	-8.186	1.33
152	374.986	8.082	-8.197	1.34
153	374.959	8.082	-8.199	1.34
154	375.013	8.082	-8.194	1.33
155	374.986	8.082	-8.197	1.34
156	374.959	8.082	-8.199	1.34
157	374.959	8.082	-8.199	1.34
158	374.986	8.082	-8.197	1.34
159	374.986	8.082	-8.197	1.34
160	374.904	8.082	-8.205	1.35
161	374.823	8.082	-8.213	1.35
162	374.823	8.082	-8.213	1.35
163	374.904	8.082	-8.205	1.35
164	374.85	8.082	-8.211	1.35
165	374.877	8.082	-8.208	1.35
166	374.877	8.082	-8.208	1.35
167	374.877	8.082	-8.208	1.35
168	374.904	8.082	-8.205	1.35
169	374.932	8.082	-8.202	1.34
170	374.877	8.082	-8.208	1.35
171	374.959	8.082	-8.199	1.34
172	374.986	8.082	-8.197	1.34
173	374.932	8.082	-8.202	1.34
174	374.904	8.082	-8.205	1.35
175	374.85	8.082	-8.211	1.35
176	374.715	8.082	-8.224	1.36
177	374.769	8.082	-8.219	1.36
178	374.796	8.082	-8.216	1.36
179	374.796	8.082	-8.216	1.36

180	374.85	8.082	-8.211	1.35
181	374.823	8.082	-8.213	1.35
182	374.85	8.082	-8.211	1.35
183	374.796	8.082	-8.216	1.36
184	374.715	8.082	-8.224	1.36
185	374.742	8.082	-8.222	1.36
186	374.688	8.082	-8.227	1.37
187	374.66	8.082	-8.23	1.37
188	374.633	8.082	-8.233	1.37
189	374.66	8.082	-8.23	1.37
190	374.715	8.082	-8.224	1.36
191	374.688	8.082	-8.227	1.37
192	374.688	8.082	-8.227	1.37
193	374.715	8.082	-8.224	1.36
194	374.66	8.082	-8.23	1.37
195	374.742	8.082	-8.222	1.36
196	374.66	8.082	-8.23	1.37
197	374.66	8.082	-8.23	1.37
198	374.688	8.082	-8.227	1.37
199	374.688	8.082	-8.227	1.37
200	374.742	8.082	-8.222	1.36
201	374.742	8.082	-8.222	1.36
202	374.796	8.082	-8.216	1.36
203	374.769	8.082	-8.219	1.36
204	374.769	8.082	-8.219	1.36
205	374.796	8.082	-8.216	1.36
206	374.796	8.082	-8.216	1.36
207	374.823	8.082	-8.213	1.35
208	374.85	8.082	-8.211	1.35
209	374.877	8.082	-8.208	1.35
210	374.796	8.082	-8.216	1.36
211	374.796	8.082	-8.216	1.36
212	374.796	8.082	-8.216	1.36
213	374.85	8.082	-8.211	1.35
214	374.823	8.082	-8.213	1.35
215	374.85	8.082	-8.211	1.35
216	374.85	8.082	-8.211	1.35
217	374.85	8.082	-8.211	1.35
218	374.877	8.082	-8.208	1.35
219	374.85	8.082	-8.211	1.35
220	374.85	8.082	-8.211	1.35
221	374.904	8.082	-8.205	1.35
222	374.904	8.082	-8.205	1.35
223	374.85	8.082	-8.211	1.35
224	374.877	8.082	-8.208	1.35
225	374.877	8.082	-8.208	1.35
226	374.877	8.082	-8.208	1.35
227	374.877	8.082	-8.208	1.35
228	374.877	8.082	-8.208	1.35
229	374.904	8.082	-8.205	1.35
230	374.877	8.082	-8.208	1.35
231	374.85	8.082	-8.211	1.35
232	374.877	8.082	-8.208	1.35
233	374.85	8.082	-8.211	1.35
234	374.932	8.082	-8.202	1.34
235	374.904	8.082	-8.205	1.35
236	374.877	8.082	-8.208	1.35
237	374.85	8.082	-8.211	1.35
238	374.823	8.082	-8.213	1.35
239	374.85	8.082	-8.211	1.35
240	374.823	8.082	-8.213	1.35
241	374.85	8.082	-8.211	1.35
242	374.85	8.082	-8.211	1.35
243	374.85	8.082	-8.211	1.35
244	374.877	8.082	-8.208	1.35
245	374.796	8.082	-8.216	1.36
246	374.742	8.082	-8.222	1.36
247	374.688	8.082	-8.227	1.37
248	374.742	8.082	-8.222	1.36
249	374.688	8.082	-8.227	1.37
250	374.688	8.082	-8.227	1.37
251	374.688	8.082	-8.227	1.37
252	374.742	8.082	-8.222	1.36
253	374.742	8.082	-8.222	1.36
254	374.66	8.082	-8.23	1.37
255	374.715	8.082	-8.224	1.36
256	374.66	8.082	-8.23	1.37
257	374.715	8.082	-8.224	1.36
258	374.769	8.082	-8.219	1.36
259	374.742	8.082	-8.222	1.36
260	374.715	8.082	-8.224	1.36
261	374.688	8.082	-8.227	1.37
262	374.66	8.082	-8.23	1.37
263	374.66	8.082	-8.23	1.37
264	374.66	8.082	-8.23	1.37
265	374.66	8.082	-8.23	1.37
266	374.688	8.082	-8.227	1.37
267	374.688	8.082	-8.227	1.37
268	374.633	8.082	-8.233	1.37
269	374.66	8.082	-8.23	1.37
270	374.606	8.082	-8.235	1.38
271	374.606	8.082	-8.235	1.38
272	374.633	8.082	-8.233	1.37

273	374.606	8.082	-8.235	1.38
274	374.633	8.082	-8.233	1.37
275	374.552	8.082	-8.241	1.38
276	374.606	8.082	-8.235	1.38
277	374.688	8.082	-8.227	1.37
278	374.66	8.082	-8.23	1.37
279	374.688	8.082	-8.227	1.37
280	374.66	8.082	-8.23	1.37
281	374.633	8.082	-8.233	1.37
282	374.606	8.082	-8.235	1.38
283	374.606	8.082	-8.235	1.38
284	374.633	8.082	-8.233	1.37
285	374.498	8.082	-8.246	1.39
286	374.471	8.082	-8.249	1.39
287	374.471	8.082	-8.249	1.39
288	374.498	8.082	-8.246	1.39
289	374.498	8.082	-8.246	1.39
290	374.498	8.082	-8.246	1.39
291	374.471	8.082	-8.249	1.39
292	374.471	8.082	-8.249	1.39
293	374.471	8.082	-8.249	1.39
294	374.498	8.082	-8.246	1.39
295	374.525	8.082	-8.244	1.38
296	374.552	8.082	-8.241	1.38
297	374.552	8.082	-8.241	1.38
298	374.552	8.082	-8.241	1.38
299	374.552	8.082	-8.241	1.38
300	374.606	8.082	-8.235	1.38
301	374.552	8.082	-8.241	1.38
302	374.552	8.082	-8.241	1.38
303	374.579	8.082	-8.238	1.38
304	374.552	8.082	-8.241	1.38
305	374.498	8.082	-8.246	1.39
306	374.552	8.082	-8.241	1.38
307	374.552	8.082	-8.241	1.38
308	374.579	8.082	-8.238	1.38
309	374.552	8.082	-8.241	1.38
310	374.525	8.082	-8.244	1.38
311	374.525	8.082	-8.244	1.38
312	374.552	8.082	-8.241	1.38
313	374.579	8.082	-8.238	1.38
314	374.552	8.082	-8.241	1.38
315	374.579	8.082	-8.238	1.38
316	374.606	8.082	-8.235	1.38
317	374.525	8.082	-8.244	1.38
318	374.579	8.082	-8.238	1.38
319	374.525	8.082	-8.244	1.38
320	374.552	8.082	-8.241	1.38
321	374.552	8.082	-8.241	1.38
322	374.579	8.082	-8.238	1.38
323	374.552	8.082	-8.241	1.38
324	374.579	8.082	-8.238	1.38
325	374.579	8.082	-8.238	1.38
326	374.525	8.082	-8.244	1.38
327	374.606	8.082	-8.235	1.38
328	374.552	8.082	-8.241	1.38
329	374.579	8.082	-8.238	1.38
330	374.525	8.082	-8.244	1.38
331	374.579	8.082	-8.238	1.38
332	374.579	8.082	-8.238	1.38
333	374.552	8.082	-8.241	1.38
334	374.416	8.082	-8.255	1.40
335	374.362	8.082	-8.26	1.40
336	374.416	8.082	-8.255	1.40
337	374.471	8.082	-8.249	1.39
338	374.498	8.082	-8.246	1.39
339	374.606	8.082	-8.235	1.38
340	374.579	8.082	-8.238	1.38
341	374.579	8.082	-8.238	1.38
342	374.552	8.082	-8.241	1.38
343	374.579	8.082	-8.238	1.38
344	374.552	8.082	-8.241	1.38
345	374.525	8.082	-8.244	1.38
346	374.525	8.082	-8.244	1.38
347	374.552	8.082	-8.241	1.38
348	374.579	8.082	-8.238	1.38
349	374.579	8.082	-8.238	1.38
350	374.579	8.082	-8.238	1.38
351	374.579	8.082	-8.238	1.38
352	374.579	8.082	-8.238	1.38
353	374.579	8.082	-8.238	1.38
354	374.579	8.082	-8.238	1.38
355	374.552	8.082	-8.241	1.38
356	374.525	8.082	-8.244	1.38
357	374.579	8.082	-8.238	1.38
358	374.552	8.082	-8.241	1.38
359	374.579	8.082	-8.238	1.38
360	374.552	8.082	-8.241	1.38

TW1- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



RECOVERY DATA TW-1


t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	361	385.053	8.082	-7.17	0.31	78%
2	181.0	386.275	8.082	-7.045	0.19	87%
3	121.0	386.601	8.082	-7.012	0.15	89%
4	91.0	386.846	8.082	-6.987	0.13	91%
5	73.0	386.954	8.082	-6.976	0.12	92%
6	61.0	387.063	8.082	-6.965	0.11	92%
7	52.4	387.144	8.082	-6.957	0.10	93%
8	46.0	387.199	8.082	-6.951	0.09	93%
9	41.0	387.226	8.082	-6.949	0.09	94%
10	37.0	387.253	8.082	-6.946	0.09	94%
11	33.7	387.28	8.082	-6.943	0.08	94%
12	31.0	387.307	8.082	-6.94	0.08	94%
13	28.7	387.335	8.082	-6.937	0.08	94%
14	26.7	387.416	8.082	-6.929	0.07	95%
15	25.0	387.443	8.082	-6.926	0.07	95%
16	23.5	387.443	8.082	-6.926	0.07	95%
17	22.2	387.498	8.082	-6.921	0.06	96%
18	21.0	387.498	8.082	-6.921	0.06	96%
19	19.9	387.525	8.082	-6.918	0.06	96%
20	19.0	387.525	8.082	-6.918	0.06	96%
21	18.1	387.525	8.082	-6.918	0.06	96%
22	17.4	387.525	8.082	-6.918	0.06	96%
23	16.7	387.498	8.082	-6.921	0.06	96%
24	16.0	387.525	8.082	-6.918	0.06	96%
25	15.4	387.552	8.082	-6.915	0.05	96%
26	14.8	387.525	8.082	-6.918	0.06	96%
27	14.3	387.416	8.082	-6.929	0.07	95%
28	13.9	386.248	8.082	-7.048	0.19	86%
29	13.4	386.628	8.082	-7.009	0.15	89%
30	13.0	387.498	8.082	-6.921	0.06	96%
31	12.6	387.552	8.082	-6.915	0.05	96%
32	12.3	387.579	8.082	-6.913	0.05	96%
33	11.9	387.579	8.082	-6.913	0.05	96%
34	11.6	387.579	8.082	-6.913	0.05	96%
35	11.3	387.579	8.082	-6.913	0.05	96%
36	11.0	387.606	8.082	-6.91	0.05	96%
37	10.7	387.642	8.182	-6.906	0.05	97%
38	10.5	387.633	8.082	-6.907	0.05	97%
39	10.2	387.669	8.182	-6.903	0.04	97%
40	10.0	387.669	8.182	-6.903	0.04	97%
41	9.8	387.669	8.182	-6.903	0.04	97%
42	9.6	387.669	8.182	-6.903	0.04	97%
43	9.4	387.669	8.182	-6.903	0.04	97%
44	9.2	387.669	8.182	-6.903	0.04	97%
45	9.0	387.696	8.182	-6.901	0.04	97%
46	8.8	387.696	8.182	-6.901	0.04	97%
47	8.7	387.669	8.182	-6.903	0.04	97%
48	8.5	387.696	8.182	-6.901	0.04	97%
49	8.3	387.696	8.182	-6.901	0.04	97%
50	8.2	387.669	8.182	-6.903	0.04	97%
51	8.1	387.669	8.182	-6.903	0.04	97%
52	7.9	387.669	8.182	-6.903	0.04	97%
53	7.8	387.669	8.182	-6.903	0.04	97%
54	7.7	387.669	8.182	-6.903	0.04	97%
55	7.5	387.669	8.182	-6.903	0.04	97%
56	7.4	387.669	8.182	-6.903	0.04	97%
57	7.3	387.669	8.182	-6.903	0.04	97%
58	7.2	387.669	8.182	-6.903	0.04	97%
59	7.1	387.669	8.182	-6.903	0.04	97%
60	7.0	387.642	8.182	-6.906	0.05	97%



ATTACHMENT I

PUMPING TEST DATA FOR TW2

TW2-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



DRAWDOWN DATA TW2


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	392.344	8.182	-6.68	0.00
1	390.194	8.182	-6.899	0.22
2	390.672	8.182	-6.85	0.17
3	386.79	8.182	-7.246	0.57
4	385.417	8.182	-7.386	0.71
5	384.969	8.182	-7.432	0.75
6	384.88	8.182	-7.441	0.76
7	384.73	8.182	-7.456	0.78
8	383.738	8.082	-7.558	0.88
9	383.35	8.082	-7.597	0.92
10	383.231	8.082	-7.609	0.93
11	383.112	8.082	-7.621	0.94
12	383.022	8.082	-7.631	0.95
13	382.992	8.082	-7.634	0.95
14	382.903	8.082	-7.643	0.96
15	382.903	8.082	-7.643	0.96
16	382.962	8.082	-7.637	0.96
17	382.955	7.983	-7.637	0.96
18	382.955	7.983	-7.637	0.96
19	382.866	7.983	-7.646	0.97
20	382.896	7.983	-7.643	0.96
21	382.985	7.983	-7.634	0.95
22	382.866	7.983	-7.646	0.97
23	382.866	7.983	-7.646	0.97
24	382.926	7.983	-7.64	0.96
25	382.806	7.983	-7.653	0.97
26	382.836	7.983	-7.65	0.97
27	382.806	7.983	-7.653	0.97
28	382.746	7.983	-7.659	0.98
29	382.687	7.983	-7.665	0.99
30	382.866	7.983	-7.646	0.97
31	382.717	7.983	-7.662	0.98
32	382.687	7.983	-7.665	0.99
33	382.687	7.983	-7.665	0.99
34	382.687	7.983	-7.665	0.99
35	382.657	7.983	-7.668	0.99
36	382.776	7.983	-7.656	0.98
37	382.687	7.983	-7.665	0.99
38	382.567	7.983	-7.677	1.00
39	382.538	7.983	-7.68	1.00
40	382.657	7.983	-7.668	0.99
41	382.687	7.983	-7.665	0.99
42	382.687	7.983	-7.665	0.99
43	382.717	7.983	-7.662	0.98
44	382.538	7.983	-7.68	1.00
45	382.508	7.983	-7.683	1.00
46	382.627	7.983	-7.671	0.99
47	382.508	7.983	-7.683	1.00
48	382.687	7.983	-7.665	0.99
49	382.597	7.983	-7.674	0.99
50	382.597	7.983	-7.674	0.99
51	382.657	7.983	-7.668	0.99
52	382.597	7.983	-7.674	0.99
53	382.597	7.983	-7.674	0.99
54	382.597	7.983	-7.674	0.99
55	382.687	7.983	-7.665	0.99
56	382.657	7.983	-7.668	0.99
57	382.597	7.983	-7.674	0.99
58	382.209	7.983	-7.713	1.03
59	382.329	7.983	-7.701	1.02
60	382.418	7.983	-7.692	1.01
61	382.567	7.983	-7.677	1.00
62	382.478	7.983	-7.686	1.01
63	382.508	7.983	-7.683	1.00
64	382.567	7.983	-7.677	1.00
65	382.388	7.983	-7.695	1.02
66	382.478	7.983	-7.686	1.01
67	382.538	7.983	-7.68	1.00
68	382.627	7.983	-7.671	0.99
69	382.508	7.983	-7.683	1.00
70	382.418	7.983	-7.692	1.01
71	382.508	7.983	-7.683	1.00
72	382.687	7.983	-7.665	0.99
73	382.448	7.983	-7.689	1.01
74	382.448	7.983	-7.689	1.01
75	382.508	7.983	-7.683	1.00
76	382.538	7.983	-7.68	1.00
77	382.388	7.983	-7.695	1.02
78	382.538	7.983	-7.68	1.00
79	382.567	7.983	-7.677	1.00
80	382.448	7.983	-7.689	1.01
81	382.478	7.983	-7.686	1.01
82	382.448	7.983	-7.689	1.01
83	382.418	7.983	-7.692	1.01
84	382.388	7.983	-7.695	1.02
85	382.508	7.983	-7.683	1.00
86	382.448	7.983	-7.689	1.01

87	382.448	7.983	-7.689	1.01
88	382.418	7.983	-7.692	1.01
89	382.508	7.983	-7.683	1.00
90	382.478	7.983	-7.686	1.01
91	382.418	7.983	-7.692	1.01
92	382.388	7.983	-7.695	1.02
93	382.388	7.983	-7.695	1.02
94	382.329	7.983	-7.701	1.02
95	382.358	7.983	-7.698	1.02
96	382.329	7.983	-7.701	1.02
97	382.388	7.983	-7.695	1.02
98	382.299	7.983	-7.704	1.02
99	382.299	7.983	-7.704	1.02
100	382.358	7.983	-7.698	1.02
101	382.329	7.983	-7.701	1.02
102	382.358	7.983	-7.698	1.02
103	382.388	7.983	-7.695	1.02
104	382.358	7.983	-7.698	1.02
105	382.388	7.983	-7.695	1.02
106	382.388	7.983	-7.695	1.02
107	382.418	7.983	-7.692	1.01
108	382.418	7.983	-7.692	1.01
109	382.299	7.983	-7.704	1.02
110	382.358	7.983	-7.698	1.02
111	382.388	7.983	-7.695	1.02
112	382.418	7.983	-7.692	1.01
113	382.329	7.983	-7.701	1.02
114	382.388	7.983	-7.695	1.02
115	382.388	7.983	-7.695	1.02
116	382.329	7.983	-7.701	1.02
117	382.299	7.983	-7.704	1.02
118	382.329	7.983	-7.701	1.02
119	382.329	7.983	-7.701	1.02
120	382.418	7.983	-7.692	1.01
121	382.388	7.983	-7.695	1.02
122	382.388	7.983	-7.695	1.02
123	382.388	7.983	-7.695	1.02
124	382.388	7.983	-7.695	1.02
125	382.329	7.983	-7.701	1.02
126	382.299	7.983	-7.704	1.02
127	382.299	7.983	-7.704	1.02
128	382.358	7.983	-7.698	1.02
129	382.329	7.983	-7.701	1.02
130	382.209	7.983	-7.713	1.03
131	382.448	7.983	-7.689	1.01
132	382.358	7.983	-7.698	1.02
133	382.508	7.983	-7.683	1.00
134	382.329	7.983	-7.701	1.02
135	382.448	7.983	-7.689	1.01
136	382.358	7.983	-7.698	1.02
137	382.239	7.983	-7.71	1.03
138	382.329	7.983	-7.701	1.02
139	382.358	7.983	-7.698	1.02
140	382.388	7.983	-7.695	1.02
141	382.358	7.983	-7.698	1.02
142	382.418	7.983	-7.692	1.01
143	382.448	7.983	-7.689	1.01
144	382.388	7.983	-7.695	1.02
145	382.388	7.983	-7.695	1.02
146	382.329	7.983	-7.701	1.02
147	382.239	7.983	-7.71	1.03
148	382.418	7.983	-7.692	1.01
149	382.269	7.983	-7.707	1.03
150	382.358	7.983	-7.698	1.02
151	382.299	7.983	-7.704	1.02
152	382.478	7.983	-7.686	1.01
153	382.448	7.983	-7.689	1.01
154	382.269	7.983	-7.707	1.03
155	382.269	7.983	-7.707	1.03
156	382.358	7.983	-7.698	1.02
157	382.448	7.983	-7.689	1.01
158	382.299	7.983	-7.704	1.02
159	382.388	7.983	-7.695	1.02
160	382.299	7.983	-7.704	1.02
161	382.478	7.983	-7.686	1.01
162	382.358	7.983	-7.698	1.02
163	382.388	7.983	-7.695	1.02
164	382.329	7.983	-7.701	1.02
165	382.299	7.983	-7.704	1.02
166	382.448	7.983	-7.689	1.01
167	382.269	7.983	-7.707	1.03
168	382.209	7.983	-7.713	1.03
169	382.269	7.983	-7.707	1.03
170	382.329	7.983	-7.701	1.02
171	382.329	7.983	-7.701	1.02
172	382.358	7.983	-7.698	1.02
173	382.299	7.983	-7.704	1.02
174	382.299	7.983	-7.704	1.02
175	382.299	7.983	-7.704	1.02
176	382.329	7.983	-7.701	1.02
177	382.239	7.983	-7.71	1.03
178	382.329	7.983	-7.701	1.02
179	382.358	7.983	-7.698	1.02

180	382.358	7.983	-7.698	1.02
181	382.299	7.983	-7.704	1.02
182	382.329	7.983	-7.701	1.02
183	382.329	7.983	-7.701	1.02
184	382.329	7.983	-7.701	1.02
185	382.299	7.983	-7.704	1.02
186	382.269	7.983	-7.707	1.03
187	382.299	7.983	-7.704	1.02
188	382.299	7.983	-7.704	1.02
189	382.269	7.983	-7.707	1.03
190	382.329	7.983	-7.701	1.02
191	382.269	7.983	-7.707	1.03
192	382.269	7.983	-7.707	1.03
193	382.209	7.983	-7.713	1.03
194	382.299	7.983	-7.704	1.02
195	382.239	7.983	-7.71	1.03
196	382.239	7.983	-7.71	1.03
197	382.239	7.983	-7.71	1.03
198	382.388	7.983	-7.695	1.02
199	382.239	7.983	-7.71	1.03
200	382.299	7.983	-7.704	1.02
201	382.209	7.983	-7.713	1.03
202	382.269	7.983	-7.707	1.03
203	382.239	7.983	-7.71	1.03
204	382.209	7.983	-7.713	1.03
205	382.269	7.983	-7.707	1.03
206	382.06	7.983	-7.729	1.05
207	382.09	7.983	-7.726	1.05
208	382.299	7.983	-7.704	1.02
209	382.179	7.983	-7.717	1.04
210	382.239	7.983	-7.71	1.03
211	382.179	7.983	-7.717	1.04
212	382.209	7.983	-7.713	1.03
213	382.06	7.983	-7.729	1.05
214	382.209	7.983	-7.713	1.03
215	382.12	7.983	-7.723	1.04
216	382.12	7.983	-7.723	1.04
217	382.12	7.983	-7.723	1.04
218	382.179	7.983	-7.717	1.04
219	382.179	7.983	-7.717	1.04
220	382.15	7.983	-7.719	1.04
221	382.15	7.983	-7.719	1.04
222	382.09	7.983	-7.726	1.05
223	382.09	7.983	-7.726	1.05
224	382.09	7.983	-7.726	1.05
225	382.06	7.983	-7.729	1.05
226	382.15	7.983	-7.719	1.04
227	382.06	7.983	-7.729	1.05
228	382.09	7.983	-7.726	1.05
229	382.03	7.983	-7.732	1.05
230	382.06	7.983	-7.729	1.05
231	382.03	7.983	-7.732	1.05
232	382.09	7.983	-7.726	1.05
233	382.09	7.983	-7.726	1.05
234	382	7.983	-7.735	1.06
235	382.06	7.983	-7.729	1.05
236	381.971	7.983	-7.738	1.06
237	381.941	7.983	-7.741	1.06
238	382	7.983	-7.735	1.06
239	382.179	7.983	-7.717	1.04
240	382.03	7.983	-7.732	1.05
241	382.06	7.983	-7.729	1.05
242	382.15	7.983	-7.719	1.04
243	382.09	7.983	-7.726	1.05
244	382.209	7.983	-7.713	1.03
245	382.12	7.983	-7.723	1.04
246	382.12	7.983	-7.723	1.04
247	382.09	7.983	-7.726	1.05
248	382.03	7.983	-7.732	1.05
249	382.03	7.983	-7.732	1.05
250	381.971	7.983	-7.738	1.06
251	382.03	7.983	-7.732	1.05
252	382	7.983	-7.735	1.06
253	381.971	7.983	-7.738	1.06
254	382.03	7.983	-7.732	1.05
255	382.209	7.983	-7.713	1.03
256	382	7.983	-7.735	1.06
257	382.09	7.983	-7.726	1.05
258	382.03	7.983	-7.732	1.05
259	382.03	7.983	-7.732	1.05
260	381.941	7.983	-7.741	1.06
261	382.06	7.983	-7.729	1.05
262	382.06	7.983	-7.729	1.05
263	382.06	7.983	-7.729	1.05
264	382.12	7.983	-7.723	1.04
265	382.06	7.983	-7.729	1.05
266	382.179	7.983	-7.717	1.04
267	382.06	7.983	-7.729	1.05
268	382.03	7.983	-7.732	1.05
269	382.09	7.983	-7.726	1.05
270	382.09	7.983	-7.726	1.05
271	382.179	7.983	-7.717	1.04
272	382.09	7.983	-7.726	1.05

273	382.12	7.983	-7.723	1.04
274	382.12	7.983	-7.723	1.04
275	382.12	7.983	-7.723	1.04
276	382.239	7.983	-7.71	1.03
277	382	7.983	-7.735	1.06
278	382.12	7.983	-7.723	1.04
279	382.15	7.983	-7.719	1.04
280	382	7.983	-7.735	1.06
281	382.12	7.983	-7.723	1.04
282	382.09	7.983	-7.726	1.05
283	382.15	7.983	-7.719	1.04
284	382.09	7.983	-7.726	1.05
285	382	7.983	-7.735	1.06
286	382.06	7.983	-7.729	1.05
287	382.03	7.983	-7.732	1.05
288	382	7.983	-7.735	1.06
289	382.179	7.983	-7.717	1.04
290	382.15	7.983	-7.719	1.04
291	382.12	7.983	-7.723	1.04
292	382.09	7.983	-7.726	1.05
293	382.09	7.983	-7.726	1.05
294	382.09	7.983	-7.726	1.05
295	382	7.983	-7.735	1.06
296	382.09	7.983	-7.726	1.05
297	381.941	7.983	-7.741	1.06
298	382.03	7.983	-7.732	1.05
299	382.12	7.983	-7.723	1.04
300	382.09	7.983	-7.726	1.05
301	382.06	7.983	-7.729	1.05
302	382.03	7.983	-7.732	1.05
303	382.06	7.983	-7.729	1.05
304	382	7.983	-7.735	1.06
305	382.03	7.983	-7.732	1.05
306	382.03	7.983	-7.732	1.05
307	382.06	7.983	-7.729	1.05
308	382.03	7.983	-7.732	1.05
309	382	7.983	-7.735	1.06
310	382.239	7.983	-7.71	1.03
311	381.941	7.983	-7.741	1.06
312	382.03	7.983	-7.732	1.05
313	381.971	7.983	-7.738	1.06
314	382.06	7.983	-7.729	1.05
315	382	7.983	-7.735	1.06
316	382.09	7.983	-7.726	1.05
317	381.941	7.983	-7.741	1.06
318	382.06	7.983	-7.729	1.05
319	381.971	7.983	-7.738	1.06
320	382.06	7.983	-7.729	1.05
321	381.911	7.983	-7.744	1.06
322	381.732	7.983	-7.762	1.08
323	381.881	7.983	-7.747	1.07
324	381.911	7.983	-7.744	1.06
325	381.971	7.983	-7.738	1.06
326	382.03	7.983	-7.732	1.05
327	382	7.983	-7.735	1.06
328	381.941	7.983	-7.741	1.06
329	382.12	7.983	-7.723	1.04
330	381.851	7.983	-7.75	1.07
331	381.971	7.983	-7.738	1.06
332	381.941	7.983	-7.741	1.06
333	381.971	7.983	-7.738	1.06
334	381.941	7.983	-7.741	1.06
335	381.941	7.983	-7.741	1.06
336	381.971	7.983	-7.738	1.06
337	382	7.983	-7.735	1.06
338	381.941	7.983	-7.741	1.06
339	382	7.983	-7.735	1.06
340	382	7.983	-7.735	1.06
341	382	7.983	-7.735	1.06
342	381.941	7.983	-7.741	1.06
343	382.12	7.983	-7.723	1.04
344	381.971	7.983	-7.738	1.06
345	382	7.983	-7.735	1.06
346	381.911	7.983	-7.744	1.06
347	381.971	7.983	-7.738	1.06
348	382.06	7.983	-7.729	1.05
349	382	7.983	-7.735	1.06
350	382	7.983	-7.735	1.06
351	381.941	7.983	-7.741	1.06
352	381.971	7.983	-7.738	1.06
353	381.971	7.983	-7.738	1.06
354	382.06	7.983	-7.729	1.05
355	381.971	7.983	-7.738	1.06
356	382.09	7.983	-7.726	1.05
357	381.971	7.983	-7.738	1.06
358	382.09	7.983	-7.726	1.05
359	381.971	7.983	-7.738	1.06
360	382.15	7.983	-7.719	1.04
361	382.06	7.983	-7.729	1.05
362	382	7.983	-7.735	1.06
363	381.941	7.983	-7.741	1.06
364	382.06	7.983	-7.729	1.05
365	382.179	7.983	-7.717	1.04

TW2- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



RECOVERY DATA TW-2

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	366.0	389.523	7.983	-6.968	0.29	73%
2	183.5	390.359	7.983	-6.882	0.20	81%
3	122.7	390.687	7.983	-6.849	0.17	84%
4	92.3	390.896	7.983	-6.828	0.15	86%
5	74.0	391.016	7.983	-6.815	0.14	87%
6	61.8	391.105	7.983	-6.806	0.13	88%
7	53.1	391.195	7.983	-6.797	0.12	89%
8	46.6	391.255	7.983	-6.791	0.11	90%
9	41.6	391.314	7.983	-6.785	0.11	90%
10	37.5	391.374	7.983	-6.779	0.10	91%
11	34.2	391.374	7.983	-6.779	0.10	91%
12	31.4	391.374	7.983	-6.779	0.10	91%
13	29.1	391.434	7.983	-6.773	0.09	91%
14	27.1	391.464	7.983	-6.77	0.09	91%
15	25.3	391.494	7.983	-6.767	0.09	92%
16	23.8	391.523	7.983	-6.764	0.08	92%
17	22.5	391.523	7.983	-6.764	0.08	92%
18	21.3	391.523	7.983	-6.764	0.08	92%
19	20.2	391.523	7.983	-6.764	0.08	92%
20	19.3	391.523	7.983	-6.764	0.08	92%
21	18.4	391.494	7.983	-6.767	0.09	92%
22	17.6	391.523	7.983	-6.764	0.08	92%
23	16.9	391.553	7.983	-6.761	0.08	92%
24	16.2	391.553	7.983	-6.761	0.08	92%
25	15.6	391.553	7.983	-6.761	0.08	92%
26	15.0	391.553	7.983	-6.761	0.08	92%
27	14.5	391.553	7.983	-6.761	0.08	92%
28	14.0	391.583	7.983	-6.758	0.08	93%
29	13.6	391.553	7.983	-6.761	0.08	92%
30	13.2	391.583	7.983	-6.758	0.08	93%
31	12.8	391.583	7.983	-6.758	0.08	93%
32	12.4	391.553	7.983	-6.761	0.08	92%
33	12.1	391.553	7.983	-6.761	0.08	92%
34	11.7	391.553	7.983	-6.761	0.08	92%
35	11.4	391.583	7.983	-6.758	0.08	93%
36	11.1	391.583	7.983	-6.758	0.08	93%
37	10.9	391.613	7.983	-6.755	0.08	93%
38	10.6	391.583	7.983	-6.758	0.08	93%
39	10.4	391.583	7.983	-6.758	0.08	93%
40	10.1	391.583	7.983	-6.758	0.08	93%
41	9.9	391.583	7.983	-6.758	0.08	93%
42	9.7	391.583	7.983	-6.758	0.08	93%
43	9.5	391.583	7.983	-6.758	0.08	93%
44	9.3	391.613	7.983	-6.755	0.08	93%
45	9.1	391.553	7.983	-6.761	0.08	92%
46	8.9	390.687	7.983	-6.849	0.17	84%
47	8.8	391.673	7.983	-6.748	0.07	94%
48	8.6	391.613	7.983	-6.755	0.08	93%
49	8.4	391.673	7.983	-6.748	0.07	94%
50	8.3	391.643	7.983	-6.751	0.07	93%
51	8.2	391.643	7.983	-6.751	0.07	93%
52	8.0	391.673	7.983	-6.748	0.07	94%
53	7.9	391.673	7.983	-6.748	0.07	94%
54	7.8	390.986	7.983	-6.818	0.14	87%
55	7.6	391.016	7.983	-6.815	0.14	87%
56	7.5	391.703	7.983	-6.745	0.07	94%
57	7.4	391.733	7.983	-6.742	0.06	94%
58	7.3	391.942	7.983	-6.721	0.04	96%


59	7.2	391.673	7.983	-6.748	0.07	94%
60	7.1	391.643	7.983	-6.751	0.07	93%
61	7.0	391.673	7.983	-6.748	0.07	94%
62	6.9	391.673	7.983	-6.748	0.07	94%
63	6.8	391.673	7.983	-6.748	0.07	94%
64	6.7	391.703	7.983	-6.745	0.07	94%
65	6.6	391.74	8.082	-6.742	0.06	94%
66	6.5	391.74	8.082	-6.742	0.06	94%
67	6.4	391.74	8.082	-6.742	0.06	94%
68	6.4	391.77	8.082	-6.739	0.06	94%
69	6.3	391.77	8.082	-6.739	0.06	94%
70	6.2	391.77	8.082	-6.739	0.06	94%
71	6.1	391.77	8.082	-6.739	0.06	94%
72	6.1	391.799	8.082	-6.736	0.06	95%
73	6.0	391.77	8.082	-6.739	0.06	94%
74	5.9	391.77	8.082	-6.739	0.06	94%
75	5.9	391.799	8.082	-6.736	0.06	95%
76	5.8	391.799	8.082	-6.736	0.06	95%
77	5.7	391.799	8.082	-6.736	0.06	95%
78	5.7	391.799	8.082	-6.736	0.06	95%
79	5.6	391.829	8.082	-6.733	0.05	95%
80	5.6	391.859	8.082	-6.729	0.05	95%
81	5.5	391.859	8.082	-6.729	0.05	95%
82	5.5	391.859	8.082	-6.729	0.05	95%
83	5.4	391.859	8.082	-6.729	0.05	95%
84	5.3	391.829	8.082	-6.733	0.05	95%
85	5.3	391.829	8.082	-6.733	0.05	95%
86	5.2	391.829	8.082	-6.733	0.05	95%
87	5.2	391.829	8.082	-6.733	0.05	95%
88	5.1	391.829	8.082	-6.733	0.05	95%
89	5.1	391.829	8.082	-6.733	0.05	95%
90	5.1	391.829	8.082	-6.733	0.05	95%
91	5.0	391.829	8.082	-6.733	0.05	95%
92	5.0	391.859	8.082	-6.729	0.05	95%
93	4.9	391.859	8.082	-6.729	0.05	95%
94	4.9	391.889	8.082	-6.726	0.05	96%
95	4.8	391.859	8.082	-6.729	0.05	95%
96	4.8	391.859	8.082	-6.729	0.05	95%
97	4.8	391.859	8.082	-6.729	0.05	95%
98	4.7	391.859	8.082	-6.729	0.05	95%
99	4.7	391.859	8.082	-6.729	0.05	95%
100	4.7	391.889	8.082	-6.726	0.05	96%
101	4.6	391.889	8.082	-6.726	0.05	96%
102	4.6	391.889	8.082	-6.726	0.05	96%
103	4.5	391.919	8.082	-6.723	0.04	96%
104	4.5	391.919	8.082	-6.723	0.04	96%
105	4.5	391.919	8.082	-6.723	0.04	96%
106	4.4	391.919	8.082	-6.723	0.04	96%
107	4.4	391.889	8.082	-6.726	0.05	96%
108	4.4	391.919	8.082	-6.723	0.04	96%
109	4.3	391.949	8.082	-6.72	0.04	96%
110	4.3	391.949	8.082	-6.72	0.04	96%
111	4.3	391.979	8.082	-6.717	0.04	97%
112	4.3	391.979	8.082	-6.717	0.04	97%
113	4.2	391.979	8.082	-6.717	0.04	97%
114	4.2	392.008	8.082	-6.714	0.03	97%
115	4.2	391.979	8.082	-6.717	0.04	97%
116	4.1	391.979	8.082	-6.717	0.04	97%
117	4.1	391.979	8.082	-6.717	0.04	97%
118	4.1	391.979	8.082	-6.717	0.04	97%
119	4.1	391.979	8.082	-6.717	0.04	97%
120	4.0	392.008	8.082	-6.714	0.03	97%



ATTACHMENT J

PUMPING TEST DATA FOR TW3

TW3-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 210064



DRAWDOWN DATA TW3


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	359.25	7.983	-4.53	0.00
1	358.863	7.983	-4.569	0.04
2	358.833	7.983	-4.573	0.04
3	358.774	7.983	-4.579	0.05
4	358.714	7.983	-4.585	0.05
5	358.506	7.983	-4.606	0.08
6	358.535	7.983	-4.603	0.07
7	358.416	7.983	-4.615	0.09
8	358.446	7.983	-4.612	0.08
9	358.357	7.983	-4.621	0.09
10	358.297	7.983	-4.627	0.10
11	358.297	7.983	-4.627	0.10
12	358.238	7.983	-4.633	0.10
13	358.208	7.983	-4.636	0.11
14	358.118	7.983	-4.645	0.11
15	358.148	7.983	-4.642	0.11
16	358.118	7.983	-4.645	0.11
17	358.029	7.983	-4.655	0.13
18	357.94	7.983	-4.664	0.13
19	357.91	7.983	-4.667	0.14
20	357.88	7.983	-4.67	0.14
21	357.91	7.983	-4.667	0.14
22	357.91	7.983	-4.667	0.14
23	357.91	7.983	-4.667	0.14
24	357.94	7.983	-4.664	0.13
25	357.94	7.983	-4.664	0.13
26	357.94	7.983	-4.664	0.13
27	357.94	7.983	-4.664	0.13
28	357.969	7.983	-4.661	0.13
29	357.94	7.983	-4.664	0.13
30	357.999	7.983	-4.658	0.13
31	357.969	7.983	-4.661	0.13
32	357.999	7.983	-4.658	0.13
33	357.969	7.983	-4.661	0.13
34	358.029	7.983	-4.655	0.13
35	357.91	7.983	-4.667	0.14
36	357.969	7.983	-4.661	0.13
37	357.969	7.983	-4.661	0.13
38	357.91	7.983	-4.667	0.14
39	357.88	7.983	-4.67	0.14
40	357.82	7.983	-4.676	0.15
41	357.85	7.983	-4.673	0.14
42	357.82	7.983	-4.676	0.15
43	357.791	7.983	-4.679	0.15
44	357.791	7.983	-4.679	0.15
45	357.791	7.983	-4.679	0.15
46	357.791	7.983	-4.679	0.15
47	357.82	7.983	-4.676	0.15
48	357.82	7.983	-4.676	0.15
49	357.672	7.983	-4.691	0.16
50	357.731	7.983	-4.685	0.15
51	357.701	7.983	-4.688	0.16
52	357.672	7.983	-4.691	0.16
53	357.642	7.983	-4.694	0.16
54	357.701	7.983	-4.688	0.16
55	357.642	7.983	-4.694	0.16
56	357.612	7.983	-4.697	0.17
57	357.672	7.983	-4.691	0.16
58	357.672	7.983	-4.691	0.16
59	357.463	7.983	-4.712	0.18
60	357.582	7.983	-4.7	0.17
61	357.582	7.983	-4.7	0.17
62	357.612	7.983	-4.697	0.17
63	357.582	7.983	-4.7	0.17
64	357.552	7.983	-4.703	0.17
65	357.552	7.983	-4.703	0.17
66	357.642	7.983	-4.694	0.16
67	357.523	7.983	-4.706	0.18
68	357.552	7.983	-4.703	0.17
69	357.582	7.983	-4.7	0.17
70	357.582	7.983	-4.7	0.17
71	357.582	7.983	-4.7	0.17
72	357.582	7.983	-4.7	0.17
73	357.523	7.983	-4.706	0.18
74	357.523	7.983	-4.706	0.18
75	357.523	7.983	-4.706	0.18
76	357.552	7.983	-4.703	0.17
77	357.552	7.983	-4.703	0.17
78	357.582	7.983	-4.7	0.17
79	357.582	7.983	-4.7	0.17
80	357.552	7.983	-4.703	0.17
81	357.344	7.983	-4.724	0.19
82	357.374	7.983	-4.721	0.19
83	357.403	7.983	-4.718	0.19
84	357.403	7.983	-4.718	0.19
85	357.284	7.983	-4.73	0.20

86	357.284	7.983	-4.73	0.20
87	357.314	7.983	-4.727	0.20
88	357.344	7.983	-4.724	0.19
89	357.284	7.983	-4.73	0.20
90	357.255	7.983	-4.733	0.20
91	357.284	7.983	-4.73	0.20
92	357.255	7.983	-4.733	0.20
93	357.255	7.983	-4.733	0.20
94	357.225	7.983	-4.736	0.21
95	357.284	7.983	-4.73	0.20
96	357.314	7.983	-4.727	0.20
97	357.374	7.983	-4.721	0.19
98	357.344	7.983	-4.724	0.19
99	357.344	7.983	-4.724	0.19
100	357.403	7.983	-4.718	0.19
101	357.374	7.983	-4.721	0.19
102	357.403	7.983	-4.718	0.19
103	357.344	7.983	-4.724	0.19
104	357.374	7.983	-4.721	0.19
105	357.374	7.983	-4.721	0.19
106	357.374	7.983	-4.721	0.19
107	357.403	7.983	-4.718	0.19
108	357.403	7.983	-4.718	0.19
109	357.403	7.983	-4.718	0.19
110	357.403	7.983	-4.718	0.19
111	357.433	7.983	-4.715	0.19
112	357.403	7.983	-4.718	0.19
113	357.433	7.983	-4.715	0.19
114	357.433	7.983	-4.715	0.19
115	357.433	7.983	-4.715	0.19
116	357.433	7.983	-4.715	0.19
117	357.463	7.983	-4.712	0.18
118	357.433	7.983	-4.715	0.19
119	357.403	7.983	-4.718	0.19
120	357.463	7.983	-4.712	0.18
121	357.523	7.983	-4.706	0.18
122	357.374	7.983	-4.721	0.19
123	357.523	7.983	-4.706	0.18
124	357.552	7.983	-4.703	0.17
125	357.433	7.983	-4.715	0.19
126	357.463	7.983	-4.712	0.18
127	357.433	7.983	-4.715	0.19
128	357.433	7.983	-4.715	0.19
129	357.374	7.983	-4.721	0.19
130	357.463	7.983	-4.712	0.18
131	357.403	7.983	-4.718	0.19
132	357.403	7.983	-4.718	0.19
133	357.374	7.983	-4.721	0.19
134	357.433	7.983	-4.715	0.19
135	357.403	7.983	-4.718	0.19
136	357.284	7.983	-4.73	0.20
137	357.403	7.983	-4.718	0.19
138	357.374	7.983	-4.721	0.19
139	357.374	7.983	-4.721	0.19
140	357.403	7.983	-4.718	0.19
141	357.374	7.983	-4.721	0.19
142	357.225	7.983	-4.736	0.21
143	357.284	7.983	-4.73	0.20
144	357.284	7.983	-4.73	0.20
145	357.344	7.983	-4.724	0.19
146	357.284	7.983	-4.73	0.20
147	357.314	7.983	-4.727	0.20
148	357.344	7.983	-4.724	0.19
149	357.403	7.983	-4.718	0.19
150	357.284	7.983	-4.73	0.20
151	357.284	7.983	-4.73	0.20
152	357.284	7.983	-4.73	0.20
153	357.195	7.983	-4.74	0.21
154	357.255	7.983	-4.733	0.20
155	357.225	7.983	-4.736	0.21
156	357.314	7.983	-4.727	0.20
157	357.314	7.983	-4.727	0.20
158	357.255	7.983	-4.733	0.20
159	357.284	7.983	-4.73	0.20
160	357.165	7.983	-4.743	0.21
161	357.195	7.983	-4.74	0.21
162	357.284	7.983	-4.73	0.20
163	357.225	7.983	-4.736	0.21
164	357.195	7.983	-4.74	0.21
165	357.225	7.983	-4.736	0.21
166	357.255	7.983	-4.733	0.20
167	357.195	7.983	-4.74	0.21
168	357.165	7.983	-4.743	0.21
169	357.165	7.983	-4.743	0.21
170	357.165	7.983	-4.743	0.21
171	357.225	7.983	-4.736	0.21
172	357.195	7.983	-4.74	0.21
173	357.255	7.983	-4.733	0.20
174	357.255	7.983	-4.733	0.20
175	357.284	7.983	-4.73	0.20
176	357.255	7.983	-4.733	0.20

177	357.195	7.983	-4.74	0.21
178	357.255	7.983	-4.733	0.20
179	357.255	7.983	-4.733	0.20
180	357.284	7.983	-4.73	0.20
181	357.255	7.983	-4.733	0.20
182	357.344	7.983	-4.724	0.19
183	357.344	7.983	-4.724	0.19
184	357.344	7.983	-4.724	0.19
185	357.284	7.983	-4.73	0.20
186	357.314	7.983	-4.727	0.20
187	357.284	7.983	-4.73	0.20
188	357.314	7.983	-4.727	0.20
189	357.314	7.983	-4.727	0.20
190	357.284	7.983	-4.73	0.20
191	357.284	7.983	-4.73	0.20
192	357.225	7.983	-4.736	0.21
193	357.344	7.983	-4.724	0.19
194	357.195	7.983	-4.74	0.21
195	357.314	7.983	-4.727	0.20
196	357.255	7.983	-4.733	0.20
197	357.284	7.983	-4.73	0.20
198	357.284	7.983	-4.73	0.20
199	357.225	7.983	-4.736	0.21
200	357.225	7.983	-4.736	0.21
201	357.255	7.983	-4.733	0.20
202	357.255	7.983	-4.733	0.20
203	357.284	7.983	-4.73	0.20
204	357.255	7.983	-4.733	0.20
205	357.314	7.983	-4.727	0.20
206	357.255	7.983	-4.733	0.20
207	357.225	7.983	-4.736	0.21
208	357.284	7.983	-4.73	0.20
209	357.314	7.983	-4.727	0.20
210	357.314	7.983	-4.727	0.20
211	357.284	7.983	-4.73	0.20
212	357.344	7.983	-4.724	0.19
213	357.344	7.983	-4.724	0.19
214	357.374	7.983	-4.721	0.19
215	357.374	7.983	-4.721	0.19
216	357.314	7.983	-4.727	0.20
217	357.344	7.983	-4.724	0.19
218	357.344	7.983	-4.724	0.19
219	357.314	7.983	-4.727	0.20
220	357.284	7.983	-4.73	0.20
221	357.374	7.983	-4.721	0.19
222	357.314	7.983	-4.727	0.20
223	357.374	7.983	-4.721	0.19
224	357.314	7.983	-4.727	0.20
225	357.225	7.983	-4.736	0.21
226	357.284	7.983	-4.73	0.20
227	357.255	7.983	-4.733	0.20
228	357.225	7.983	-4.736	0.21
229	357.165	7.983	-4.743	0.21
230	357.135	7.983	-4.746	0.22
231	357.165	7.983	-4.743	0.21
232	357.135	7.983	-4.746	0.22
233	357.135	7.983	-4.746	0.22
234	357.165	7.983	-4.743	0.21
235	357.165	7.983	-4.743	0.21
236	357.135	7.983	-4.746	0.22
237	357.106	7.983	-4.749	0.22
238	357.165	7.983	-4.743	0.21
239	357.046	7.983	-4.755	0.23
240	357.135	7.983	-4.746	0.22
241	357.106	7.983	-4.749	0.22
242	357.076	7.983	-4.752	0.22
243	357.195	7.983	-4.74	0.21
244	357.165	7.983	-4.743	0.21
245	357.165	7.983	-4.743	0.21
246	357.165	7.983	-4.743	0.21
247	357.165	7.983	-4.743	0.21
248	357.195	7.983	-4.74	0.21
249	357.135	7.983	-4.746	0.22
250	357.165	7.983	-4.743	0.21
251	357.195	7.983	-4.74	0.21
252	357.195	7.983	-4.74	0.21
253	357.016	7.983	-4.758	0.23
254	357.076	7.983	-4.752	0.22
255	357.106	7.983	-4.749	0.22
256	357.106	7.983	-4.749	0.22
257	357.165	7.983	-4.743	0.21
258	357.135	7.983	-4.746	0.22
259	357.106	7.983	-4.749	0.22
260	357.106	7.983	-4.749	0.22
261	357.135	7.983	-4.746	0.22
262	356.986	7.983	-4.761	0.23
263	357.016	7.983	-4.758	0.23
264	357.076	7.983	-4.752	0.22
265	356.986	7.983	-4.761	0.23
266	357.046	7.983	-4.755	0.23
267	357.016	7.983	-4.758	0.23

268	356.986	7.983	-4.761	0.23
269	357.046	7.983	-4.755	0.23
270	357.076	7.983	-4.752	0.22
271	357.016	7.983	-4.758	0.23
272	357.076	7.983	-4.752	0.22
273	357.106	7.983	-4.749	0.22
274	356.957	7.983	-4.764	0.23
275	357.135	7.983	-4.746	0.22
276	357.076	7.983	-4.752	0.22
277	357.165	7.983	-4.743	0.21
278	357.225	7.983	-4.736	0.21
279	357.165	7.983	-4.743	0.21
280	357.195	7.983	-4.74	0.21
281	357.225	7.983	-4.736	0.21
282	357.195	7.983	-4.74	0.21
283	357.255	7.983	-4.733	0.20
284	357.225	7.983	-4.736	0.21
285	357.195	7.983	-4.74	0.21
286	357.135	7.983	-4.746	0.22
287	357.135	7.983	-4.746	0.22
288	357.195	7.983	-4.74	0.21
289	357.046	7.983	-4.755	0.23
290	357.046	7.983	-4.755	0.23
291	357.106	7.983	-4.749	0.22
292	357.106	7.983	-4.749	0.22
293	357.106	7.983	-4.749	0.22
294	357.135	7.983	-4.746	0.22
295	357.165	7.983	-4.743	0.21
296	357.135	7.983	-4.746	0.22
297	357.135	7.983	-4.746	0.22
298	357.135	7.983	-4.746	0.22
299	357.165	7.983	-4.743	0.21
300	357.195	7.983	-4.74	0.21
301	357.165	7.983	-4.743	0.21
302	357.165	7.983	-4.743	0.21
303	357.165	7.983	-4.743	0.21
304	357.195	7.983	-4.74	0.21
305	357.165	7.983	-4.743	0.21
306	357.135	7.983	-4.746	0.22
307	357.135	7.983	-4.746	0.22
308	357.135	7.983	-4.746	0.22
309	357.195	7.983	-4.74	0.21
310	357.165	7.983	-4.743	0.21
311	357.165	7.983	-4.743	0.21
312	357.135	7.983	-4.746	0.22
313	357.106	7.983	-4.749	0.22
314	357.076	7.983	-4.752	0.22
315	357.046	7.983	-4.755	0.23
316	357.046	7.983	-4.755	0.23
317	356.957	7.983	-4.764	0.23
318	356.927	7.983	-4.767	0.24
319	356.927	7.983	-4.767	0.24
320	356.986	7.983	-4.761	0.23
321	356.957	7.983	-4.764	0.23
322	356.927	7.983	-4.767	0.24
323	356.897	7.983	-4.77	0.24
324	356.867	7.983	-4.773	0.24
325	356.838	7.983	-4.776	0.25
326	356.897	7.983	-4.77	0.24
327	356.927	7.983	-4.767	0.24
328	356.897	7.983	-4.77	0.24
329	356.927	7.983	-4.767	0.24
330	357.016	7.983	-4.758	0.23
331	356.986	7.983	-4.761	0.23
332	356.897	7.983	-4.77	0.24
333	356.897	7.983	-4.77	0.24
334	356.897	7.983	-4.77	0.24
335	356.897	7.983	-4.77	0.24
336	356.927	7.983	-4.767	0.24
337	356.897	7.983	-4.77	0.24
338	356.957	7.983	-4.764	0.23
339	356.897	7.983	-4.77	0.24
340	356.897	7.983	-4.77	0.24
341	356.867	7.983	-4.773	0.24
342	356.897	7.983	-4.77	0.24
343	356.927	7.983	-4.767	0.24
344	356.957	7.983	-4.764	0.23
345	356.897	7.983	-4.77	0.24
346	356.838	7.983	-4.776	0.25
347	356.867	7.983	-4.773	0.24
348	356.867	7.983	-4.773	0.24
349	356.778	7.983	-4.782	0.25
350	356.808	7.983	-4.779	0.25
351	356.838	7.983	-4.776	0.25
352	356.808	7.983	-4.779	0.25
353	356.838	7.983	-4.776	0.25
354	356.927	7.983	-4.767	0.24
355	356.927	7.983	-4.767	0.24
356	356.927	7.983	-4.767	0.24
357	356.986	7.983	-4.761	0.23
358	356.986	7.983	-4.761	0.23

TW3- WELL RECOVERY VS. TIME - KOLLAARD FILE 210064



RECOVERY DATA TW-3

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	359.0	357.195	7.983	-4.74	95.24	
2	180.0	357.344	7.983	-4.724	95.22	
3	120.3	357.433	7.983	-4.715	0.19	12%
4	90.5	357.493	7.983	-4.709	0.18	15%
5	72.6	357.582	7.983	-4.7	0.17	19%
6	60.7	357.672	7.983	-4.691	0.16	23%
7	52.1	357.731	7.983	-4.685	0.15	26%
8	45.8	357.761	7.983	-4.682	0.15	28%
9	40.8	357.82	7.983	-4.676	0.15	30%
10	36.8	357.85	7.983	-4.673	0.14	32%
11	33.5	357.94	7.983	-4.664	0.13	36%
12	30.8	357.88	7.983	-4.67	0.14	33%
13	28.5	357.94	7.983	-4.664	0.13	36%
14	26.6	357.969	7.983	-4.661	0.13	38%
15	24.9	357.999	7.983	-4.658	0.13	39%
16	23.4	358.089	7.983	-4.648	0.12	44%
17	22.1	358.059	7.983	-4.651	0.12	42%
18	20.9	358.089	7.983	-4.648	0.12	44%
19	19.8	358.089	7.983	-4.648	0.12	44%
20	18.9	358.267	7.983	-4.63	0.10	52%
21	18.0	358.178	7.983	-4.639	0.11	48%
22	17.3	358.238	7.983	-4.633	0.10	51%
23	16.6	357.94	7.983	-4.664	0.13	36%
24	15.9	358.297	7.983	-4.627	0.10	54%
25	15.3	358.327	7.983	-4.624	0.09	55%
26	14.8	358.357	7.983	-4.621	0.09	57%
27	14.3	358.357	7.983	-4.621	0.09	57%
28	13.8	358.327	7.983	-4.624	0.09	55%
29	13.3	358.357	7.983	-4.621	0.09	57%
30	12.9	358.327	7.983	-4.624	0.09	55%
31	12.5	358.416	7.983	-4.615	0.09	60%
32	12.2	358.446	7.983	-4.612	0.08	61%
33	11.8	358.476	7.983	-4.609	0.08	62%
34	11.5	358.476	7.983	-4.609	0.08	62%
35	11.2	358.446	7.983	-4.612	0.08	61%
36	10.9	358.506	7.983	-4.606	0.08	64%
37	10.7	358.565	7.983	-4.6	0.07	67%
38	10.4	358.565	7.983	-4.6	0.07	67%
39	10.2	358.595	7.983	-4.597	0.07	68%
40	10.0	358.595	7.983	-4.597	0.07	68%
41	9.7	358.625	7.983	-4.594	0.06	70%
42	9.5	358.625	7.983	-4.594	0.06	70%
43	9.3	358.625	7.983	-4.594	0.06	70%
44	9.1	358.655	7.983	-4.591	0.06	71%
45	9.0	358.684	7.983	-4.588	0.06	72%
46	8.8	358.684	7.983	-4.588	0.06	72%

47	8.6	358.655	7.983	-4.591	0.06	71%
48	8.5	358.655	7.983	-4.591	0.06	71%
49	8.3	358.714	7.983	-4.585	0.05	74%
50	8.2	358.714	7.983	-4.585	0.05	74%
51	8.0	358.714	7.983	-4.585	0.05	74%
52	7.9	358.744	7.983	-4.582	0.05	75%
53	7.8	358.744	7.983	-4.582	0.05	75%
54	7.6	358.774	7.983	-4.579	0.05	77%
55	7.5	358.774	7.983	-4.579	0.05	77%
56	7.4	358.684	7.983	-4.588	0.06	72%
57	7.3	358.655	7.983	-4.591	0.06	71%
58	7.2	358.655	7.983	-4.591	0.06	71%
59	7.1	358.684	7.983	-4.588	0.06	72%
60	7.0	358.595	7.983	-4.597	0.07	68%
61	6.9	358.535	7.983	-4.603	0.07	65%
62	6.8	358.595	7.983	-4.597	0.07	68%
63	6.7	358.595	7.983	-4.597	0.07	68%
64	6.6	358.625	7.983	-4.594	0.06	70%
65	6.5	358.655	7.983	-4.591	0.06	71%
66	6.4	358.655	7.983	-4.591	0.06	71%
67	6.3	358.714	7.983	-4.585	0.05	74%
68	6.3	358.714	7.983	-4.585	0.05	74%
69	6.2	358.714	7.983	-4.585	0.05	74%
70	6.1	358.714	7.983	-4.585	0.05	74%
71	6.0	358.714	7.983	-4.585	0.05	74%
72	6.0	358.744	7.983	-4.582	0.05	75%
73	5.9	358.744	7.983	-4.582	0.05	75%
74	5.8	358.744	7.983	-4.582	0.05	75%
75	5.8	358.803	7.983	-4.576	0.05	78%
76	5.7	358.803	7.983	-4.576	0.05	78%
77	5.6	358.803	7.983	-4.576	0.05	78%
78	5.6	358.833	7.983	-4.573	0.04	80%
79	5.5	358.833	7.983	-4.573	0.04	80%
80	5.5	358.863	7.983	-4.569	0.04	81%
81	5.4	358.893	7.983	-4.566	0.04	83%
82	5.4	358.833	7.983	-4.573	0.04	80%
83	5.3	358.863	7.983	-4.569	0.04	81%
84	5.3	358.893	7.983	-4.566	0.04	83%
85	5.2	358.893	7.983	-4.566	0.04	83%
86	5.2	358.893	7.983	-4.566	0.04	83%
87	5.1	358.893	7.983	-4.566	0.04	83%
88	5.1	358.923	7.983	-4.563	0.03	84%
89	5.0	358.863	7.983	-4.569	0.04	81%
90	5.0	358.863	7.983	-4.569	0.04	81%
91	4.9	358.893	7.983	-4.566	0.04	83%
92	4.9	358.923	7.983	-4.563	0.03	84%
93	4.8	358.893	7.983	-4.566	0.04	83%
94	4.8	358.923	7.983	-4.563	0.03	84%
95	4.8	358.952	7.983	-4.56	0.03	86%
96	4.7	358.923	7.983	-4.563	0.03	84%

97	4.7	358.982	7.983	-4.557	0.03	87%
98	4.7	359.012	7.983	-4.554	0.02	89%
99	4.6	358.982	7.983	-4.557	0.03	87%
100	4.6	359.012	7.983	-4.554	0.02	89%
101	4.5	359.072	7.983	-4.548	0.02	91%
102	4.5	359.042	7.983	-4.551	0.02	90%
103	4.5	359.042	7.983	-4.551	0.02	90%
104	4.4	358.982	7.983	-4.557	0.03	87%
105	4.4	359.012	7.983	-4.554	0.02	89%
106	4.4	359.042	7.983	-4.551	0.02	90%
107	4.3	359.042	7.983	-4.551	0.02	90%
108	4.3	359.012	7.983	-4.554	0.02	89%
109	4.3	359.072	7.983	-4.548	0.02	91%
110	4.3	359.072	7.983	-4.548	0.02	91%
111	4.2	359.042	7.983	-4.551	0.02	90%
112	4.2	359.012	7.983	-4.554	0.02	89%
113	4.2	359.042	7.983	-4.551	0.02	90%
114	4.1	359.072	7.983	-4.548	0.02	91%
115	4.1	359.101	7.983	-4.545	0.01	93%
116	4.1	359.042	7.983	-4.551	0.02	90%
117	4.1	359.072	7.983	-4.548	0.02	91%
118	4.0	359.072	7.983	-4.548	0.02	91%
119	4.0	359.072	7.983	-4.548	0.02	91%
120	4.0	359.072	7.983	-4.548	0.02	91%
121	4.0	359.042	7.983	-4.551	0.02	90%
122	3.9	359.072	7.983	-4.548	0.02	91%
123	3.9	359.072	7.983	-4.548	0.02	91%
124	3.9	359.072	7.983	-4.548	0.02	91%
125	3.9	359.042	7.983	-4.551	0.02	90%
126	3.8	359.012	7.983	-4.554	0.02	89%
127	3.8	359.012	7.983	-4.554	0.02	89%
128	3.8	359.012	7.983	-4.554	0.02	89%
129	3.8	358.952	7.983	-4.56	0.03	86%
130	3.8	358.952	7.983	-4.56	0.03	86%
131	3.7	358.982	7.983	-4.557	0.03	87%
132	3.7	358.952	7.983	-4.56	0.03	86%
133	3.7	358.982	7.983	-4.557	0.03	87%
134	3.7	358.863	7.983	-4.569	0.04	81%
135	3.7	358.923	7.983	-4.563	0.03	84%
136	3.6	358.952	7.983	-4.56	0.03	86%
137	3.6	358.952	7.983	-4.56	0.03	86%
138	3.6	358.893	7.983	-4.566	0.04	83%
139	3.6	358.923	7.983	-4.563	0.03	84%
140	3.6	358.923	7.983	-4.563	0.03	84%
141	3.5	358.923	7.983	-4.563	0.03	84%
142	3.5	358.923	7.983	-4.563	0.03	84%
143	3.5	358.923	7.983	-4.563	0.03	84%
144	3.5	358.923	7.983	-4.563	0.03	84%
145	3.5	358.923	7.983	-4.563	0.03	84%
146	3.5	358.923	7.983	-4.563	0.03	84%

147	3.4	358.923	7.983	-4.563	0.03	84%
148	3.4	358.923	7.983	-4.563	0.03	84%
149	3.4	358.952	7.983	-4.56	0.03	86%
150	3.4	358.923	7.983	-4.563	0.03	84%
151	3.4	358.833	7.983	-4.573	0.04	80%
152	3.4	358.952	7.983	-4.56	0.03	86%
153	3.3	358.952	7.983	-4.56	0.03	86%
154	3.3	358.952	7.983	-4.56	0.03	86%
155	3.3	358.833	7.983	-4.573	0.04	80%
156	3.3	358.923	7.983	-4.563	0.03	84%
157	3.3	358.923	7.983	-4.563	0.03	84%
158	3.3	358.923	7.983	-4.563	0.03	84%
159	3.3	358.833	7.983	-4.573	0.04	80%
160	3.2	358.833	7.983	-4.573	0.04	80%
161	3.2	358.893	7.983	-4.566	0.04	83%
162	3.2	358.923	7.983	-4.563	0.03	84%
163	3.2	358.952	7.983	-4.56	0.03	86%
164	3.2	358.803	7.983	-4.576	0.05	78%
165	3.2	358.923	7.983	-4.563	0.03	84%
166	3.2	358.952	7.983	-4.56	0.03	86%
167	3.1	358.923	7.983	-4.563	0.03	84%
168	3.1	358.982	7.983	-4.557	0.03	87%
169	3.1	358.893	7.983	-4.566	0.04	83%
170	3.1	358.982	7.983	-4.557	0.03	87%
171	3.1	358.982	7.983	-4.557	0.03	87%
172	3.1	358.982	7.983	-4.557	0.03	87%
173	3.1	358.923	7.983	-4.563	0.03	84%
174	3.1	358.952	7.983	-4.56	0.03	86%
175	3.0	358.982	7.983	-4.557	0.03	87%
176	3.0	359.012	7.983	-4.554	0.02	89%
177	3.0	358.982	7.983	-4.557	0.03	87%
178	3.0	358.982	7.983	-4.557	0.03	87%
179	3.0	358.982	7.983	-4.557	0.03	87%
180	3.0	358.952	7.983	-4.56	0.03	86%
181	3.0	358.863	7.983	-4.569	0.04	81%
182	3.0	358.893	7.983	-4.566	0.04	83%
183	3.0	358.923	7.983	-4.563	0.03	84%
184	2.9	358.982	7.983	-4.557	0.03	87%
185	2.9	359.042	7.983	-4.551	0.02	90%
186	2.9	359.042	7.983	-4.551	0.02	90%
187	2.9	359.042	7.983	-4.551	0.02	90%
188	2.9	359.042	7.983	-4.551	0.02	90%
189	2.9	359.042	7.983	-4.551	0.02	90%
190	2.9	359.012	7.983	-4.554	0.02	89%
191	2.9	359.072	7.983	-4.548	0.02	91%
192	2.9	359.101	7.983	-4.545	0.01	93%
193	2.9	359.072	7.983	-4.548	0.02	91%
194	2.8	359.072	7.983	-4.548	0.02	91%
195	2.8	359.101	7.983	-4.545	0.01	93%
196	2.8	359.101	7.983	-4.545	0.01	93%

197	2.8	359.131	7.983	-4.542	0.01	94%
198	2.8	359.131	7.983	-4.542	0.01	94%
199	2.8	359.042	7.983	-4.551	0.02	90%
200	2.8	359.042	7.983	-4.551	0.02	90%
201	2.8	359.042	7.983	-4.551	0.02	90%
202	2.8	359.101	7.983	-4.545	0.01	93%
203	2.8	359.072	7.983	-4.548	0.02	91%
204	2.8	359.072	7.983	-4.548	0.02	91%
205	2.7	359.072	7.983	-4.548	0.02	91%
206	2.7	359.042	7.983	-4.551	0.02	90%
207	2.7	359.042	7.983	-4.551	0.02	90%
208	2.7	359.042	7.983	-4.551	0.02	90%
209	2.7	358.774	7.983	-4.579	0.05	77%
210	2.7	358.982	7.983	-4.557	0.03	87%
211	2.7	359.012	7.983	-4.554	0.02	89%
212	2.7	359.012	7.983	-4.554	0.02	89%
213	2.7	358.982	7.983	-4.557	0.03	87%
214	2.7	358.982	7.983	-4.557	0.03	87%
215	2.7	358.923	7.983	-4.563	0.03	84%
216	2.7	358.893	7.983	-4.566	0.04	83%
217	2.6	358.833	7.983	-4.573	0.04	80%
218	2.6	358.863	7.983	-4.569	0.04	81%
219	2.6	358.893	7.983	-4.566	0.04	83%
220	2.6	358.893	7.983	-4.566	0.04	83%
221	2.6	358.893	7.983	-4.566	0.04	83%
222	2.6	358.923	7.983	-4.563	0.03	84%
223	2.6	358.893	7.983	-4.566	0.04	83%
224	2.6	358.893	7.983	-4.566	0.04	83%
225	2.6	358.774	7.983	-4.579	0.05	77%
226	2.6	358.893	7.983	-4.566	0.04	83%
227	2.6	358.893	7.983	-4.566	0.04	83%
228	2.6	358.863	7.983	-4.569	0.04	81%
229	2.6	358.833	7.983	-4.573	0.04	80%
230	2.6	358.863	7.983	-4.569	0.04	81%
231	2.5	358.863	7.983	-4.569	0.04	81%
232	2.5	358.893	7.983	-4.566	0.04	83%
233	2.5	358.863	7.983	-4.569	0.04	81%
234	2.5	358.863	7.983	-4.569	0.04	81%
235	2.5	358.863	7.983	-4.569	0.04	81%
236	2.5	358.893	7.983	-4.566	0.04	83%
237	2.5	358.863	7.983	-4.569	0.04	81%
238	2.5	358.863	7.983	-4.569	0.04	81%
239	2.5	358.893	7.983	-4.566	0.04	83%
240	2.5	358.923	7.983	-4.563	0.03	84%
241	2.5	358.952	7.983	-4.56	0.03	86%
242	2.5	358.923	7.983	-4.563	0.03	84%
243	2.5	358.952	7.983	-4.56	0.03	86%
244	2.5	358.982	7.983	-4.557	0.03	87%
245	2.5	358.982	7.983	-4.557	0.03	87%
246	2.5	358.952	7.983	-4.56	0.03	86%

247	2.4	359.012	7.983	-4.554	0.02	89%
248	2.4	359.012	7.983	-4.554	0.02	89%
249	2.4	359.042	7.983	-4.551	0.02	90%
250	2.4	359.042	7.983	-4.551	0.02	90%
251	2.4	359.101	7.983	-4.545	0.01	93%
252	2.4	359.042	7.983	-4.551	0.02	90%
253	2.4	359.131	7.983	-4.542	0.01	94%
254	2.4	359.101	7.983	-4.545	0.01	93%
255	2.4	358.863	7.983	-4.569	0.04	81%
256	2.4	358.982	7.983	-4.557	0.03	87%
257	2.4	358.952	7.983	-4.56	0.03	86%
258	2.4	358.952	7.983	-4.56	0.03	86%
259	2.4	358.923	7.983	-4.563	0.03	84%
260	2.4	358.923	7.983	-4.563	0.03	84%
261	2.4	358.893	7.983	-4.566	0.04	83%
262	2.4	358.952	7.983	-4.56	0.03	86%
263	2.4	358.923	7.983	-4.563	0.03	84%
264	2.4	358.893	7.983	-4.566	0.04	83%
265	2.4	358.923	7.983	-4.563	0.03	84%
266	2.3	358.923	7.983	-4.563	0.03	84%
267	2.3	358.952	7.983	-4.56	0.03	86%
268	2.3	358.923	7.983	-4.563	0.03	84%
269	2.3	358.923	7.983	-4.563	0.03	84%
270	2.3	358.982	7.983	-4.557	0.03	87%
271	2.3	359.012	7.983	-4.554	0.02	89%
272	2.3	358.863	7.983	-4.569	0.04	81%
273	2.3	358.923	7.983	-4.563	0.03	84%
274	2.3	358.952	7.983	-4.56	0.03	86%
275	2.3	358.952	7.983	-4.56	0.03	86%
276	2.3	358.952	7.983	-4.56	0.03	86%
277	2.3	358.893	7.983	-4.566	0.04	83%
278	2.3	358.982	7.983	-4.557	0.03	87%
279	2.3	359.012	7.983	-4.554	0.02	89%
280	2.3	358.982	7.983	-4.557	0.03	87%
281	2.3	358.982	7.983	-4.557	0.03	87%
282	2.3	358.893	7.983	-4.566	0.04	83%
283	2.3	358.863	7.983	-4.569	0.04	81%
284	2.3	358.982	7.983	-4.557	0.03	87%
285	2.3	358.982	7.983	-4.557	0.03	87%
286	2.3	358.982	7.983	-4.557	0.03	87%
287	2.2	359.012	7.983	-4.554	0.02	89%
288	2.2	359.012	7.983	-4.554	0.02	89%
289	2.2	358.952	7.983	-4.56	0.03	86%
290	2.2	358.952	7.983	-4.56	0.03	86%
291	2.2	358.952	7.983	-4.56	0.03	86%
292	2.2	358.863	7.983	-4.569	0.04	81%
293	2.2	358.863	7.983	-4.569	0.04	81%
294	2.2	358.893	7.983	-4.566	0.04	83%
295	2.2	358.893	7.983	-4.566	0.04	83%
296	2.2	358.952	7.983	-4.56	0.03	86%

297	2.2	358.923	7.983	-4.563	0.03	84%
298	2.2	358.833	7.983	-4.573	0.04	80%
299	2.2	358.684	7.983	-4.588	0.06	72%
300	2.2	358.744	7.983	-4.582	0.05	75%
301	2.2	358.714	7.983	-4.585	0.05	74%
302	2.2	358.446	7.983	-4.612	0.08	61%
303	2.2	358.506	7.983	-4.606	0.08	64%
304	2.2	358.625	7.983	-4.594	0.06	70%
305	2.2	358.655	7.983	-4.591	0.06	71%
306	2.2	358.595	7.983	-4.597	0.07	68%
307	2.2	358.595	7.983	-4.597	0.07	68%
308	2.2	358.595	7.983	-4.597	0.07	68%
309	2.2	358.625	7.983	-4.594	0.06	70%
310	2.2	358.625	7.983	-4.594	0.06	70%
311	2.2	358.655	7.983	-4.591	0.06	71%
312	2.1	358.655	7.983	-4.591	0.06	71%
313	2.1	358.684	7.983	-4.588	0.06	72%
314	2.1	358.655	7.983	-4.591	0.06	71%
315	2.1	358.684	7.983	-4.588	0.06	72%
316	2.1	358.684	7.983	-4.588	0.06	72%
317	2.1	358.714	7.983	-4.585	0.05	74%
318	2.1	358.714	7.983	-4.585	0.05	74%
319	2.1	358.595	7.983	-4.597	0.07	68%
320	2.1	358.506	7.983	-4.606	0.08	64%
321	2.1	358.595	7.983	-4.597	0.07	68%
322	2.1	358.595	7.983	-4.597	0.07	68%
323	2.1	358.595	7.983	-4.597	0.07	68%
324	2.1	358.595	7.983	-4.597	0.07	68%
325	2.1	358.625	7.983	-4.594	0.06	70%
326	2.1	358.655	7.983	-4.591	0.06	71%
327	2.1	358.655	7.983	-4.591	0.06	71%
328	2.1	358.655	7.983	-4.591	0.06	71%
329	2.1	358.535	7.983	-4.603	0.07	65%
330	2.1	358.625	7.983	-4.594	0.06	70%
331	2.1	358.684	7.983	-4.588	0.06	72%
332	2.1	358.655	7.983	-4.591	0.06	71%
333	2.1	358.714	7.983	-4.585	0.05	74%
334	2.1	358.684	7.983	-4.588	0.06	72%
335	2.1	358.625	7.983	-4.594	0.06	70%
336	2.1	358.506	7.983	-4.606	0.08	64%
337	2.1	358.565	7.983	-4.6	0.07	67%
338	2.1	358.506	7.983	-4.606	0.08	64%
339	2.1	358.565	7.983	-4.6	0.07	67%
340	2.1	358.565	7.983	-4.6	0.07	67%
341	2.0	358.625	7.983	-4.594	0.06	70%
342	2.0	358.684	7.983	-4.588	0.06	72%
343	2.0	358.714	7.983	-4.585	0.05	74%
344	2.0	358.684	7.983	-4.588	0.06	72%
345	2.0	358.714	7.983	-4.585	0.05	74%
346	2.0	358.744	7.983	-4.582	0.05	75%

347	2.0	358.744	7.983	-4.582	0.05	75%
348	2.0	358.714	7.983	-4.585	0.05	74%
349	2.0	358.684	7.983	-4.588	0.06	72%
350	2.0	358.714	7.983	-4.585	0.05	74%
351	2.0	358.714	7.983	-4.585	0.05	74%
352	2.0	358.595	7.983	-4.597	0.07	68%
353	2.0	358.655	7.983	-4.591	0.06	71%
354	2.0	358.625	7.983	-4.594	0.06	70%
355	2.0	358.655	7.983	-4.591	0.06	71%
356	2.0	358.684	7.983	-4.588	0.06	72%
357	2.0	358.684	7.983	-4.588	0.06	72%
358	2.0	358.684	7.983	-4.588	0.06	72%
359	2.0	358.744	7.983	-4.582	0.05	75%
360	2.0	358.714	7.983	-4.585	0.05	74%
361	2.0	358.774	7.983	-4.579	0.05	77%
362	2.0	358.714	7.983	-4.585	0.05	74%
363	2.0	358.714	7.983	-4.585	0.05	74%
364	2.0	358.744	7.983	-4.582	0.05	75%
365	2.0	358.744	7.983	-4.582	0.05	75%
366	2.0	358.714	7.983	-4.585	0.05	74%
367	2.0	358.714	7.983	-4.585	0.05	74%
368	2.0	358.744	7.983	-4.582	0.05	75%
369	2.0	358.655	7.983	-4.591	0.06	71%
370	2.0	358.655	7.983	-4.591	0.06	71%
371	2.0	358.595	7.983	-4.597	0.07	68%
372	2.0	358.625	7.983	-4.594	0.06	70%
373	2.0	358.684	7.983	-4.588	0.06	72%
374	2.0	358.684	7.983	-4.588	0.06	72%
375	2.0	358.625	7.983	-4.594	0.06	70%
376	2.0	358.655	7.983	-4.591	0.06	71%
377	1.9	358.565	7.983	-4.6	0.07	67%
378	1.9	358.595	7.983	-4.597	0.07	68%
379	1.9	358.595	7.983	-4.597	0.07	68%
380	1.9	358.565	7.983	-4.6	0.07	67%
381	1.9	358.684	7.983	-4.588	0.06	72%
382	1.9	358.655	7.983	-4.591	0.06	71%
383	1.9	358.714	7.983	-4.585	0.05	74%
384	1.9	358.655	7.983	-4.591	0.06	71%
385	1.9	358.714	7.983	-4.585	0.05	74%
386	1.9	358.684	7.983	-4.588	0.06	72%
387	1.9	358.714	7.983	-4.585	0.05	74%
388	1.9	358.684	7.983	-4.588	0.06	72%
389	1.9	358.714	7.983	-4.585	0.05	74%
390	1.9	358.714	7.983	-4.585	0.05	74%
391	1.9	358.744	7.983	-4.582	0.05	75%
392	1.9	358.744	7.983	-4.582	0.05	75%
393	1.9	358.774	7.983	-4.579	0.05	77%
394	1.9	358.744	7.983	-4.582	0.05	75%
395	1.9	358.774	7.983	-4.579	0.05	77%
396	1.9	358.774	7.983	-4.579	0.05	77%


397	1.9	358.744	7.983	-4.582	0.05	75%
398	1.9	358.774	7.983	-4.579	0.05	77%
399	1.9	358.774	7.983	-4.579	0.05	77%
400	1.9	358.774	7.983	-4.579	0.05	77%
401	1.9	358.684	7.983	-4.588	0.06	72%
402	1.9	358.744	7.983	-4.582	0.05	75%
403	1.9	358.774	7.983	-4.579	0.05	77%
404	1.9	358.774	7.983	-4.579	0.05	77%
405	1.9	358.774	7.983	-4.579	0.05	77%
406	1.9	358.684	7.983	-4.588	0.06	72%
407	1.9	358.714	7.983	-4.585	0.05	74%
408	1.9	358.744	7.983	-4.582	0.05	75%
409	1.9	358.774	7.983	-4.579	0.05	77%
410	1.9	358.744	7.983	-4.582	0.05	75%
411	1.9	358.774	7.983	-4.579	0.05	77%
412	1.9	358.744	7.983	-4.582	0.05	75%
413	1.9	358.803	7.983	-4.576	0.05	78%
414	1.9	358.833	7.983	-4.573	0.04	80%
415	1.9	358.863	7.983	-4.569	0.04	81%
416	1.9	358.863	7.983	-4.569	0.04	81%
417	1.9	358.893	7.983	-4.566	0.04	83%
418	1.9	358.863	7.983	-4.569	0.04	81%
419	1.9	358.893	7.983	-4.566	0.04	83%
420	1.9	358.923	7.983	-4.563	0.03	84%
421	1.9	358.893	7.983	-4.566	0.04	83%
422	1.8	358.893	7.983	-4.566	0.04	83%
423	1.8	358.893	7.983	-4.566	0.04	83%
424	1.8	358.982	7.983	-4.557	0.03	87%
425	1.8	358.982	7.983	-4.557	0.03	87%
426	1.8	358.982	7.983	-4.557	0.03	87%
427	1.8	359.012	7.983	-4.554	0.02	89%
428	1.8	359.012	7.983	-4.554	0.02	89%
429	1.8	359.042	7.983	-4.551	0.02	90%
430	1.8	359.012	7.983	-4.554	0.02	89%
431	1.8	359.042	7.983	-4.551	0.02	90%
432	1.8	359.072	7.983	-4.548	0.02	91%
433	1.8	359.042	7.983	-4.551	0.02	90%
434	1.8	359.072	7.983	-4.548	0.02	91%
435	1.8	359.131	7.983	-4.542	0.01	94%
436	1.8	359.101	7.983	-4.545	0.01	93%
437	1.8	359.072	7.983	-4.548	0.02	91%
438	1.8	359.161	7.983	-4.539	0.01	96%
439	1.8	359.131	7.983	-4.542	0.01	94%
440	1.8	359.131	7.983	-4.542	0.01	94%
441	1.8	359.161	7.983	-4.539	0.01	96%
442	1.8	359.191	7.983	-4.536	0.01	97%
443	1.8	359.191	7.983	-4.536	0.01	97%
444	1.8	359.191	7.983	-4.536	0.01	97%
445	1.8	359.25	7.983	-4.53	0.00	100%




ATTACHMENT K

OBSERVATION WELL DATA USING PRESSURE TRANSDUCER LOGGERS

Drawdown vs. Time in Observation Well During Pumping Test for TW2



Drawdown vs. Time in Observation Well During Pumping Test for TW1



Attachment L

Groundwater Velocity and Lateral and Vertical Gradients

$$\frac{Q}{A} = K \frac{dh}{dL}$$

where Q/A = darcy flux, d

K, saturated hydraulic conductivity, in m/s

dh, change in head between two standpipes

dL, lateral distance between two standpipes

Linear velocity, V = d/n where n is the porosity of the soil

K 2.6E-04 m/s

n 0.3

Travel time = dL / V

Start Point	End Point	Distance (dL) metres	Change in head (dh) metres * February 27, 2024	Darcy, flux, Q/A m3/m2/s	Groundwater velocity, v m/s	Estimated Travel Time days	Estimated Travel Time years
BH1	BH8	61	1.25	5.3E-06	1.8E-05	39.8	0.109
BH1	BH5	125	0.97	2.0E-06	6.7E-06	215.1	0.589
BH9	BH3	56	0.92	4.3E-06	1.4E-05	45.5	0.125
BH1	BH3	113	1.96	4.5E-06	1.5E-05	87.0	0.238
BH1	BH9	64	1.04	4.2E-06	1.4E-05	52.6	0.144
BH1	BH7	4.5	0.03	1.7E-06	5.8E-06	9.0	0.025

Average lateral gw velocity (m/day)

1.2 m/day