PROMERITA westbank BC HOUSING ZGF

EAST VILLAGE

3

EAST 3: 1168, 1172 & 1180 East Hastings Street
Rezoning, April 2024

Revision 02: September 2024

3

TABLE OF CONTENTS

A INTRODUCTION

East Village Overview

East Village Overview 6
Purpose-built and Equitable Housing 7

Policy Enquiry Process Criteria Alignment

Project Goals 8
Urban Design Goals 9
BC Housing Partnership. 10

B URBAN DESIGN RATIONALE

The Hastings Street Corridor

A History of Community 13
Community Continuum: East Village 14
Location 15
Responding to Axial Shifts along Hastings. 16
Policy Area - Urban Design 17
Neighbourhood - Urban Design 18

C EAST 3 PROJECT

Site

Location 21
Current Use 22
Street Elevations 23
Site Photos 23
Contextual Aerial View 24
Future Contextual Aerial View 26

Zoning Analysis + Review Criteria

Applicable Policies & Guidelines. 28
Variance Rationale 28
Project Information 29
1. Housing. 30
2. Jobs. 31
3. Cultural, Social, and other City Serving Amenities. 32
4. Energy and Greenhouse Gases. 33
5. Neighbourhoods 34

Proposal

East 3 Project Overview. 36
Key Design Moves 37
Hastings Block Typology 39
Facade Strategy 40
Podium Strategy. 41
Architectural Expression 42
Form of Development 44
Livability 46
Amenities 48
Sustainable Transport 50
Sustainability. 51
CPTED Measures 52

Drawing Sets

Development Data. 54
Site Survey 58
Building Grades Survey 59
Context Site Plan 60
Site Plan 61
Streetscape Elevations. 62
Shadow Study. 65
Floor Plans 66
Section East/West 74
Section North/South 75
Elevations 76
Materials 78

This document has been digitally certified with digital certificate and encryption technology authorized by the Architectural Institute of BC and the Engineers and Geoscientists BC. The authoritative original has been transmitted to you in digital form. Printed versions can only be relied upon as a true copy of the original when supplied by the architect, bearing the professional seal and digital certificate.

This page intentionally left blank



A INTRODUCTION

East Village Overview

East Village Overview 6
Purpose-built and Equitable Housing 7

Policy Enquiry Process Criteria Alignment

Project Goals 8
Urban Design Goals 9
BC Housing Partnership. 10

East Village Overview

924 **TOTAL HOMES**

767 **SECURED PURPOSE-BUILT RENTAL**
EAST 1 - 382 units
EAST 2 - 385 units

157 **SENIOR SOCIAL HOUSING**
EAST 3 - 157 Social Housing Units
(Includes 36 Replacement SRA units)

12,925 **SF STREET LEVEL COMMERCIAL**

2,289 **SF STREET LEVEL SOCIAL ENTERPRISE**

20.47% **SOCIAL HOUSING**
STANDALONE LOW-INCOME HOUSING FOR SENIORS
20.47% of total rental units that are provided on East 1 & East 2 (767 units) would be dedicated Social Housing and these units would be provided on the East 3 site. Westbank and Promerita have transfered the ownership of the East 3 Land to BC Housing for the construction of these 157 standalone Social Housing units for Seniors on the East 3 Site.

ZGF, on behalf of Promerita and Westbank, have assembled a multi-disciplinary team that is community minded and strives to deliver critically needed secured purpose-built rental, and social housing to the Downtown Eastside.

The development proposal is comprised of three residential buildings with commercial space at grade. The combined proposal seeks to add secured purpose-built rental homes, and social housing units that achieve high levels of quality and livability and that meet the needs of the tenants and the community.

Following the Downtown Eastside Guidelines, the proposal seeks to rezone all 3 properties under a single application to create CD-1 Comprehensive Development.

- East 1: 1030, 1040, 1050, 1060 & 1070 East Hastings Street, Vancouver, BC
- East 2: 1115 & 1127 East Hastings Street, Vancouver, BC
- East 3: 1168, 1172 & 1180 East Hastings Street, Vancouver, BC.



Purpose–built and Equitable Housing

We are seeking to process the rezoning of all three East Village properties in a single application allowing us to concentrate the most affordable homes into a single building (East 3).

East 1 and East 2, to be owned by Westbank/Promerita as purpose-built market rental units.

Westbank and Promerita have transfered ownership of the East 3 property to BC Housing for the construction of 157 social and affordable rental homes for seniors. Design and construction of the East 3 building will be managed by Westbank and 100% funded by BC Housing through a combination of capital and operating grants and low-cost construction financing.

Secured Purpose-built Rental - 767 Units

East 1

382 Secured Market Rental

East 2

385 Secured Market Rental

- Owner: Promerita/Westbank
- Total Units: 767 Units of Secured Market Rental Housing including 3 Affordable live work units
- Prospective Financing Partner: BC Housing
- Building Performance Target: To meet Green Buildings Policy for Rezoning
- Transportation: Minimal car parking and focus on sustainable transport
- 3 Affordable Live Work Units: These are intended to be made available to the creative community such as local artists and musicians help foster the creative culture within the area.
- 1,559 SF Community Serving Retail/Maker Space: The intent would be to have dedicated programed space that support and foster creative culture within the community with space for craft, woodworking, carving, creating, making and artist studio/display space.

+

Seniors Social Housing - 157 Units

East 3

121 Seniors Housing + 36 Replacement SRA Units

- Owner: BC Housing
- Operator: To be determined
- Total Units: 157 Units of Secured Social Housing (Housing Agreement) for seniors
- 36 Single Room Accomodation (SRA) replacement units (100% shelter rates)
- 121 Social Housing Units
- Affordability: 33.33% of units shelter rate, 33.33% of units HILs rate, 33.33% of units low end of market
- Land Partner: Promerita/Westbank contributing East 3 land
- Prospective Financing & Funding (capital and operating) Partner: BC Housing
- CMHC: Funding
- Diversity: Mixed income building
- Building Performance Target: To meet Green Buildings Policy for Rezoning
- Transportation: Minimal car parking and focus on sustainable transport
- Commercial unit designated as social enterprise.
- Timing: Delivered concurrently with East 1 + 2
- Estimated Rental Rates 2023
  - Shelter: $375
  - HIL's - Mixed Income: $850 - $1150
  - LEM: $1150 - $1550
  - Note: Proposed tenure/rents will be subject to BC Housing approvals and available funding.

East Village
924 Total Units

Policy Enquiry Process Criteria Alignment

The City of Vancouver proposes a Policy Enquiry Process that intends to provide a consistent review process for development enquiries that do not comply with rezoning policy but may offer opportunities and benefits that may warrant further consideration by Council. This page summarizes East Village project goals alignment with the Baseline and Review Criteria set by the Policy Enquiry Process. The project proposal notably focuses on housing criteria while also meeting a majority of Baseline and Review Criteria.


Council unanimously supported the project moving forward with Enhanced Rezoning through a Policy Enquiry Directions report on July 21st 2022.



Policy Enquiry Process Review Criteria

1. Housing
2. Jobs
3. Cultural, Social, City Serving Amenities
4. Energy and Greenhouse Gases
5. Neighbourhoods
6. Ecology
7. Municipal Infrastructure


Project Goals



Neighbourhood Development & Local Economy

Jump start reinvigoration of street level activity by providing grade related commercial from west of Glen Drive to Vernon Drive.

Introduce pedestrian related commercial to Viaduct. Design buildings to anticipate future development: Introduce a variation in streetwall heights that achieve a transitional scale between buildings within the block to reflect the historical Hastings Block Typology.



Housing, Health, & Well-being

The project intends to deliver a mix of well designed units, providing the much needed housing supply for singles, families and seniors in the Hastings East community.

Replacement of 36 Single Room Accommodation (SRA) units that are at the end of their life and in need of replacement. The replacement units will be larger and built to meet the latest guidelines for livability. Building will be designed with a focus on occupant livability. Buildings designed to maximize access to views and daylight. Access to indoor and outdoor amenities will promote a healthy and active lifestyle for the residents.



Affordability

The project will bring a diverse mix of high-quality purpose-built rental housing that meets the needs of the tenants and the community.

Focus for the project has been put on maximizing the number of homes along with ensuring an appropriate mix of studio, one bedroom, family homes and housing for seniors.



Sustainability

Project aims to adhere to *Green Buildings Policy for Rezoning*. The design team will be exploring opportunities through the design process to reach beyond the performance targets set out in the *Green Buildings Policy for Rezoning* such as reducing the carbon impact and exploring construction innovation.

Each of the projects through design aims to foster a sustainable culture for the occupants, reducing the dependency on cars and promoting more sustainable and active forms of transport.

PROMERITA westbank BC HOUSING ZGF

Urban Design Goals



Create a Heart

Be guided by the objective of creating a heart to the Hastings East Neighbourhood.

Enhance the linear nature of the Hastings East neighbourhood with a defined heart or center at the eastern end of the Downtown Eastside (DTES) plan.






Intensify the Range of Housing Types

Consider intensifying the quantity and range of housing types at the heart of Hastings East to better meet the City's housing needs.

Use the intensification as a means of creating social connections and sense of community, integrating social and market housing at the neighbourhood scale.





Evolve the Hasting Block Typology

Create opportunity to evolve the building typology by breaking from its traditional typological urban design and building form and re-think the relationship between the buildings and the street.





Create Neighbourhood Identity through Building Form

Consider an alternative to the linear extrusion of a single urban form to allow for a modulation and variation in interpretation of that form.

Evolve the vision of the DTES Plan for Hastings East to create variations in themes established elsewhere in the plan.

Enrich the urban environment with distinctive character layered onto repetitive character.



BC Housing Partnership

BC HOUSING

1701 – 4555 Kingsway
Burnaby, BC V5H 4V8
T: 604 433 1711
F: 604 439 4722
www.bchousing.org

March 25, 2024

City of Vancouver
453 West 12th Avenue,
Vancouver, BC V5Y 1V4

Attn: Josh White, General Manager of Planning, Urban Design and Sustainability

Re: East Village – 3 Properties Redevelopment
East Village East 1: 1030-1070 East Hastings Street, Vancouver ("East 1")
East Village East 2: 1115-1127 East Hastings Street, Vancouver ("East 2") and
East Village East 3: 1168-1180 East Hastings Street, Vancouver ("East 3")

Dear Josh:

This letter is to affirm BC Housing's strong support and provide an outline of the discussions regarding the collaboration between Promerita Group ("Landowner"), Westbank Corp. ("Developer"), and BC Housing (collectively the "Partners") that have commenced through the Province's BC Builds program as we explore the incredible opportunity to develop Living East Village which is a portfolio of 3 sites for redevelopment in the Downtown East Side ("DTES"), Strathcona Neighbourhood. The East Village is within the planning sub-area of the East Hastings Corridor of the DTES Local Area Plan.

The East Village is a portfolio approach to the proposed redevelopment of the 3 properties proposed as East 1, East 2, and East 3 that will include two buildings (East 1 & 2) of purpose built rental housing and one building of Non-Market social and affordable rental housing (East 3) that would replace the existing 36 SRO units with new studio units and add additional purpose built affordable housing units. It is envisaged that the East 1 & 2 building properties will be owned by Westbank/Promerita and ownership of the East 3 will be given to BC Housing, for a nominal fee. BC Housing is the current owner of East 3. Westbank will also be responsible as the lead Developer partner who will head the rezoning, development and construction processes. The funding for the redevelopment of East 3 will be provided by BC Housing and/or affiliate partners.

The East Village redevelopment proposal will require a rezoning of 3 properties to allow the height, density, and form of development that would create over 900 rental units total across the 3 properties, together with new local serving retail spaces, and would have a positive impact in the Downtown Eastside (DTES) community by delivering a new supply of below market purpose built rental and new deeply affordable non-market and rent geared to income social housing options.

Promerita, Westbank, and BC Housing as Partners are proposing to rezone and develop the East Village redevelopment proposal through the Province's BC Builds program together with other provincial funding programs available to BC Housing in the future to create deeper affordability in the portfolio. BC Builds aims to provide interim construction financing to our development partners to create affordability. The non-profit operator, brought on by BC Housing through a competitive RFP process, will seek Community Housing Fund ("CHF") program capital and operating grant funding as well as financing from BC Builds for the redevelopment of East 3, and provided additional financing capacity is available. BC Housing would provide up to 100% of the interim construction financing for the additional East 1 & 2 properties. Timing and access to interim financing is currently in discussion and remains subject to approval by BC Housing's Executive Committee and associated Boards for approvals. BC Housing, through BC Builds, is very interested in participating in the proposed creation of new rental housing at the East Village with Promerita, Westbank, and a future non-profit operator, however, BC Housing's final participation is further contingent on City Council rezoning approval as well as settlement of the final negotiated business terms amongst the parties.

One of these milestones have been achieved and BC Housing has certainty regarding the inclusion of affordable rental units being approved, Final Project Approval by our Executive Committee and associated Boards will be confirmed. We anticipate this development accomplishes the mutual objectives set out by the City of Vancouver, the Project Partners, and BC Housing, while more importantly, providing future residents with access to a stock of brand new below market rental units where affordability across the portfolio will exceed the requirements of the DTES Local Area Plan.

We value this potential partnership and see this as a positive response in alleviating the pressures faced in the DTES neighbourhood with resect to housing and additional rental supply for rental households in Vancouver. Please let us know if you have any questions regarding BC Housing's support of this partnership.

Yours truly,

Mike Pistrin,
Vice President, Development and Asset Strategies
BC Housing Management Commission

Director,
Provincial Rental Housing Corporation



B URBAN DESIGN RATIONALE

The Hastings Street Corridor

A History of Community 13
Community Continuum: East Village 14
Location 15
Responding to Axial Shifts along Hastings 16
Policy Area - Urban Design 17
Neighbourhood - Urban Design 18

This page intentionally left blank



East Hastings Street, Vancouver. B.C. 1949 P.N.E. Opening Day Parade







The Hastings Street Corridor


A History of Community

Since its naming in 1885, the story of the Hastings Street Corridor is one of both success and adversity, but in retrospect it is one of resilience. It has always been and remains one of the most important east-west corridors in the history of the region, and has been a city centre, transportation centre, entertainment centre, tourism centre, and centre for diversity, community, and culture for its many residents throughout the century.

Its legacy is trumped by none, while its neighbourhoods continue to carry the diversity and influence of many peoples, beginning with West Coast Indigenous peoples, the early lumber industry, and many subsequent migrant groups; notably the Irish, Japanese, Russians, Italians, and Chinese. This blended group of first and new Canadians built a rich community, supported and serviced by buildings such as meeting halls, places of worship, and tree-lined family oriented residential neighbourhoods of detached single-family homes, punctuated by multi-family or apartment buildings. Hastings East's proximity to the industrial waterfront lends another layer to the built character of the neighbourhood, with the Rogers Sugar Building, Ballantyne Pier, low-rise industrial buildings, a rail network, and the shipping container terminal being the more obvious displays of this context.

Community Continuum: East Village


Existing Hastings East communities and emergent developments are well serviced by Hastings Street which maintains its role as a major East-West transportation corridor connecting Vancouver and Burnaby. Nearby Clark Drive connects the waterfront on the north, to the rest of the Lower Mainland to the south.



DTES Neighbourhood Map



PROMERITA westbank BC HOUSING ZGF



East Village Aerial

East 1: 1030-1070 East Hastings Street
East 2: 1115 & 1127 East Hastings Street
East 3: 1168, 1172 & 1180 East Hastings Street

The Downtown East-side plan has set up a frame work for a resurgence of community led developments along the Hastings corridor that set out and aims to deliver much needed community amenities and Housing. Only a few projects have been able to move forward in the Hastings East area since the plan was released back in 2014. The housing needs for the community and beyond have evolved and there is an urgent need to provide a socially sustainable mix of equitable homes.

The approved Rezoning at 1015 East Hastings is under construction which is adjacent to the East Village sites on the North side of Hastings between Glen Drive and Raymur. Strathcona Village are is another large mixed-use building on the north side of Hastings Street between Campbell Avenue and Raymur Avenue. These projects along with the East Village projects will help to create a new node along this stretch of the Hastings corridor that helps revitalize the public realm, street-frontage while providing much needed housing.

We believe that our East Village project, as a collection of three buildings sited and designed to support community diversity, respect and honour the past, and well serve the needs of the present, offers a remarkable opportunity to redefine, invigorate and bring much needed social housing and community activation to a barren precinct that has seen its most recent use as low density, low activation, and light industrial.

Location

Hastings East is part of a vibrant community that has recently seen a reinvigoration of services and businesses. Traditionally, the DTES has been influenced by waves of different groups starting with the Indigenous peoples, the early lumber industry and many subsequent migrant groups, notably the Irish, Japanese, Russians, Italians and Chinese. As a result, there is a diverse fabric of detached, residential housing at the south of the project sites.

There also exists much built evidence of these groups in the form of cultural buildings such as meeting halls and places of worship. Hastings East's proximity to the industrial waterfront lends another layer to the built character of the neighbourhood with the Rogers Sugar Building, Ballantyne pier, and the container terminal being the more obvious displays of this context. Immediately adjacent to the site are low-rise industrial buildings. Integrated into the industrial nature of the Hastings East waterfront is the rail network that services it.

Hastings Street maintains its role as a major transportation corridor at Hastings East. Notably, there exists major public transportation services that connect east to west. In close proximity is Clark Drive, which connects the waterfront on the north to the rest of the Lower Mainland, to the south. There has been several mixed-use projects that are already complete or have begun the process for approval. These projects are preparing the area for its anticipated growth as set out in the Downtown Eastside Plan.

Responding to Axial Shifts along Hastings


Typically when there is an axis shift on Hastings Street, we observe a special condition in the form of a framed view or a pause point. 1 From the very west of Hastings, there exists a view corridor toward Coal Harbour. 2 At Howe, Hastings Street acts as a framed view for the Marine Building from the east. 3 At Cambie, the shift on Hastings Street creates a framed view of the Epitaph at Victory Square also from the east. 4 At Carrall Street, the slight shift in axis creates a visual widening on Hastings Street and pause point at Pidgeon Park. 5 Immediately adjacent to our project on Vernon, there exists another axis shift, which the Hastings East area plan has already earmarked as flatiron sites. 6 As the rail runs under the viaduct at Raymur it provides a break in the street but also provides unhindered views to the mountains. We see the opportunity for our proposed buildings to have a strong dialog set up between them and the potential to create special gateway node in the neighborhood between the Viaduct and the Wiggle of Hastings Street at Vernon Drive.













New node in the East Hastings corridor with a distinct character zone




PROMERITA westbank BC HOUSING ZGF

Policy Area – Urban Design



Neighbourhood – Urban Design



PROMERITA westbank BC HOUSING ZGF



EAST 3 PROJECT

Site

Location 21
Current Use 22
Street Elevations 23
Site Photos 23
Contextual Aerial View 24
Future Contextual Aerial View 26

Zoning Analysis + Review Criteria

Applicable Policies & Guidelines 28
Variance Rationale 28
Project Information 29
1. Housing. 30
2. Jobs. 31
3. Cultural, Social, and other City Serving Amenities. 32
4. Energy and Greenhouse Gases 33
5. Neighbourhoods 34

Proposal

East 3 Project Overview. 36
Key Design Moves 37
Hastings Block Typology 39
Facade Strategy 40
Podium Strategy. 41
Architectural Expression 42
Form of Development 44
Livability 46
Amenities 48
Sustainable Transport 50
Sustainability. 51
CPTED Measures 52

Drawing Sets

Development Data. 54
Site Survey 58
Building Grades Survey 59
Context Site Plan 60
Site Plan 61
Streetscape Elevations. 62
Shadow Study. 65
Floor Plans 66
Section East/West 74
Section North/South 75
Elevations 76
Materials 78

Site

Location 21
Current Use. 22
Street Elevations. 23
Site Photos 23
Contextual Aerial View. 24
Future Contextual Aerial View 26

Location


WATERFRONT STATION
BURRARD ST
GRANVILLE ST
DOWNTOWN
BC PLACE
YALETOWN
SCIENCE WORLD
20 min walk
10 min walk
5 min walk
CRAB PARK
9 mins
2.6 km
GASTOWN
14, 16, 20
OPPENHEIMER PARK
EAST HASTINGS ST
R5
CHINATOWN
ANDY LIVINGSTON PARK
MAIN ST
CONCORD COMMUNITY PARK
CREEKSIDE PARK
THORNTON PARK
HINGE PARK
DAVID LAM PARK
NEW ST PAUL'S HOSPITAL
PRIOR ST
STRATHCONA
TRILLIUM TURF
STRATHCONA PARK
HASTINGS EAST POLICY
E1
E2
E3
HEATLEY AVE
CAMPBELL AVE
MACLEAN PARK
GLEN DR
CLARK DR
BRITANIA RUNNING TRACK
WOODLAND PARK
COMMERCIAL DR
GRANDVIEW PARK
N


Current Use

Both East 1 and East 2 sites are lots on opposing corners of the East Hastings and Glen Drive intersection. East 3 site is located less than a block away.

East 3: 1168, 1172 & 1180 East Hastings Street

The 1172 and 1180 site is currently a low-rise commercial building, zoned M-1. The 1168 site contains low rise social housing with outdated SRO units and is currently zoned RT-3. The project site has the following adjacencies:

South: Single family home neighbourhood
West: Low-rise commercial development
North: Car dealership
East: Social housing



Surrounding Program


- Single Family Home Neighbourhood
- Low-Rise Commercial
- Industrial and Tertiary Sites
- Parking Lot
- Vacant Lot
- Mixed-use Development
- Community Centre
- Social Housing
- Restaurant

PROMERITA westbank BC HOUSING ZGF

Street Elevations




Site Key



A EAST HASTINGS STREET

Site Photos











Contextual Aerial View

Looking North West



Contextual Aerial View

Looking South West



Future Contextual Aerial View

Looking South West



PROMERITA westbank BC HOUSING ZGF

Zoning Analysis + Review Criteria

Applicable Policies & Guidelines 28
Variance Rationale 28
Project Information. 29
1. Housing 30
2. Jobs. 31
3. Cultural, Social, and other City Serving Amenities . 32
4. Energy and Greenhouse Gases 33
5. Neighbourhoods. 34

Applicable Policies & Guidelines

- Council-adopted Policy Enquiry Process: Approach and Criteria (2021)
- Downtown Eastside Plan (2018); Downtown Eastside Rezoning Policy (2014)
- SRA (Single Room Accommodation) By-law (2003, last amended 2020)
- SRO Revitalization Action Plan (2017)
- Housing Vancouver Strategy (2017)
- Employment Lands & Economy Review Phase 2 Report: Emerging Directions for Consideration Through Vancouver Plan (2020)
- Culture|Shift (2020)
- Making Space for Arts and Culture: Vancouver Cultural Infrastructure Plan (2019)
- Community Amenity Contributions – Through Rezonings (1999, last amended 2021)
- Community Benefit Agreement Policy (2018) City of Vancouver Green
- Buildings Policy for RezoningCity of Vancouver Parking Bylaw 6059 - January 2019
- High-Density Housing for Families with Children Guidelines (1992)
- Policy Enquiry: Directions Report to council July 21st 2022.

Variance Rationale

This proposal is being considered under the new Policy Enquiry Process, which was endorsed by Council in July 2021. Following this Council unanimously supported the project moving forward with Enhanced Rezoning following the Policy Enquiry Directions Report on July 21st 2022.

The Policy Enquiry Process intends to provide a consistent review process for development enquiries that do not comply with rezoning policy, but which offer opportunities and benefits that warrant further consideration by council due to their significant public benefits.

This Rezoning is seeking support for the three projects that deviate from the heights, densities, and built form guidelines set out in the Downtown Eastside Plan. These variances from policy are needed to support an economically viable project that can deliver critically needed housing for families, singles and Low income seniors.

The entire East Village project significantly contributes to the development of the Hastings corridor and East Hastings neighbourhood by responding to the immediate current and future context and the rising housing needs. The project proposal notably focuses on housing criteria while also meeting majority of other council priorities outlined in the review criteria set by the Policy Enquiry Process. Also, provision of homes for artists/musicians in support of the local community. The team asks that staff consider this rationale and significant community benefits to support the variances needed.



Project Information

Site Location:
1168, 1172, 1180
East Hastings Street
Vancouver BC

Title:
Proposed Lot A
Lots 15 & 16 (Plus1168 lot)
Block 14 of Block A
District Lot 181, Group 1,
New Westminster District, Plan 355

Required Setbacks:

West:	0
South:	10.17' (3.1 m) Measured from centre of lane***
East:	0
North:	18.04' (5.5 m) Surface Right of Way**

Allowable Building Height:
120' / 36.58m

Existing Zoning:
M-1 & RT-3

*** Per COV Engineering Department advice*
**** Per M-1 zoning bylaw*

SITE AREA
9,191 SF
853.87 m²

GROSS FLOOR AREA
102,754 SF
9,546 m²
Including Area Exclusions

RESIDENTIAL AREA
100,465 SF
9,334 m²
Total (Townhomes + Tower)
Includes In-suite storage

SOCIAL ENTERPRISE
2,289 SF
212.66 m²
Total Unit Area Social Enterprise

DENSITY
10.4 FSR
Floor Space Ratio

SOCIAL HOUSING UNITS
121

SRA REPLACEMENT UNITS
36
at Shelter Rates

TOTAL HOUSING UNITS
157
33.33% at Shelter Rates
33.33% at HIL's
33.33% at Low end of Market

PROPOSED HEIGHT
194'-8" ~
59.3 m
19 STOREYS

CAR PARKING
5
Stalls

BICYCLE PARKING
288
Total (131 Class A stalls provided at below grade and additional 157 provided in-suite, 1 per suite)

LOADING
2
1 Class B Loading Stall Shared between Residential and Social Enterprise

1 Class A Passenger Loading Stall

~*Measured from level 1 T.O.S to top of parapet above the elevator overrun*

1. Housing


Goal: Provide a range of affordable housing choices by shifting towards a focus on rental, social, cooperative, and supportive housing as well as owner occupied homes for first-time buyers.

Criteria

- If the proposal is located within the boundaries of a community / area plan, does it exceed the requirements of the plan (e.g. deeper affordability or a larger number of affordable units) or achieve the plan objectives in an all-rental development?
- Does the proposal retain existing affordable rental units, or if not possible, replaced with affordability retained and tenants supported?
- Does the proposal meet the City's housing affordability goals, focusing on households with incomes below $80,000? Does it achieve deeper levels of affordability for households with lower incomes and/or other housing barriers and/or underserved tenant populations (e.g. lone-parent families, people with disabilities, etc.)?
- Does the proposal support the shift to the right supply of housing, with strong emphasis on rental housing and community-based housing?
- Does the proposal include strata floor area? (Note: strata developments that are not compliant with existing policy should be considered only in exceptional circumstances due to potential for speculative impacts on land value.)

Design Teams Rationale

- The project proposal aims to provide a range of housing types with a focus on housing for families, singles, and seniors. This housing supply responds to the needs of the community that is outlined within the Downtown Eastside Area Plan.
- The project aims to deliver a total of 924 units that include 767 units of secured purpose-built rental housing, and 157 social affordable rental homes for seniors.
- East 1, East 2 buildings are to be owned by Westbank/ Promerita as purpose-built market rental units.
- The Social housing on East 3 will provide higher levels of affordability with homes at Shelter, HIL's and LEM rents. Based on these criteria, approximately 80% of the units across the three buildings would be considered affordable for households with incomes below $80,000. The units on East 3 are aimed at households with much lower incomes.
- The existing Single Room Accommodation (SRA) units located on East 3 site are at the end of their life, undersized (~120 SF) and in need of replacement. The East 3 project proposes to replace the 36 existing SRA units which will be a 1 for 1 replacement with much larger studio units with sizes ranging from 340 SF - 390 SF (gross area). All these replacement SRA units will be offered at shelter rates.



PROMERITA westbank BC HOUSING ZGF

2. Jobs

Goal: Ensure a resilient local economy that provides a broad range of employment opportunities for all with a particular focus on fostering a strong green, creative, and tech sector.

Criteria

- Does the proposal assist with addressing the challenges identified through the Employment Lands and Economy Review?
- Provides major office or hotel space in high demand areas (DT West, Broadway Corridor, Oakridge)
- Increases small office / retail-commercial space above what is typically delivered in residential or choice of use areas
- Delivers stacked light industrial space
- Provides secured space for non-profit operators / arts and culture / social services / social enterprise / childcare

Design Teams Rationale

- The project aims to deliver 12,925 SF of street related community serving commercial space.
- 2,289 SF of Social Enterprise space will be offered in the East 3 project.
- The East 3 project would be Non-Profit owned. This site will provide a standalone Social Housing Building for Seniors and complemented with community serving social enterprise located at grade.
- The construction of three building projects will generate extensive employment opportunities for the workers in the construction industry.
- The East 1 project will contain 3 dedicated affordable Live Work Units. These are intended to be made available to to the creative community such as local artists and musicians help foster the creative culture within the area. Strategically located in the massing to allow for a stepped down transition from the tower to the lower density Kiwassa Neighborhood to the south. The programmed space at grade level has the opportunity to create a more active edge on Glen Drive interface with the laneway.
- East 2 project contains 1,559 SF Community Serving Retail/Maker Space. The intent would be to have dedicated programed space that would support and foster creative culture within the community with space for craft, woodworking carving creating & making. This will create a good program transition to the industrial lands North of the site and help keep an activate the edge along Glen Drive and the laneway.



EAST 1
4,973 SF Community Serving Retail
2,481 SF of Live Work - These are intended to be made available to the creative community such as local artists, musicians etc.



EAST 2
7,952 SF Community Serving Retail
1,559 SF Community Serving Retail/Maker Space



EAST 3
2,289 SF Social Enterprise
Non-Profit operated Social Housing

3. Cultural, Social, and other City Serving Amenities

Goal: Fulfill a City goal and/or meet City targets that is otherwise difficult to achieve through existing mechanisms or policy, including social or cultural infrastructure, i.e. culture shift.

Criteria

- Does the proposal include a significant public amenity(ies), including social and/or cultural public amenity(ies), based on an identified need in the community and cannot be delivered through existing mechanisms (e.g. childcare, community facilities, cultural spaces, new park space)?
- Is there an immediacy of the opportunity based on funding / partnership opportunities?
- If the proposal is located within the boundaries of a community / area plan, does the proposal include a significant public amenity, pursuant to policy direction in the plan and/or the area Public Benefit Strategy, that is beyond what would be expected as a CAC in the proposed development under plan policy.
- Does the proposal meet a City goal and/or target, i.e. Culture|Shift goals, priorities and cultural space targets?
- Does the proposal secure significant cultural space and meet Reconciliation and/or Cultural Redress infrastructure needs of the community?

Design Teams Rationale

- Social Enterprise located on the grade level at East 3 project will serve the community and respond to activating the street frontage.
- Public art is proposed on the façades of East 3 building. A façade treatment/mural will be added to the building interface of East 1 and the CN Rail.
- East 3 project proposes a 1 for 1 replacement of the 36 SRA units that are undersized and at the end of their lives.
- In response to the change in axis of East Hastings Street at Vernon Drive in front of the East 3 site, an opportunity to create a small public plaza or park space will be explored with the City for civic improvement.
- In an attempt to embrace the creative culture rooted within the community the project is proposing 3 Affordable Live Work Units: These are intended to be made available to the creative community such as local artists and musicians.
- To help continue to foster and grow this creative culture within the neigbourhood the project is proposing 1,559 SF of Community Serving Retail/Maker Space with dedicated space for craft, woodworking carving creating & making.



PROMERITA westbank BC HOUSING ZGF

4. Energy and Greenhouse Gases

Goal: Eliminate dependence on fossil fuels, helping residents and local businesses survive and thrive in a post-carbon era.

Criteria

- Is the proposal in an area well-served by sustainable active transportation networks, such as pedestrian, public transit and bike infrastructure (or can be provided through development) to meet City goals for safety and sustainable transportation (including Transportation 2040 & Climate Emergency Action Plan)
- Will the project electrify and be energy efficient? What is the material strategy to reduce the embodied carbon impact? What is the design rational for Climate Resiliency? What are transit connections to reduce reliance on cars?


Design Teams Rationale

Operational Energy:
- The project will be fully electrified, reducing the GHGI of the project.
- Energy efficient design strategies include simple form factor, reduced WWR, Air-to-Water Heat pump for heating, cooling and DHW.


Embodied Carbon:
- Volume of concrete will be reduced through reducing parking levels and transfer slabs
- Low embodied carbon materials will be selected meeting the City of Vancouver target of 10% reduction on 400kgCO_2e/m^2

Climate resiliency:
The team has conducted Climate Resiliency Hazard Assessment and are developing Climate Resilient Design strategies, including:
- Earthquake – project is designed to comply with CSA-A23.3
- Extreme heat and warmer summer / winter temperatures – Strategies include reducing the Window-to-Wall Ratio (WWR) and the mechanical cooling system is sized for future warming weather conditions.
- Poor air quality (wildfire and traffic) – Each unit's Heat Recovery Ventilation (HRV) system includes a MERV 13 filter.
- Power outage – there is a diesel back-up generator located on roof providing emergency back up for life safety systems,
- Drought / Water restrictions – Investigation into high-efficiency irrigation systems with timed and rain sensor controls. The planting scheme prioritizes native, adaptive, and drought-resilient vegetation.
- Design Team will further develop and refine the Climate Resilient Design strategies through workshops and analysis in subsequent development stages.

Sustainable Transport:
- The intent for each of the buildings is to offer housing with accessible transit and active mobility options. This approach intends to reduce the dependency on individually owned cars and will allow inhabitants to have easier access to, fosters sustainable modes of transport, and promote the health and wellbeing of the occupants. The project team will work with Bunt and Associates on our TDM plan that aims to encourage sustainable modes of transportation such as walking, cycling, public transit and car share.
- The project sites are located less than a 10-minute cycle from the downtown convention center and the project intends to foster a strong bike culture through enhanced bicycle amenities.



Integrating the intake and exhaust air into envelope systems



Bike path network, Bus and Rapid bus routes in proximity to the project sites.

5. Neighbourhoods

Goal: Ensure our neighbourhoods are places where residents and workers have access to open space, shops and community amenities and where urban land use and street networks support everyone's ability to walk, roll, and take transit for their daily needs.


Criteria

- Is the proposal located in an area that has convenient access to shops, community centres or neighbourhood houses, childcare, parks, plazas, or other open space amenities?
- Will the proposal make a significant contribution to the completeness of the neighbourhood, through a combination of increased affordable housing, local-serving retail, and/or public amenities which meet a demonstrated community need?
- Does the proposal retain existing local-serving commercial or non-profit spaces, or if not possible, replace these with affordability retained and tenants supported?
- If the proposal is located within the boundaries of a recently approved community / area plan (2010 onward), are there other specific factors that need to be considered (will vary by plan area policies)

Design Teams Rationale

- East village project aims to create a heart in the Hastings East Area of the Downtown Eastside. The development of these three building along with the recently approved 1015 East Hastings project will act as a catalyst for future growth of this socially sustainable neighborhood.
- These collections of projects aim to provide community serving retail for the occupants and residents living in the surrounding Kiwassa and Strathcona areas.
- The project proposes active frontages on the streets, additional sidewalk widths, small parklets and places to pause to enhance the public realm and create a more walkable neighborhood.
- The project has easy access to rapid transit route and bicycle routes to increase how its connected to the rest of the city. Climate Emergency Plan and Transportation 2040 identifies actions to develop the Hastings corridor transit route and services to serve the future growth and improve the transit network.
- The East 3 project is to be owned by a Non-Profit. Social Enterprise at ground level to enhance and support affordable community serving retail at the ground level. The team intends to work with the local community groups and residents to better understand the needs for these community serving retail spaces.





Activating the ground plane as landmarks and establishing standards for the future growth as set out in the Downtown Eastside Plan to enhance the public realm

PROMERITA westbank BC HOUSING ZGF

Proposal

East 3 Project Overview 36
Key Design Moves 37
Hastings Block Typology 39
Facade Strategy 40
Podium Strategy 41
Architectural Expression 42
Form of Development 44
Livability 46
Amenities 48
Sustainable Transport 50
Sustainability 51
CPTED Measures 52

East 3 Project Overview

Proposed for the East 3 site is a 19 storey building including 1 level of above grade mezzanine parking. East 3 accounts for the social housing requirements generated by the total rental units that are provided on East 1 & East 2 (767 units). These would be provided as dedicated Social Housing and on the East 3 site. Westbank and Promerita have transfered the ownership of the East 3 Land to BC Housing for the construction of these 157 standalone Social Housing units for Seniors on the East 3 Site. This includes the replacement of 36 Single Room Accomodation (SRA) units on the site that are being upsized to meet current standards.

The existing 36 SRA units located on the East 3 site are drastically undersized at approximately 120 SF and they are at the end of their life and in need of replacement. It is proposed that units will be replaced 1 for 1 with studio units with sizes in the range of 340 SF - 390 SF (gross area).

In response to the change in axis of East Hastings Street at Vernon Drive in front of the East 3 site, an opportunity to create a small public plaza or park space will be explored with the City for civic improvement.

On the ground level, there will be 2,289 SF of social enterprise space that fronts East Hastings Street. As an infill building, East 3 will stand 13 and 19-storeys tall. The lower volume acts as an interface to the corner site to the east, as it is part of the intention of the Hastings Area Plan to introduce random streetwall heights that achieve transitional scale between buildings within the block. The building is oriented in an L formation in plan, with maximum exposure to the south. This creates a courtyard that provides cross ventilation and daylight from both sides.

The project takes cues from the heritage of the traditional Hastings Block Typology. The volume of the building is broken up into the base, the middle, and the top. While the middle reflects the rhythm and order of the Hastings Block Typology and provides direct contextual connection, the base and top breaks from the typology to create new relationships to the pedestrian and roof scales.

Affordability

The East 3 building is proposed as a mixed income social housing building for seniors. As this building is aiming to provide much needed affordable housing for seniors, made up of 1-bed and studio units. This unit mix is supported by 9.2.6 of the Downtown Eastside Area Plan.

The proposed affordability breakdown on East 3 would be:

- **157 Social Housing Units**
  - 33.33% of units at shelter rate
  - 33.33% of units at HILs rates
  - 33.33% of units at low end of market
- **36 Replacement SRA Units**
  - 100% of units at shelter rate





Relate to the Hastings Block Typology



Industrial Like Simplicity




Expression of Grid

PROMERITA westbank BC HOUSING ZGF


Key Design Moves

The design aims to redefine the Hastings Block Typology through a series of key design moves, creating new relationships to the site and greater activation of the public realm while working with the objectives set out in the Downtown Eastside Plan.




Maximize

Maximize site area based on setbacks from the Downtown Eastside Plan.




Integrate

Activate the site area for podium and tower and set up the formation of a distinct base, middle, and top that reflects the rhythm and order of the traditional tripartite Hastings Block Typology through simple massing, lasting materials, and proportion.




Articulate & Activate

While the middle of the building retains the connection to the Hastings Block Typology and industrial context, the ground plane is articulated to break from the typologic form and departs from the traditional base.



Lighten

Lighten the top of the building to break from the typologic form and to speak to the Vancouver skyline. The top lantern form reiterates the gateway function of East Village between Grandview Woodlands and downtown east.




Program

Deliver an appropriate mix of studio and one bedroom housing for seniors. Introduce indoor and outdoor amenities that promote and support a healthy and active lifestyle for tenants.

Key

- Social Enterprise
- Residential
- Bike Storage
- Outdoor Amenity
- Indoor Amenity




Enhance

The proposal seeks to enhance the public realm experience by positioning active uses along East Hastings Street, while being mindful of CPTED concerns. The form is integrated to the public realm to create engagement, visibility and vibrancy of the East Hastings streetfront as described in the Downtown Eastside Plan.


Hastings Block Typology

While maintaining certain connections to the Hastings Block Typology through simplicity, proportions, and strong ties to the grid structure, the project strives to challenge and redefine the relationships established by the traditional Hastings Block Typology.


The departure from the established typology allows us to rethink the relationship between the building and the street and challenge traditional building and planning notions in both the urban design scale and the building scale. This allows us to essentially transform the relationship to the street and enhance the public realm.



Typical Podium Building




East Hasting Block like typology
Tripartite base middle top composition



Evolution of Hastings Block Typology
with erosion at the base and top

Facade Strategy


The facade module is configured to preserve the strong ties to the grid. Various patterns and forms will be explored to enhance livability, articulate program, and aid in building performance.



Podium Strategy

The design of the building podium aims to integrate elements that harmonize with the surrounding single-family neighbourhood and keep the connection with the historical context.

Drawing inspiration from the neighbourhood's architectural vernacular while challenging the relationships established by the traditional Hastings Block Typology.




1. Grid









2. Podium Expression










3. Podium + Program








4. Coxtetual Relationship









5. Program Specificity







Architectural Expression

Top

Celebrate the Industrial Heritage of the Site
Arches at the top of the massing will help reinforce the East hastings Block like topology at the top and draw a strong connection to the industrial typology surrounding the site

The upper floor amenity spaces offer incredible views to the north-shore mountains. The architectural articulation and expression at the top of these buildings will help frame a gateway at the new node of East village when traveling East along Hastings Street to the Grandview Woodlands area.

Middle

Relationship to Hastings Block Typology
Through simple massing, materiality, proportions, and strong ties to the grid structure, the project strives to maintain the connection to the Hastings Block Typology and the relationship to the grid.

Celebrate The Industrial Heritage of the Site
The project is rooted in the order and rhythm that is emphasized in its industrial context.

Base

Connect to Nature
The manipulation of the scale of the ground plane and how the building hits the ground seeks to reflect the openness of nature by bringing the outdoors in.

Outdoor space and amenity locations are oriented to maximize views to the Two Sisters Mountains.

Relate to A Variety of Neighbourhood Scales
The project aims to create a transitional scale between residential, industrial, and tower typologies by responding to the variation of scales in the neighbourhood.





View to the Two Sisters Mountains



The Middle reflects the order and rhythm of the Hastings Block Typology



Break from typological form

PROMERITA westbank BC HOUSING ZGF

Ground Floor Social Enterprise Space at Hastings Street



Form of Development

1. **Transitional Scale**
Variation in scale of the massing base and ground plane allow the buildings to respond to the variety of scales in the neighbourhood.

   Connection to Hastings Typology and scale.

2. **Consideration to Neighbouring Lots**
Current height of corner site

3. **Activating Street Frontage**
Hastings Street is activated with commercial use at grade.
A pedestrian scaled street frontage enhances pedestrian experience by breaking down the commercial facade into smaller units.

4. **Project Performance**
Targets for building performance requires the building to achieve 40-50% glazing.

5. **Public Art**
Lower interface volume creates opportunity for semiotics on exposed walls, as per historic precedents of the Hastings BlockTypology.

6. **Hastings Block Typology**
The distinct bottom, middle, and top reflects the architectural nature of Hastings Street. Regular rhythm and order are emphasized in the middle, while the bottom and top break from that order to create new relationships to the street and pedestrian scale.

7. **Reducing Massing Bulk**
Lowered volume to interface with neighbouring corner property.

8. **Outdoor Space**
As a result of reducing bulk on the upper floors, and to create a transition volume for future development for the neighbour to the east, the lower volume provides opportunity for a rooftop garden.

9. **CPTED**
Enhanced CPTED response with eyes on the lane from the amenity space.

10. **Lightening of Massing**
Increased glazing on upper portion of building lightens massing.



PROMERITA westbank BC HOUSING atira ZGF

1 Transitional Scale
Variation in scale of the massing base and ground plane allow the buildings to respond to the variety of scales in the neighbourhood.

Connection to Hastings Typology and scale.

2 Consideration to Neighbouring Lots
Current height of corner site

3 Activating Street Frontage
Hastings Street is activated with commercial use at grade.
A pedestrian scaled street frontage enhances pedestrian experience by breaking down the commercial facade into smaller units.

4 Project Performance
Targets for building performance requires the building to achieve 40-50% glazing.

5 Public Art
Lower interface volume creates opportunity for semiotics on exposed walls, as per historic precedents of the Hastings Block Typology.

6 Hastings Block Typology
The distinct bottom, middle, and top reflects the architectural nature of Hastings Street. Regular rhythm and order are emphasized in the middle, while the bottom and top break from that order to create new relationships to the street and pedestrian scale.

7 Reducing Massing Bulk
Lowered volume to interface with neighbouring corner property.

8 Outdoor Space
As a result of reducing bulk on the upper floors, and to create a transition volume for future development for the neighbour to the east, the lower volume provides opportunity for a rooftop garden.

9 CPTED
Enhanced CPTED response with eyes on the lane from the amenity space.

10 Lightening of Massing
Increased glazing on upper portion of building lightens massing.

Livability

The project strives to surpass livability of occupants through:

- Maximizing indoor comfort through building performance goals
- Maximizing daylight and views
- Encouraging natural ventilation
- Bringing the outdoors in
- Access to shared amenities
- In-Suite bulk storage
- Flexibility
- Modularity
- Accessibility



East 3: Typical Studio



Encourage Natural Ventilation



Maximize Daylight & Views


Create a Private Oasis


Bring the Outdoors In

The facade module is configured to preserve the strong ties to the grid. Individual HRV's located closer to the window minimizes the run of insulated ductwork and can prove to be more cost effective. The addition of a perforated panel aims to hide the supply and exhaust penetrations of the individual HRV's and maintain a seamless architectural expression.







Amenities

The proposal aims to maximize indoor and outdoor semi-public amenities within each building to aid in the enhanced livability of residents. Additionally, public amenity spaces through CRU contributes to broader community spaces.

Indoor:

The podium accommodates commercial space on the ground floor, shared meeting space and library on the mezzanine floor, a multi-purpose room on the second floor and shared indoor amenity on the roof.

Outdoor:

Multiple outdoor spaces are provided, including outdoor amenity decks on the second floor podium and twelfth floor massing setback, and outdoor amenity space on the rooftop. All outdoor spaces have been designed to be exposed to south facing light and are oriented to maximize views to the Two Sisters Mountains to the northwest.



Key

- Future Context (Downtown Eastside Plan)
- Commercial
- Social Enterprise
- Amenity
- Bike Storage
- Residential Entry
- Outdoor Amenity
- BOH

PROMERITA westbank BC HOUSING ZGF

East 3 aims to provide a multitude of interior and exterior amenity spaces to enhance the overall livability of residents.

Interior

- Concierge desk
- Mail packages drop off
- Building manager office
- Bike lounge
  - Bike workshop
  - Hang out space
  - Bike wash station
  - Changing rooms
- Multi-purpose room
  - Cooking / Servery
  - Lounge
  - Party room
  - Connection to outdoors
- Health and wellness
  - Fitness centre / gym
- Building Co-working space
  - Office space
  - Floating workstations
  - Meeting rooms
  - Lounge / business center
  - Library
- Billiards / games room
- Dog Wash (buildings are pet friendly)
- Below grade storage lockers.

Exterior

- Rooftop gardens
- Rooftop BBQ area
- Outdoor Fitness
- Firepit lounge.


Rooftop BBQ & Social Space


Co-working space for residents


Games room / Kids space



Dogwash Station


Workshop


Sustainable Transport

The proposal aims to provide enhanced bicycle amenities and storage within each building, to support and promote cycling lifestyles. Additionally, the project team is investigating strategic design moves to incorporate bicycle and gear storage in-suite. Adjacent to the site, there is a key bike path network with connections to downtown and across the City of Vancouver.

East Village is also adjacent to bus stops providing access to the number 14, 16, and 20 major bus routes and a 5-10 min walk to the Commercial Drive RapidBus Bus Stop.




Enhanced bike amenities



In-suite storage





PROMERITA westbank BC HOUSING ZGF

Sustainability

Green Buildings Policy for Rezoning

The sustainable design strategy for the East Village portfolio is being developed to meet the City of Vancouver's (CoV) Policy: Green Buildings for Rezonings (last amended July 25th, 2023). East 3 Green and Resilient Building Measures Package has been developed with energy modelling, Life Cycle Analysis and a desk top Climate Risk Assessment. The Green and Resilient Building design strategies for East 3 will be further refined through detailed workshops, iterative energy modelling, and Life Cycle Analysis.

Sustainability Goals

The sustainability strategies include:

- Green transit with a reduction in car parking and the provision of bike facilities adjacent to a bike path network with connections across the City of Vancouver.
- Shared exterior landscaped roof top terraces.
- Full electrification of systems, with high energy efficient design strategies.
- Embodied carbon reduction through volume reduction of concrete and selection of low embodied carbon materials.
- Climate Resilient design features to mitigate identified Climate Hazards.

Requirements

Energy & Emissions Performance Summary Proposed (adj)[1]	TEUI (kWh/m²) - 120.6 Pass TEDI (kWh/m²) - 24.8 Pass GHGI (kgCO2/m²) - 1.2 Pass
Embodied Carbon Limits	Early stage wbLCA analysis indicates that 10% reduction target on 400kgCO_2e/m²
Resilient Buildings Planning	Resilient design strategies are being included in the project to respond to hazard events including earthquake/extreme heat/ poor air quality.
Enhanced Commissioning	3rd party commissioning authority will form part of team and will develop commissioning plan and report in line with City of Vancouver commissioning requirements.
Energy System Sub-metering	Energy sub-metering will be incorporated in line with City of Vancouver requirements.

[1] *Includes TEDI / TEUI adjustment*

CPTED Measures

Building Identification & Exterior Entrances

- East 3 will be clearly identified with a street number towards the main street frontage on East Hastings Street.
- Lobbies are designed to be visible from East Hastings Street with clear identifiable signage as well as landscaping and paving features directing users towards the entries.

Common/Open Space Areas and On-Site Open Space

- Active outdoor amenities are located adjacent to indoor amenity spaces and residential units so that visual connection promotes indirect surveillance.
- Visual connection that the outdoor amenity space has to the laneway, is maintained to promote indirect surveillance to the lane from the Level 2 Terrace.

Lighting - Exterior

- All outdoor amenity areas, the lane, and street frontages will be well lit for both residents and public.

Natural Surveillance

- Public and semi-private areas provide unobstructed eye-level views from other regularly occupied areas. Barriers such as fences and gates are also minimized. Where fences are required, the project will provide decorative picket fencing.
- Where possible, windows are provided to stairways, corridors, shared amenity, and other common rooms to improve visibility and safety.
- All building surface materials will be graffiti resistant.
- There are no alcove conditions along the building frontages, on Hastings Street and the lane.
- All door and window hardware will be durable and vandal resistant.
- Operable windows are located at higher levels and in visible areas to minimize any potential for concealed attempts at breaking and entering.
- Garbage and recycling rooms are fully enclosed within the building footprint and accessible only to residents and tenants.

Parking

- Parking area will be well lit and monitored.
- All surfaces will be painted with a light and reflective colour to provide a bright environment.
- Access into the parking area will have a secured overhead entry door controlled with remote electronic key access.

Security

- At all entry points into residential areas, the buildings will be fitted with electronic key access and enterphone systems to reduce unauthorized entry.
- A monitored fire alarm system with annunciator will be installed. The commercial spaces, residential units, and the parking areas will have their own fire detection and suppression system.

Site and Building Layout

- Main entrances into the buildings are oriented towards, and visible from, East Hastings Street.
- The number of entry points into the buildings are minimized.
- Access to elevators, stairwells, and pedestrian pathways are clearly marked and lit, and unsecured hidden areas are minimized.

Drawing Sets

Development Data 54
Site Survey 58
Building Grades Survey 59
Context Site Plan 60
Site Plan 61
Streetscape Elevations 62
Shadow Study 65
Floor Plans 66
Section East/West 74
Section North/South 75
Elevations 76
Materials 78

Development Data

EAST VILLAGE: Project Stats

East 1:		382 Units
East 2:		385 Units
East 1 + East 2:		**767 Units**
East 3:	Senior Social Housing Units	121 Units
East 3:	Replacement SRA Units	36 Units
Senior Social Housing (East 3):		**157 Units**

Project Total Social Housing (Including SRA replacement) **157 Units** **20.47% Social**

**20.47% of total rental units that are provided on East 1 & East 2 (767 units) would be dedicated Social housing and these units would be provided on the East 3 site. Westbank and Promerita have transfered the ownership of the East 3 Land to BC Housing for the construction of these 157 standalone Social Housing units for Seniors on the East 3 Site.*

Street Level Commercial - East 1 + East 2 total: **12,925 SF**
Street Level Commercial Enterprise - East 3 **2,289 SF**

EAST 3: Project Data Summary

Site Address

Street: 1168, 1172 & 1180 East Hastings Street, Vancouver, BC
Legal: Proposed Lot A, Lots 15 & 16 (Plus 1168 lot) Block 14 of Block A, District Lot 181, Group 1, New Westminster District, Plan 355

Gross Site Area		**9,191**	**Sq.Ft.**	**853.87**	**Sq.M.**
Total Commercial Unit Area		2,289	Sq.Ft.	212.66	Sq.M.
Total Commercial Non Unit Area		0	Sq.Ft.	0.00	Sq.M.
Total Residential Unit Area		100,465	Sq.Ft.	9,333.51	Sq.M.
Gross Floor Area		**102,754**	**Sq.Ft.**	**9,546.17**	**Sq.M.**
Exclusions	** See stats breakdown for details*	7,409	Sq.Ft.	688	Sq.M.
Net Floor Area		**95,345**	**Sq.Ft.***	**8,858**	**Sq.M.**
Floor Space Ratio		**10.4**	**F.S.R***		

Exterior Areas

	Rate	Permitted/ Required	Proposed
Balconies	8% of residential GFA	8,037 Sq.Ft.	3,638 Sq.Ft.
Outdoor Amenity			6,123 Sq.Ft.
Total Exterior			**9,761** Sq.Ft.

Height and Setbacks

	Permitted/ Required		Proposed	
Building Height:	120 ft	30.5m		
(Measured: Level 1 top of slab to top of parapet above uppermost habitable floor)			*178'-2"*	*54.3m*
(Measured: Level 1 top of slab to top of slab of elevator overrun)			*192'-8"*	*58.7m*
(Measured: Level 1 top of slab to top of parapet above Elevator Overrun)			*194'-8"*	*59.3m*
Setbacks				
North			*0'-0"*	*0.0m*
West			*0'-0"*	*0.0m*
South			*18'-0"*	*5.5m*
East			*0'-0"*	*0.0m*

Proposed measurements to tower: See Zoning Analysis & drawings for details

Bike Parking

Residential								
			Required / permitted		40 % TDM Increase		Proposed	
Rate	Rate	Units	Class A	Class B	Class A	Class B	Class A	Class B
Units under 65m2 (700 st)	0.75	147	110.25		154			
Units Under 105m2 (1,130sf)	1.5	10	15		21			
Units Over 105m2 (1,130sf)	1.5	0	0		0			
Class B 2/20 units	20	157		7.85				
TOTAL:			**125.25**	**7.85**	**175**		131	8
Bike Storage Provided In-Suite							157	
TOTAL Including In-Suite Bike storage:							288	

of which Regular Horizontal	3							
Min Lockers	10%		12.525		18			
Max Vertical	30%		37.575		53			
Max Stacked	NA							
Max Stacked + Vertical	60%		75.15		105			
Oversized	5%		6.2625		9			
TOTALS								

Retail								
			Required		40 % TDM Increase		Proposed	
Rate	Rate	Area	Class A	Class B	Class A	Class B	Class A	Class B
Class A 1/340m2 (3,660sf)	3660	2289	0.6		0		6	
Class B: 6 > 1,000m2(10,764)	6.0	0		0	0		2	

Vehicle Parking

Residential	Rate	Areas/ units	Required	60% With TDM Reductions	Proposed
				-	
				-	
Total Actual stalls Residential			**38**	**15**	**5**
Total with Accessible stalls X2					**9**
of which are accessible stalls			6	2	4
of which are small car	25%	MAX	6	MAX 4	0
of which are regular stalls			6		1

Commercial (Restaurant use)					
Restaurant 1/50m sq for 1st 100m sq	1	100	2	0.8	
Restaurant 1/10m sq after 1st 100m sq	1	113	11	5	
Total Commercial Restaurant			**13**	**5**	0

TOTALS			**51**	**20**	**5**

Loading

Residential	Rate	Areas/ units		Required	Proposed
Residential Class B		-		1	SHARED 1
Commercial				1	SHARED 1
Passenger Loading (drop off)				1	1
Total Loading				**3**	**2**

Project is proposing to minimize the use of vehicle parking and focus on sustainable transportation. Parking Loading and Bike parking numbers are approximate. (TDM and parking stats to be verified by BUNT)

Development Data

Proposed Stats Details

	Rental Unit Area (Includes In-Suite Storage)						Rental Program Area						Social Enterprise		GFA	Exclusions				FSR	Exterior	
Level	Total Units	SRO Replacement Studios	Studios	1 Bed	2 beds	Res Rental	Residential Amenity	Admin / Support	Circulation	Service	Storage (excludes in-Suite)	Residential Total	Social Enterprise	Commercial Circulation		Amenity	In-Suite storage	* Other	Total Exclusions		Roof Terrace	Balcony
Level 19 (Amenity)	-	-	-	-	-	-	560	-	725	69	-	1,354	-	-	1,354	560			560	794	3,660	-
Level 18	8		1,505	2,406	-	3,911	-	-	983	122	-	5,016	-	-	5,016	-	265		265	4,751	-	238
Level 17	8		1,505	2,406	-	3,911	-	-	983	122	-	5,016	-	-	5,016	-	265		265	4,751	-	238
Level 16	8		1,505	2,406	-	3,911	-	-	983	122	-	5,016	-	-	5,016	-	265		265	4,751	-	238
Level 15	8		1,505	2,406	-	3,911	-	-	983	122	-	5,016	-	-	5,016	-	265		265	4,751	-	238
Level 14	7		1,055	2,398	-	3,453	450	-	983	122	-	5,008	-	-	5,008	450	225		675	4,333	738	246
Level 13	10		1,829	2,882	-	4,711	-	-	1,019	122	-	5,852	-	-	5,852	-	294		294	5,558	-	164
Level 12	10		1,829	2,882	-	4,711	-	-	1,019	122	-	5,852	-	-	5,852	-	294		294	5,558	-	164
Level 11	10		1,829	2,882	-	4,711	-	-	1,019	122	-	5,852	-	-	5,852	-	294		294	5,558	-	164
Level 10	10	345	1,484	2,882	-	4,711	-	-	1,019	122	-	5,852	-	-	5,852	-	294		294	5,558	-	164
Level 09	10	1,829		2,882	-	4,711	-	-	1,019	122	-	5,852	-	-	5,852	-	294		294	5,558	-	164
Level 08	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 07	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 06	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 05	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 04	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 03	10	1,847		2,861	-	4,708	-	-	1,022	122	-	5,852	-	-	5,852	-	324		324	5,528	-	163
Level 02	8		1,430	2,346	-	3,776	1,064	-	1,018	122	-	5,980	-	-	5,980	1,064	291		1,355	4,625	1,725	642
Mez Level	-	-	-	-	-	-	345	-	1,412	122		1,879	-	-	1,879	345			345	1,534		
Level 01	-	-	-	-	-	-		353	1,146	309		1,808	2,289	-	4,097	-			-	4,097		
Total	**157**	**13,256**	**15,476**	**45,944**	**-**	**74,676**	**2,419**	**353**	**20,443**	**2,574**	**-**	**100,465**	**2,289**	**-**	**102,754**	**2,419**	**4,990**	**-**	**7,409**	**95,345**	**6,123**	**3,638**
Total (sq m)		**1,232**	**1,438**	**4,268**	**-**	**6,938**	**225**	**33**	**1,899**	**239**	**-**	**9,334**	**213**	**-**	**9,546**	**225**	**464**	**-**	**688**	**8,858**	**569**	**338**

74.33%

FSR: 10.37

Parking and Below Grade Areas

		Amenity	Support	Circulation	Service	Storage (Includes Bike Storage)		Parking	Loading	Total Area					
Mez Parking	* Site Grade changes - assumed unfinished/ unheated spaces at laneway grade				929	538		2,540		4,007	-		4,007		-
Level 1 BOH	* Site Grade changes - assumed below grade spaces based on grade changes			1,465	1,483	2,038		-	-	4,986	-		4,986		-
Total (sq ft)	**-**	**-**	**-**	**1,465**	**2,412**	**2,576**		**2,540**	**-**	**8,993**	**-**	**-**	**8,993**		**-**
Total (sq m)		**-**	**-**	**136**	**224**	**239**		**236**	**-**	**835**	**-**	**-**	**835**		**-**

PROMERITA westbank BC HOUSING ZGF

Proposed Social %

	Units
East 1	382
East 2	385
Total	767

	Target	Proposed East 3
20% E1 + E2	153.4	121
Replacement SRA		36
	153.4	157

Proposed Unit Mix - Breakdown


Level	Total	SRA Rep	Studio	1 beds	1 Bed Acc	Rental SF
(Amenity)Level 19						
Level 18	8		4	3	1	3911
Level 17	8		4	3	1	3911
Level 16	8		4	3	1	3911
Level 15	8		4	3	1	3911
(Amenity) Level 14	7		3	3	1	3453
Level 13	10		5	4	1	4711
Level 12	10		5	4	1	4711
Level 11	10		5	4	1	4711
Level 10	10	1	4	4	1	4711
Level 09	10	5	0	4	1	4711
Level 08	10	5	0	5		4708
Level 07	10	5	0	5		4708
Level 06	10	5	0	5		4708
Level 05	10	5	0	5		4708
Level 04	10	5	0	5		4708
Level 03	10	5	0	5		4708
(Amenity) Level 02	8		4	4		3776
Level 01	0					0

** All units to be designed to meet 3.8.5 - ADAPTABLE DWELLING REQUIREMENTS*

Proposed Unit Mix Summary


	Total	SRA Rep	Studio	1 Bed	Acc 1 Bed	2 Bed
Avg Unit SF *(Gross)*	476	375	375	595		
Net Rent - Shelter	33.33%	$375	$375	$375	-	-
Net Rent - HILS	33.33%	$850	$1,000	$1,150	-	-
Net Rent - LEM	33.33%	$1,150	$1,250	$1,550	-	-
Unit Count	157	36	42	69	10	0
Percentage of Units	100.00%	22.93%	26.75%	43.95%	6.37%	0.00%
Family Units %		-	-	-	-	0.00%

Site Survey




PROMERITA westbank BC HOUSING ZGF

Building Grades Survey




Context Site Plan




PROMERITA westbank BC HOUSING ZGF


Site Plan


HASTINGS STREET
RESIDENTIAL ENTRY
CRU ENTRY
CRU ENTRY
PROPERTY LINE
PROPERTY LINE
PROPERTY LINE
TERRACE - LEVEL 14
51.13 m
167' - 9"
SENIORS SOCIAL HOUSING
OVER RUN
70.74 m
232' - 1"
ROOF LEVEL
65.10 m
213' - 7"
TERRACE - LEVEL 2
17.60 m
57' - 9"
1190 EXISTING BUILDING
3 STORY
EXISTING LIGHT WELL
LANE ENTRY TO PARKING
PROPERTY LINE
EXISTING POWER POLE
EXISTING POWER POLE
EXISTING POWER POLE
N
0
500
1000
2500
5000

Streetscape Elevations




North Elevation - Laneway



North Elevation - Future Context Assumptions

PROMERITA westbank BC HOUSING ZGF

Streetscape Elevations




West Elevation - Glen Drive


West Elevation - Future Context Assumptions

Site Key

Streetscape Elevations



South Elevation - Laneway



South Elevation - Future Context Assumptions

Site Key

PROMERITA westbank BC HOUSING ZGF

Shadow Study

No parks are shaded with proposed building heights.


Spring Equinox




10.00 AM



12.00 PM



2.00 PM



4.00 PM


Summer Solstice




10.00 AM



12.00 PM



2.00 PM



4.00 PM


Autumn Equinox




10.00 AM



12.00 PM



2.00 PM



4.00 PM

Floor Plans

Level 1




Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

PROMERITA westbank BC HOUSING ZGF

Floor Plans

Mezzanine




Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

Floor Plans

Level 2




Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

PROMERITA westbank BC HOUSING ZGF

Floor Plans

Level 3-8



Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

Floor Plans

Level 9-13



Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

PROMERITA westbank BC HOUSING ZGF

Floor Plans

Level 14




Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

Floor Plans

Level 15-18




Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

Floor Plans

Roof





Key

- Storage
- Service
- Circulation
- Parking
- Social Office
- Social Enterprise
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

Section East/West

Site Key






Key

- Social Enterprise
- Bike Storage
- Parking
- Service
- Circulation
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed

PROMERITA westbank BC HOUSING ZGF

Section North/South

Site Key







Key

- Social Enterprise
- Bike Storage
- Parking
- Service
- Circulation
- Outdoor Amenity
- Indoor Amenity
- Residential Studio
- Residential 1 bed


Elevations

Site Key





North Elevation: Hastings Street



East Elevation: Vernon Drive

Legend - Materials

1. Masonry - Light Grey
2. Metal Panel - Copper
3. Glazing

PROMERITA westbank BC HOUSING ZGF

Elevations

Site Key




Legend - Materials

1	Masonry - Light Grey
2	Metal Panel - Copper
3	Glazing




South Elevation: Lane



West Elevation

Opportunity for temporary public art on blank walls at zero lot lines walls


Materials



Cladding



Juliet Balconies



Openings & Inset Balconies



Window Openings

PROMERITA westbank BC HOUSING ZGF